

**CHESAPEAKE BAY TMDL PROJECT
(4 PONDS)**

CONSTRUCTION OF THE PLANS TITLED

- 1. GREENWAY POND RETROFIT**
- 2. FOXRIDGE POND RETROFIT**
- 3. KOHL'S POND RETROFIT**
- 4. STRATFORD POND RETROFIT**

**BIDDING DOCUMENTS
SUPPLEMENTAL SPECIFICATIONS**

**TOWN OF LEESBURG
25 WEST MARKET STREET
LEESBURG, VIRGINIA 20176**

October 6, 2016

**IFB No. 15304-FY17-15
SLAF Project No.:14-11**

NOTICE OF ADDENDA: Any addenda to this BID will be posted on the Town's bid board and eVA and will only be emailed to those firms who have registered on the Bid Board. It is the firm's responsibility to provide a correct email address for the bid board, and to be aware of any addenda.

TABLE OF CONTENTS

ADVERTISEMENT FOR BID	6
BID FORM.....	7-12
BID BOND.....	13-14
Sample Agreement	15-20
Payment Bond.....	21-22
Performance Bond.....	23-24
INSTRUCTIONS TO BIDDERS	25-51
Comment Concerning Specifications (VPPA 2.2-4316).....	25
Required Contractor Qualifications	25-26
Incomplete Documents.....	26
Town of Leesburg Business Professional and Occupation License (BPOL)	26
Form and Style of Bids.....	26-27
Bid Bond.....	27
Submission of Bids.....	27
Modification/Withdrawal of Bid.....	27-28
Consideration of Bids.....	28
Award	28
Negotiation with the Lowest Bidder	28-29
Protest	29
Acceptance of Bid (VPPA 2.23-4377).....	29
SCC Identification Number (VPPA 2.2-4311.2.B)	29
Virginia Contractor’s License Number (Code of Virginia §54.1-1115, A1 and A6).....	29
Stipulated Prices	30
Coordination with Utilities.....	30
Trees	30
Contract Time.....	30
Special Contract Items of Work Provisions.....	31-32
Kohl’s Pond Maintenance	33
Maintenance of Traffic	34
TREE PROTECTION SPECIFICATIONS.....	35-38
Site Clearing, Demolition.....	35-36
Pruning Specifications.....	36-37
Construction Specifications	37-38
LANDSCAPING.....	39-50
PURPLE MARTIN BOXES AND BAT HOUSES.....	51

GENERAL CONDITIONS.....	52-136
ARTICLE 1: Contract Documents.....	53-56
1.1 Definitions.....	53-54
1.2 Execution, Correlation and Intent.....	54-56
1.3 Ownership and Use of Documents.....	56
ARTICLE 2: Owner's Project Manager.....	57
2.1 Definitions.....	57
2.2 Services of the Owner's Project Manager.....	57
ARTICLE 3: Owner.....	58-61
3.1 Definitions.....	58
3.2 Information, Services and Rights of the Owner.....	58-59
3.3 Owner's Right to Stop or to Suspend Work.....	59-60
3.4 Owner's Right to Carry Out the Work.....	60-61
3.5 Examination of Records.....	61
ARTICLE 4: Contractor.....	62-86
4.1 Definition.....	62
4.2 Review of Contract Documents.....	62
4.3 Supervision and Construction Procedures.....	62-63
4.4 Inspection of Construction.....	63
4.5 Contractor's Representations.....	64-66
4.6 Labor and Materials.....	66-71
4.7 Warranty.....	71-72
4.8 Taxes.....	72-73
4.9 Permits, Fees and Notices.....	73
4.10 Superintendent.....	73
4.11 Project Schedules.....	74-77
4.12 Responsibility for Completion.....	77-78
4.13 Documents, Other Submittals at the Site; As-Built Drawings.....	78
4.14 Shop Drawings, Product Data, Samples and Other Submittals.....	78-80
4.15 Cutting and Patching of Work.....	81
4.16 Drug Free Workplace.....	81
4.17 Non-Discrimination in Employment.....	82
4.18 Signs.....	82
4.19 Cleaning Up.....	83
4.20 Royalties and Patents.....	83
4.21 Anti-Trust.....	84
4.22 Indemnification.....	84-85
4.23 Persons Authorized to Sign Documents.....	85
4.24 Asbestos.....	85-86
4.25 Right to Publish.....	86
4.26 Materials and Equipment List.....	86

ARTICLE 5: Subcontractors.....	87-89
5.1 Definitions.....	87
5.2 Award of Subcontracts and Other Contracts for Portions of the Work.....	87-88
5.3 Subcontractual Relations.....	88
5.4 Qualification Submittals.....	88-89
ARTICLE 6: Work By Owner or By Separate Contractors.....	90-91
6.1 Owner's Right to Perform Work and to Award Separate Contracts.....	90
6.2 Mutual Responsibility.....	90
6.3 Owner's Right to Perform Disputed Work.....	91
6.4 Coordination of the Work.....	91
ARTICLE 7: Miscellaneous Provisions.....	92-95
7.1 Governing Law.....	92
7.2 Successors and Assigns.....	92
7.3 Claims for Damages.....	93
7.4 Disputes.....	93
7.5 Tests.....	94-95
7.6 Unenforceability of Any Provision.....	95
7.7 Availability of Lands.....	95
7.8 Nonexclusivity of Remedies.....	95
ARTICLE 8: Time.....	96-100
8.1 Definitions.....	96
8.2 Progress and Completion.....	97
8.3 Delays and Extensions of Time.....	97-100
ARTICLE 9: Payments and Completion.....	101-110
9.1 Contract Price.....	101
9.2 Schedule of Values.....	101
9.3 Applications for Payment.....	102-104
9.4 Certificates for Payment.....	104
9.5 Progress Payments.....	104-106
9.6 Payments Withheld.....	106-107
9.7 Substantial Completion.....	107-108
9.8 Final Completion and Final Payment.....	108-110
9.9 Partial Occupancy or Use.....	110
ARTICLE 10: Protection of Persons and Property.....	111-114
10.1 Safety Precautions and Programs.....	111
10.2 Safety of Persons and Property.....	111-114
10.3 Emergencies.....	114

ARTICLE 11: Bonds and Insurance	115-119
11.1 Bonds.....	115
11.2 Contractor's Liability Insurance	116-118
11.3 Waivers of Subrogation.....	119
11.4 Additional Insurance Provisions.....	119
 ARTICLE 12: Changes in the Work.....	 120-128
12.1 Changes in the Work	120
12.2 Field Order.....	120
12.3 Request for Proposal	120-121
12.4 Proposed Change Order.....	121
12.5 Change Order	122-124
12.6 Unilateral Change Order.....	124
12.7 Decreases and Work Not Performed	124-125
12.8 Changes in Line and Grade	125-126
12.9 Differing Site Conditions	126
12.10 Claims for Additional Cost and/or Time.....	127
12.11 Attorneys' Fees and Other Expenses	127-128
 ARTICLE 13: Uncovering and Correction of Work.....	 129-130
13.1 Uncovering of Work.....	129
13.2 Correction of Work	129-130
13.3 Acceptance of Defective or Non-Conforming Work	130
 ARTICLE 14: Termination of the Contract.....	 131-136
14.1 Termination for the Convenience of the Owner.....	131
14.2 Allowable Convenience Termination Costs.....	131-132
14.3 Default Termination	133-134
14.4 General Termination Provisions.....	134-136

END OF TABLE OF CONTENTS

**TOWN OF LEESBURG
ADVERTISEMENT FOR BID**

**CHESAPEAKE BAY TMDL PROJECT
(4 PONDS)
IFB No. 15304-FY17-15
SLAF Project No.:14-11**

SEALED BIDS to construct the above project WILL BE RECEIVED by Mr. Thomas H. Brandon, Manager, Office of Capital Projects for the Town of Leesburg, either by mail or hand delivered to the First Floor Lobby Receptionist, 25 West Market Street, Leesburg, VA 20176, **UNTIL BUT NO LATER THAN 3:30 p.m., Thursday, October 27, 2016.** Bids shall be marked “Sealed Bid for **Chesapeake Bay TMDL Project (4 Ponds)** Bid Date –Thursday, October 27, 2016 – 3:30 P.M.” Bids will be opened and read aloud at 25 West Market Street, Lower Level Conference Room 2, at that date and time.

All questions regarding this bid must be received in writing by email at CapitalBidQuestions@leesburgva.gov or by fax at 703-737-7065 until but no later than 5:00 p.m. on Thursday, October 20, 2016.

The project includes construction survey, erosion & sedimentation controls, excavation, embankment, storm sewer, miscellaneous site work, specialized plantings, and all incidentals related thereto for the retrofit of four (4) existing ponds (Greenway, Foxridge, Kohl’s and Stratford Ponds).

The Town reserves the right to perform all, part, or none of the work.

Bid Documents are available for download from the Town’s Bid Board at <http://www.leesburgva.gov/bidboard> and may be obtained beginning Thursday, October 6, 2016. Contact Cindy Steyer at 703-737-2302 or csteyer@leesburgva.gov with questions about obtaining these bid documents. **All addenda issued for this project will only be posted on the Town’s Bid Board and eVA (<https://eva.virginia.gov>).**

Thomas H. Brandon, Manager
Office of Capital Projects

**TOWN OF LEESBURG, VIRGINIA
OFFICE OF CAPITAL PROJECTS
25 WEST MARKET STREET
LEESBURG, VIRGINIA 20176
IFB No. 15304-FY17-15**

**BID FORM, PAGE 7 THRU 12
SUBMIT A SIGNED BID FORM BY MAIL OR IN PERSON TO
THOMAS H. BRANDON, MANAGER
OFFICE OF CAPITAL PROJECTS**

FORMAL BIDS WILL BE DUE NO LATER THAN
3:30 P.M., THURSDAY, OCTOBER 27, 2016

CONSTRUCTION OF THE PLANS TITLED
1. GREENWAY POND RETROFIT
2. FOXRIDGE POND RETROFIT
3. KOHL'S POND RETROFIT
4. STRATFORD POND RETROFIT

THE UNDERSIGNED CERTIFIES THAT (CONTRACTOR NAME):

AGREES TO FURNISH ALL NECESSARY LABOR, EQUIPMENT, MATERIALS, AND ALL THINGS NECESSARY TO PERFORM THE WORK AS SET FORTH IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS AT THE FOLLOWING PRICES: (ALL PRICES INCLUDE PROVISION AND INSTALLATION).

STIPULATED PRICE ITEMS: THE CONTRACTOR AGREES TO PERFORM RELATED WORK FOR THE FOLLOWING ITEMS AT THE STIPULATED PRICES SHOWN. USE OF THESE ITEMS WILL BE THE SOLE DISCRETION OF THE ENGINEER.

<u>ITEM</u>	<u>UNIT</u>	<u>UNIT PRICE</u>
ROCK EXCAVATION	C.Y.	\$50.00
CRUSHER RUN VDOT #25 OR APPROVED EQUAL	C.Y.	\$35.00

ROCK IS DEFINED AS ANY SOLID MATERIAL OR BOULDERS THAT CANNOT BE REMOVED FROM THE GROUND BY EXCAVATION EQUIPMENT WITHOUT THE USE OF A HOE RAM OR BLASTING METHODS.

<u>SUBMITTED BY:</u>	
VENDOR NAME:	
ADDRESS:	
CITY/STATE/ZIP:	
AUTHORIZED SIGNATURE:	
PRINT NAME AND TITLE:	
TELEPHONE NO:	FACSIMILE NO.:
STATE CORPORATION COMMISSION ID #	CONTRACTOR VA LICENSE #
TAX ID NUMBER (FIN/SSN):	
THIS FIRM IS A: (INSERT NAME OF STATE): _____	
<input type="checkbox"/> CORPORATION <input type="checkbox"/> GENERAL PARTNERSHIP <input type="checkbox"/> LTD LIABILITY COMPANY	<input type="checkbox"/> LIMITED PARTNERSHIP <input type="checkbox"/> UNINCORPORATED ASSOC. <input type="checkbox"/> SOLE PROPRIETORSHIP
E-MAIL ADDRESS:	LEESBURG BPOL #:

ADDENDA

Bidder acknowledges receipt of the following ADDENDA, which have been considered in the preparation of this bid.

Addendum No. _____
 Addendum No. _____
 Addendum No. _____
 Addendum No. _____
 Addendum No. _____

Dated: _____
 Dated: _____
 Dated: _____
 Dated: _____
 Dated: _____

BID FORM

Ref.	DESCRIPTION	Unit	Qty.	Lump sum Price
A	Foxridge Pond Retrofit, per plans and specifications	LS	1	
B	Greenway Pond Retrofit, per plans and specifications	LS	1	
C	Kohl's Pond Retrofit, per plans and specifications	LS	1	
D	Stratford Pond Retrofit, per plans and specifications	LS	1	
<i>TOTAL Lump Sum Amount (A+B+C+D)</i>				

Lump sum amount in words:

The contractor shall use the form below to provide unit rates to be used in any change in scope (\pm addition or omission)

Ref.	DESCRIPTION	Unit	Qty.	Unit Price
1	\pm Allaying dust using water truck	DY	3	
2	\pm Curb protection, Complete in Place Incl. Maintenance & Removal (see plans for details)	EA	3	
3	\pm Silt Fence Complete in Place Incl. Maintenance & Removal	LF	300	
4	\pm Safety Fence Complete in Place Incl. Maintenance & Removal	LF	300	
5	\pm Tree Protection Complete in Place Incl. Maintenance & Removal	LF	300	
6	\pm Check Dam Complete in Place Incl. Maintenance & Removal	EA	3	
7	\pm Outlet Protection Complete in Place Incl. Maintenance & Removal	EA	3	
8	\pm Culvert Inlet Protection, Complete in Place Incl. Maintenance & Removal	EA	3	
9	\pm Removal and rearranging of rip-rap (see plans for details)	SY	300	
10	\pm Rip-rap bank protection, complete in place (see plans for details)	SY	300	
11	\pm 36" RCP Pipe, Complete in place including Excavation, Bedding & Backfill	LF	30	
12	\pm Pump around - Dewatering system with pumps as needed (see plans for details)	LF	300	
13	\pm Grading of access road	SY	300	
14	\pm Repair Asphalt Access road including VDOT 21-A stone base	SF	300	
15	\pm 5' Asphalt trail (2" SM-9.5 and 4" VDOT 21-A stone base)	LF	300	
16	\pm Regular excavation Including wetland areas	CY	300	

Unit Rates (continued)

Ref.	DESCRIPTION	Unit	Qty.	Unit Price
17	± Dredging of pond areas (1 foot)	SY	300	
18	± Rock Cross Vane Incl. Splash rocks and Reinforced Bed Mix complete in place with diversion channel (see plans for details)	EA	3	
19	± Soil Amendments: add sand, compost, topsoil or wetland mulch	CY	300	
20	± Remove and reset existing white vinyl split rail fence	LF	300	
21	± Wood chip matt, Complete in Place Incl. Maintenance & Removal	SY	300	
22	± Permanent Seeding & Mulching Incl. Lime and Fertilizer	SY	300	
23	± Purple martin box with raccoon predator guard, complete in place	EA	5	
24	± Bat House, complete in place	EA	15	

ESCROW OF RETAINED FUNDS

In accordance with Section 2.2-4334 of the Virginia Public Procurement Act (VPPA), any Contract valued at \$200,000.00 or more for construction of highways, roads, streets, bridges, parking lots, demolition, clearing, grading, excavating, paving, pile driving miscellaneous drainage structures, and the installation of water, gas, sewer lines and pumping stations where portions of the Contract price are to be retained, at the time of submitting a bid, the CONTRACTOR shall have the option to indicate preference for using the escrow account procedure for utilization of the Town retained funds by so indicating in the space provided in the proposal documents. In the event the successful Contract elects to use the escrow account procedure, the "Escrow Agreement" included in the Contract documents shall be executed and submitted to the Director, Department of Capital Projects Management within 15 days after receipt of the Notice to Award. If the "Escrow Agreement" form is not submitted, the CONTRACTOR shall forfeit his rights to the use of the escrow account procedure within the 15-day period.

In order to have retained funds paid to an escrow agent, the CONTRACTOR, the escrow agent, and the surety shall execute the "Escrow Agreement" furnished by the TOWN, and submit same to the Department of Capital Projects Management for approval. The CONTRACTOR's escrow agent shall be a trust company, approved bank or savings and loan institution with its principal office located in the Commonwealth of Virginia. The "Escrow Agreement" shall contain the complete address of the escrow agent and surety, and the executed "Escrow Agreement" will be authority for the TOWN to make payment of retained funds to the escrow agent. After approving the agreement, the TOWN will pay to the escrow agent the funds retained as provided herein, except that funds retained for lack of progress or other deficiencies on the part of the CONTRACTOR will not be paid to the escrow agent. The escrow agent may, in accordance with the stipulations contained in the "Escrow Agreement", invest the funds paid into the escrow account and pay earnings on such investments to the CONTRACTOR, or release the funds to the CONTRACTOR, provided such funds are fully secured by approved securities.

Retained funds invested, and securities held as collateral for retainage may be released only as and when directed by the Director, Department of Capital Projects Management. When the final estimate is released for payment, the Director, Department of Capital Projects Management will direct the escrow agent to settle the escrow amount by paying the CONTRACTOR or the TOWN monies due them as determined by the Director, Department of Capital Projects Management. The TOWN reserves the right to recall retained funds and to release same to the surety upon receipt of written request from the CONTRACTOR or in the event of default.

- () We elect to use the escrow account procedure for the deposit of retained funds.

- () We elect not to use the escrow account procedure for the deposit of retained funds.

END OF SECTION

BID BOND

BOND NO. _____

AMOUNT: \$ _____

KNOW ALL MEN BY THESE MEN PRESENTS, that _____ hereinafter called the PRINCIPAL, and _____ a corporation duly organized under the laws of the State of _____ having its principal place of business at _____ in the State of _____ and authorized to do business in the Commonwealth of Virginia, as SURETY, are held and firmly bound unto _____, as OWNER, hereinafter called the OBLIGEE, in the sum of _____ DOLLARS (\$ _____) for the payment for which we bind ourselves, our heirs, executors, administrators, successors, and assigns, jointly and severally, firmly by these presents.

THE CONDITION OF THIS BOND IS SUCH THAT:

WHEREAS, the PRINCIPAL is herewith submitting his or its Bid Proposal for _____ said Bid Proposal, by reference thereto, being hereby made a part hereof.

NOW THEREFORE,

- (A) If the bid shall remain open for a period of not less than 90 days following opening of the bids and be rejected, or in the alternate,
- (B) If the bid shall remain open for a period of not less than 90 days following opening of the bids and be accepted and the PRINCIPAL shall execute and deliver a Contract in the form of Contract attached hereto (properly completed in accordance with the bid) and shall furnish a performance and payment deposit or surety bond for his faithful performance of the Contract, and for the payment of all persons performing labor or furnishing materials in connection therewith,
- (C) THEN, this obligation shall be void; otherwise the same shall remain in force and effect, it being expressly understood and agreed that the liability of the SURETY for any and all claims hereunder shall, in no event, exceed the said amount of this obligation as herein stated. Provided, however, that in addition to the amount of this obligation as herein stated, the SURETY shall be liable for all costs and attorney's fees incurred by the OBLIGEE in enforcing the obligations hereunder.

The SURETY, for value received, hereby stipulates and agrees that the obligation of the

SURETY and its bond shall be in no way impaired or affected by any extension of the time within which the OWNER may accept such bid; and the SURETY does hereby waive notice of such extension.

IN WITNESS WHEREOF, the PRINCIPAL and the SURETY have hereunto set their hands and seals, and have executed this instrument and such of them as are corporations have caused their corporate seals to be hereto affixed and these presents to be signed by their proper officers, the day and year first set forth above.

Signed and sealed this _____ day of _____, 20_____ .

PRINCIPAL

By _____

SURETY

By _____
Attorney-In-Fact

IMPORTANT: The SURETY executing bonds must appear on the Treasury Department's most current list (Circular 570 as amended) and be authorized to transact business in the Commonwealth of Virginia.

END OF SECTION

SAMPLE AGREEMENT

THIS AGREEMENT, dated this _____ day of _____, 20____ is between the Town of Leesburg (hereinafter called TOWN or Owner) and _____ (hereinafter called CONTRACTOR). TOWN AND CONTRACTOR, in consideration of the mutual covenants hereinafter set forth, agree as follows:

1. **WORK**

1.1 The project’s name is _____, project # _____.

1.2 CONTRACTOR shall complete all Work as specified or indicated in the Contract Documents. The Work is generally described as follows:

The project includes construction survey, erosion & sedimentation controls, excavation, embankment, storm sewer, waterline, sanitary sewer, maintenance of traffic, curb, gutter, sidewalk, paving, miscellaneous site work, and all incidentals related thereto.

2. **OWNER’S REPRESENTATIVES**

2.1 All references to the Owner’s Chief Contracting Officer shall mean:_____.

2.2 All references to the Owner’s Project Manager shall mean:_____.

2.3 The Project is designed by_____. All references to ENGINEER within the Contract Documents mean:_____.

3. **CONTRACT TIME AND LIQUIDATED DAMAGES**

3.1.1 Time of the Essence

A. All time limits for Interim Completion, Milestones, Substantial Completion, and Final Completion as stated in the Contract Documents are of the essence of the Contract.

B. Contract Time:

- a. The Work to be performed under this Contract shall be commenced after issuance of the Notice to Proceed and Substantial Completion shall be achieved within ___ calendar days.
- b. Final Completion shall be achieved within ___ calendar days.
- c. [Insert Interim or Milestone dates as appropriate.]

3.2 Liquidated Damages

- A. TOWN and CONTRACTOR recognize that time is of the essence of this Agreement and the TOWN will suffer financial loss if the Work is not completed within the time specified in paragraph 3.1 above, plus any extensions thereof allowed in accordance with the General Conditions, Article 8, "TIME." Contractor recognizes the delays, expense, and difficulties involved in proving in a legal or other dispute resolution proceeding the actual loss suffered by TOWN if the Work is not completed on time. Accordingly, instead of requiring any such proof, TOWN and CONTRACTOR agree that as liquidated damages for delay, but not as a penalty, CONTRACTOR shall pay the TOWN as follows:
 - a. For each day that expires after the time established to achieve Substantial Completion as specified above, CONTRACTOR shall pay TOWN liquidated damages in the amount of \$_____ .
 - b. For each day that expires after the time established to achieve Final Completion as specified above, CONTRACTOR shall pay TOWN liquidated damages in the amount of \$_____ .
 - c. [Insert liquidated damage rate for and Interim or Milestone dates.]
- B. CONTRACTOR hereby waives any defense as to the validity of any liquidated damages stated in this Agreement as they may appear on the ground that such liquidated damages are void as penalties or are not reasonably related to actual damages.
- C. TOWN may recover liquidated damages by deducting the amount owed from progress payments, final payment or retainage.

4. **CONTRACT PRICE**

4.1. *[If Fixed Price]* In consideration of the Performance of the Contract, the Owner agrees to pay the Contractor as compensation for his services the firm, fixed price of: _____ Dollars and _____ Cents (\$_____).

4.2 *[If Unit Price]* In consideration of the Performance of the Contract, the Owner agrees to pay the Contractor as compensation for his services in accordance with the Bid Form and Contract Documents, which are included as Exhibits to this Agreement, an amount equal to the sum of the itemized prices as shown for each item of work multiplied by the actual quantity of each item completed:

A. Total Computed Price used for Comparison and Award:

(Words)

\$ _____
(Figures)

All specific cash allowances are included in the above price and have been computed to include the Contractors profit, overhead, all furnishing and installation charges.

This is a unit price contract and the estimated quantities are not guaranteed and are given only as a basis of calculation for comparing and awarding the project. The determinations of actual quantities and classifications are to be made by Project Manager, as provided in the General Conditions, Article 9. The Total Computed Price used for Comparison and Award will be deemed to include for all Unit Price Work an amount equal to the sum of the unit price for each separately defined item times the estimated quantity for each item as indicated on the bid form. Notwithstanding the language of this paragraph, the contract price shall not exceed \$_____ without further authorization.

5. **INTEREST**

5.1 The rate of interest charged shall be the base rate on corporate loans (prime rate) at large United States money center commercial banks as reported daily in the publication entitled The Wall Street Journal. Whenever a split prime rate is published, the lower of the two rates shall be used.

6. **CONTRACT DOCUMENTS**

- 6.1 The Contract Documents which comprise the entire Agreement between TOWN and CONTRACTOR concerning the Work are defined as follows:
- A. This Agreement (pages 1 to _____, inclusive);
 - B. Performance Bond (pages 1 to _____, inclusive);
 - C. Payment Bond (pages 1 to _____, inclusive);
 - D. Insurance Certificate (pages 1 to _____, inclusive);
 - E. Project Manual (pages 1 to _____, inclusive), including the General Conditions;
 - F. Specifications as referenced in the Project Manual.
 - G. Drawings consisting of cover sheet and sheets numbered ____ thru _____, inclusive; with each sheet bearing the following general title:

 - H. Addenda
 - I. Exhibits to this Agreement (enumerated as follow):
 - 1. Notice to Proceed
 - 2. CONTRACTOR'S Bid
 - 3. Documentation submitted to TOWN by CONTRACTOR prior to Notice of Award
 - 4. _____
 - J. Deliverables issued on or after the effective date of the Agreement and are not attached hereto:
 - 1. Written Amendments
 - 2. Work Change Directives
 - 3. Change Orders

7. **Notice**

The term "Notice" as used herein shall mean and include written notice. Any legal notice by any party shall be deemed to have been duly given if either delivered personally or enclosed in a registered, postage paid envelope addressed to:

The Owner:

The Owner's Project Manager:

The Contractor:

IN WITNESS WHEREOF, TOWN and CONTRACTOR have signed two copies of this Agreement. All portions of the Contract Documents have been signed or identified by TOWN and CONTRACTOR.

TOWN OF LEESBURG
P.O. Box 88
Leesburg, VA 20178

CONTRACTOR

By _____

By _____

Town Manager

President

Date _____

Date _____

License No: _____

[CORPORATE SEAL]

Approved as to Form:

Town Attorney

Resolution authorizing execution
of Agreement is attached hereto.

Agent for service of process:

(If CONTRACTOR is a corporation
attach evidence of authority to
sign.)

END OF SECTION

VIRGINIA PAYMENT BOND

BOND NO. _____

AMOUNT: \$ _____

KNOW ALL MEN BY THESE PRESENTS, that _____
of _____ hereinafter called the CONTRACTOR
(Principal), and _____
a corporation duly organized and existing under and by virtue of the laws of the State
of _____, hereinafter called the SURETY, and authorized to
transact business _____ within the
Commonwealth of Virginia, as SURETY, are held and firmly bound unto The Town of Leesburg
as OWNER (Obligee), in the sum of:

_____ DOLLARS (\$ _____), lawful money
of the United States of America, for the payment of which, well and truly be made to the
OWNER. The CONTRACTOR and the SURETY bind themselves and each of their heirs,
executors, administrators, successors, and assigns, jointly and severally, firmly by these presents
as follows:

THE CONDITION OF THE ABOVE OBLIGATION IS SUCH THAT:

WHEREAS, the CONTRACTOR has executed and entered into a certain Contract hereto
attached with _____, naming the OWNER as beneficiary, dated this
_____ day of _____, 20 _____,
for: _____

NOW, THEREFORE, the CONTRACTOR shall promptly make payment to all persons, firms,
subcontractors, and corporations furnishing materials for or performing labor in the prosecution
of the work provided for in the Contract, and any authorized extension or modification thereof,
including all amounts due for materials, lubricants, oil, gasoline, coal and coke, repairs on
machinery, equipment, and tools consumed or used in connection with the construction of the
work, and all insurance premiums on the work, and for all labor performed in the work, whether
by subcontractor or otherwise, then this obligation shall be void; otherwise to remain in full force
and effect.

Furthermore, the SURETY, for value received, hereby stipulates and agrees that no change,
extension of time, alteration, or addition to the terms of the Contract Documents or to the work
to be performed there under, or the Specifications accompanying the same, shall in any way

affect its obligation on this bond, and it does hereby waive notice of any such change, extension of time, alteration, or addition to the terms of the Contract Documents.

PROVIDED, FURTHER that no final settlement between the OWNER and the CONTRACTOR shall abridge the right of any beneficiary hereunder, whose claim may be unsatisfied.

IN WITNESS WHEREOF, the above parties bounded together have executed this instrument this _____ day of _____, 20____, the name and corporate seal of each corporate party being hereto affixed and those presents duly signed by its undersigned representative, pursuant to authority of its governing body.

CONTRACTOR

By _____ (Seal)

Attest

SURETY

By _____ (Seal)

Attest

NOTE: Date of bond must not be prior to date of Contract. If CONTRACTOR is a partnership, all partners should execute bond.

IMPORTANT: The SURETY named on this bond shall be one who is licensed to conduct business in the Commonwealth of Virginia, and named in the current list of Companies Holding Certificates of Authority as Acceptable Sureties on Federal Bonds and as Acceptable Reinsuring Companies, as published in Circular 570 (amended) by the Audit Staff Bureau of Accounts, U.S. Treasury Department. All bonds signed by an agent must be accompanied by a certified copy of the authority to act for the SURETY at the time of the signing of this bond.

VIRGINIA PERFORMANCE BOND

BOND NO. _____

AMOUNT: \$ _____

KNOW ALL MEN BY THESE PRESENTS, that _____

of _____

hereinafter called the CONTRACTOR (Principal), and _____

_____ a corporation duly organized and existing under and by virtue of the laws of the State of _____, hereinafter called the SURETY, and authorized to transact business _____ within the Commonwealth of Virginia, as SURETY, are held and firmly bound unto The Town of Leesburg as OWNER (Obligee), in the sum of:

_____ DOLLARS (\$ _____), lawful money of the United States of America, for the payment of which, well and truly be made to the OWNER. The CONTRACTOR and the SURETY bind themselves and each of their heirs, executors, administrators, successors, and assigns, jointly and severally, firmly by these presents as follows:

THE CONDITION OF THE ABOVE OBLIGATION IS SUCH THAT:

WHEREAS, the CONTRACTOR has executed and entered into a certain Contract hereto attached with _____, naming the OWNER as beneficiary, dated this _____ day of _____, 20 _____, for: _____

NOW, THEREFORE, the CONTRACTOR shall at all times duly, promptly, and faithfully perform the Contract and any alteration in or addition to the obligations of the CONTRACTOR arising there under, including the matter of infringement, if any, of patents or other proprietary rights, and shall assure all guarantees against defective workmanship and materials, including the guarantee period following final completion by the CONTRACTOR and final acceptance by the OWNER and comply with all covenants therein contained in the Specifications, Drawings, and other Documents constituting a part of the Contract required to be performed by the CONTRACTOR, in the manner and within the times provided in the Contract, and shall fully indemnify and save harmless the OWNER from all cost and damage which it may suffer by reason or failure so to do, and shall fully reimburse and repay it all outlay and expenses which it may incur in making good any default, and reasonable counsel fees incurred in the prosecution of

or defense of any action arising out of or in connection with any such default, then this obligation shall be void; otherwise to remain in full force and effect.

Furthermore, the SURETY, for value received, hereby stipulates and agrees that no change, extension of time, alteration, or addition to the terms of the Contract Documents or to the work to be performed there under, shall in any way affect its obligation on this bond, and it does hereby waive notice of any such change, extension of time, alteration, or addition to the terms of the Contract Documents.

PROVIDED, FURTHER that no final settlement between the OWNER and the CONTRACTOR shall abridge the right of any beneficiary hereunder, whose claim may be unsatisfied.

IN WITNESS WHEREOF, the above parties bounded together have executed this instrument this _____ day of _____, 20____, the name and corporate seal of each corporate party being hereto affixed and those presents duly signed by its undersigned representative, pursuant to authority of its governing body.

CONTRACTOR

By _____(Seal)

Attest

SURETY

By _____(Seal)

Attest

NOTE: Date of bond must not be prior to date of Contract. If CONTRACTOR is a partnership, all partners should execute bond.

IMPORTANT: The SURETY named on this bond shall be one who is licensed to conduct business in the Commonwealth of Virginia, and named in the current list of Companies Holding Certificates of Authority as Acceptable Sureties on Federal Bonds and as Acceptable Reinsuring Companies, as published in Circular 570 (amended) by the Audit Staff Bureau of Accounts, U.S. Treasury Department. All bonds signed by an agent must be accompanied by a certified copy of the authority to act for the SURETY at the time of the signing of this bond.

INSTRUCTIONS TO BIDDERS

COMMENTS CONCERNING SPECIFICATIONS (VPPA 2.2-4316)

General and Technical questions relating to this solicitation shall be submitted in writing to Tom Brandon, Manager, Office of Capital Projects, either by fax at 703-737-7065 or by email at CapitalBidQuestions@leesburgva.gov. Please put the title of this IFB in the subject line of the email.

If any questions or responses require revisions to the solicitation as originally published, such revisions will be by formal addendum only. Bidders are cautioned that any written or oral representations made by any Town representative or other person that appear to change materially any portion of the solicitation shall not be relied upon unless subsequently ratified by a written addendum to this solicitation issued by the Office of Capital Projects. For determination as to whether an oral or written representation of any Town representative or other person requires that an addendum be issued, contact the Manager, Office of Capital Projects in writing at fax number 703-737-7065.

REQUIRED CONTRACTOR QUALIFICATIONS

This project requires specialized knowledge and expertise. The contractor must submit written information demonstrating experience by having completed a minimum of five (5) similar projects within the last five (5) years and commit to the availability of key, skilled personnel necessary to complete the entire scope of work required for the project. Submittals that do not comply with this criterion will be considered.

The project descriptions include the following minimum information:

1. Reference clients (5 current or former clients) for whom similar projects have been completed in the last 5 years, including names, titles, addresses, phone numbers, and email addresses for contact persons.
2. Project descriptions (5 similar projects, maximum of three (3) pages per project including photos) indicating client, project scope and objectives, location, time frame, and description of technical approaches and/or technologies applied in the pond retrofit efforts.
3. Documentation that the full-time on-site project Superintendent and/or Foreman has sufficient training and successful experience implementing at least 5 stormwater management projects with the following ecological restoration and stabilization practices:
 - a. Successful installation of native riparian vegetation for constructed wetlands, including temporary erosion control grasses, permanent deep-rooted native grasses, wetland plants, on-site transplants, bare-root seedlings, and container plants.
 - b. High-accuracy installation of stormwater collection and treatment ponds,

conveyances, outfall pipes, floodplain wet lands and vegetative swales for capturing, treating, and discharging concentrated polluted stormwater in a pond setting that contributes to overall system health and integrity.

c. Successful erosion and sedimentation control measures during pond retrofit project construction including pump-around, flow diversion, sediment fence, temporary check dams, and other turbidity reduction measures.

Qualifications shall be submitted by contractors with the Bid Response. Only bids of contractors that successfully demonstrate the experience required above will be considered for the project.

INCOMPLETE DOCUMENTS

The Contractor, as a bidder, is responsible for having determined the accuracy and completeness of bid documents upon which it relied in making its bid, and having notified the Manager, Office of Capital Projects immediately upon discovery of an apparent inaccuracy, error in, or omission of any pages, drawings, sections, or addenda whose omission from the documents was apparent from a reference or page numbering in the bidding documents.

If the Contractor proceeds with any activity that may be affected by an inaccuracy, error in, or omission described above, of which it has not notified the Manager, Office of Capital Projects, the Contractor hereby agrees to perform any work described in such missing or incomplete documents at no additional cost to the Town.

TOWN OF LEESBURG BUSINESS PROFESSIONAL AND OCCUPATION LICENSE (BPOL)

The successful bidder must comply with the provisions of Section 17-163 (License requirement) of the Town of Leesburg Code, if applicable. For information on the provisions of this chapter and its applicability to this Contract, contact the Town of Leesburg Staff Accountant, Finance Department, Town of Leesburg, Virginia, Telephone Number 703-771-6503.

FORM AND STYLE OF BIDS

The Bids shall be submitted on forms identical to the Bid Form included with the Bidding Documents, and all blanks on the Bid Form shall be filled in by a typewriter or manually in ink. Where so indicated by the makeup of the Bid Form, sums shall be expressed in both words and figures, and in case of discrepancy between the two, the amount written in words shall govern. Any interlineations, alterations, and erasures must be initialed by the signer of the Bid.

Each copy of the Bid shall include the legal name of the Bidder and a statement that the Bidder is a sole proprietor, partnership, corporation, or other legal entity. Each copy shall be signed by the person or persons legally authorized to bind the Bidder to a contract. A Bid by a corporation shall further give the state of incorporation and have the corporate seal affixed. All names shall be typed or printed in ink below the signatures. The address and phone number for communication regarding the bid shall be shown. Email address may be included at bidder's option.

The Bid shall contain evidence of the Bidder's authority to do business in the Commonwealth of

Virginia. Bidder's Virginia State contractor license number shall also be shown on the Bid form.

BID BOND

Each bid shall be accompanied by a bid security (on enclosed form or cashier's check), in the amount of five percent (5%) of the bidder's maximum Bid price, pledging that the Bidder will enter into a Contract with the TOWN on the terms stated in the Bid. Should the Bidder refuse to enter into such Contract the amount of the bid security shall be forfeited to the TOWN as liquidated damages, not as a penalty.

The TOWN will have the right to retain the bid security of Bidders to whom an award is being considered until either (a) the Contract has been executed or (b) the specified time has elapsed so that Bids may be withdrawn, or (c) all Bids have been rejected.

SUBMISSION OF BIDS

Each prospective Bidder is furnished one copy of the Bidding Documents with one separate unbound copy each of the Bid Form and the Bid Bond. The unbound copy of the Bid Form is to be completed and submitted with the Bid security.

All copies of the Bid, the bid security, and other documents required to be submitted with the Bid shall be enclosed in a sealed opaque envelope. The envelope is to be addressed to the party receiving the Bids and is to be identified with the Project name, the Bidder's name and address, contractor's Virginia License number, and if applicable, the designated portion of the Work for which the Bid is submitted. If the Bid is sent by mail, the sealed envelope is to be enclosed in a separate mailing envelope with the notation "SEALED BID ENCLOSED" on the face thereof.

The Town of Leesburg will accept bids at the designated location prior to the time and date of the receipt of Bids. Bids received after the time and date for receipt of Bids will be returned unopened. The official time will be deemed to be that of the accepting agency.

The Bidder shall assume full responsibility for timely delivery at the location designated for receipt of Bids. Verbal, telephonic, or telegraphic Bids are invalid, and will not receive consideration.

MODIFICATION/WITHDRAWAL OF BID

A Bid may not be modified, withdrawn, or cancelled by the Bidder during the stipulated time period following the time and date designated for the receipt of Bids, and each Bidder so agrees in submitting a Bid.

Prior to the time and date designated for receipt of Bids, a Bid submitted may be modified or withdrawn by notice to the party receiving Bids at the place designated for receipt of Bids. Such a notice shall be in writing over the signature of the Bidder or by telegram; if by telegram, written confirmation over the signature of the Bidder shall be mailed and postmarked on or before the date and time set for receipt of Bids. A change shall be so worded as not to reveal the amount of the

original Bid.

Withdrawn Bids may be resubmitted up to the date and time designated for the receipt of Bids, provided that they are then fully in conformance with these Instructions to Bidders.

Bid security, if required, shall be in an amount sufficient for the Bid as modified or resubmitted.

CONSIDERATION OF BIDS

The TOWN shall have the right to reject any or all Bids, reject a Bid not accompanied by a required bid security or by other data required by the Bidding Documents, or reject a Bid, which is in any way incomplete or irregular.

After the bids are opened and publicly read aloud, the town will recalculate the arithmetic of all bids. The recalculation will consist of the following:

1. The Extended Price will be the Quantity x Unit Price. The accuracy of this calculation will be verified for all unit price items of work. All mathematical errors will be corrected to arrive at the correct extended price. If no price is shown for the Unit Price, it is assumed to be zero.
2. The sum of all extensions will be calculated and any mathematical errors will be corrected.
3. If there are multiple sections to the bid, for example the Total Base Bid = Section 'A' + 'B', the sum of the sections will be calculated. All mathematical errors will be corrected.

The corrected price and correct sum thereof will be used to determine the lowest responsive, responsible bidder and will become the value of the recommended contract award.

AWARD

It is the intent of the TOWN to award a Contract to the lowest responsive and responsible Bidder, provided the low bid does not exceed the funds available. The TOWN shall have the right to waive informalities in a Bid received and to accept the Bid, which, in its judgment, is in the TOWN's best interest. The Notice of Intent to Award a contract resulting from the solicitations for bids and exceeding \$100,000 will be posted on the Public Notice Board at 25 W. Market Street, Leesburg, VA in the form of a Town Council Agenda item. Notices for contracts less than \$100,000 will be posted at the same location in the form of a separate public notice item.

NEGOTIATIONS WITH THE LOWEST BIDDER

Unless all bids are cancelled or rejected, the Town reserves the right granted by 2.2-4318 of the *Code of Virginia* to negotiate with the lowest responsive, responsible bidder to obtain a contract price within the funds available. Funds available shall mean those funds, which were budgeted for this contract prior to the issuance of the written Invitation for Bids. Negotiations with the low

bidder may include both modifications of the bid price and the Scope of Work/Specifications to be performed. The Town shall initiate such negotiations by written notice to the lowest responsive, responsible bidder that its bid exceeds the available funds and the Town wishes to negotiate a lower contract price. The times, places, and manner of negotiating shall be agreed to by the Town and the lowest responsive, responsible bidder.

PROTEST

Any bidder or offeror who desires to protest the award or decision to award a contract shall submit such protest in writing to the TOWN, no later than 10 days after public notice of award or the announcement of the decision to award, whichever occurs first, pursuant to section 2.2-4360 of the VPPA.

ACCEPTANCE OF BID (VPPA 2.2-4337)

The bids received shall be open to acceptance and is irrevocable for **sixty (60) days** from the Bid Closing date.

If the bid is accepted by the Town within the period specified above, the Contractor shall provide a certificate of insurance, Payment bond, and Performance Bond within 10 days of the Notice of Award. Each bond, the Performance Bond and the Payment Bond, shall be in the amount of 100% of the Contract Amount. The bonds shall be corporate surety bonds issued by a surety company authorized to do business in the Commonwealth of Virginia and acceptable to the Town. The Performance Bond will be conditioned upon the faithful performance of all of the work shown, described and required in the Contract Documents. The Payment Bond will be conditioned upon the payment of all persons who have and fulfill contracts for the Contractor for providing labor, equipment of material in the performance of the work provided for in the Contract Documents.

If this bid is accepted within the time stated, and the Contractor fails to provide the required Bonds, or commence the project as directed, the security deposit shall be forfeited as damages to the Town by reason or failure, limited in amount to the lesser of the face value of the security deposit or the difference between this Bid and the Bid upon which the Contract is signed.

SCC IDENTIFICATION NUMBER (VPPA §2.2-4311.2.B)

Every Bidder must include their State Corporation Commission (SCC) Identification Number or reason for exemption with his/her bid. If this information is not included, the Bid may be rejected.

VIRGINIA CONTRACTOR'S LICENSE NUMBER (Code of Virginia §54.1-1115, A1 and A6)

Bidder certifies that he/she is properly registered as a licensed contractor under Title 54 of the Code of Virginia. Bidder shall provide his/her Virginia Contractor's License Number in the designated location on the Bid Form or the Bid may be rejected.

STIPULATED PRICES

The term “STIPULATED PRICE ITEM” means and includes an item of Work, unanticipated at the time of issuance of the solicitation for a Bid and determined to be executed, based on the actual field conditions during the progress of Work under the contract, mutually by the Engineer and the Contractor. The Unit Price for the “STIPULATED PRICE ITEM”, as identified in the “Stipulated Price Items” section of the Bid Form, is predetermined by the Town as the current reasonably workable rate for the Item inclusive of all necessary labor, equipment, materials, overhead (provision and installation), and the contractor’s profit. Work on the “STIPULATED PRICE ITEM” shall be carried out either at the written request of the Contractor followed by a written approval by the Engineer or at the written order by the ENGINEER to the Contractor. The payment for a “STIPULATED PRICE ITEM” shall be made by the Town to the Contractor at the related Unit Price specified in the ‘Stipulated Price Items’ section of the Bid Form on the same basis as the payment for any other regular Bid Item.

COORDINATION WITH UTILITIES

The Contractor shall coordinate the work of his/her forces with the utility companies during the contract to ensure the continuing progress of all work to be performed within the project area.

The Contractor shall notify “MISS UTILITY” at 1-800-552-7001, 72 hours prior to beginning construction.

It shall be the responsibility of the Contractor to notify operators who maintain underground utility lines in the area of proposed excavation or blasting at least five (5) working days prior to any construction, subsequent maintenance or repair.

The Contractor shall dig test holes over all existing utilities prior to construction to determine their exact location and shall notify the construction manager of any necessity for redesign.

TREES

In the event that a tree is injured or damaged, the Contractor should contact the Town’s inspector immediately.

CONTRACT TIME

Substantial Completion:	180 calendar days from Notice to Proceed <u>Depending on easement acquisition, Kohl’s Pond may be delayed between 30 and 60 days and a stop work will be issued if needed.</u>
Final Completion:	30 calendar days from Substantial Completion
Liquidated Damages:	Per Section 108.06(b), VDOT Specifications, current edition

SPECIAL CONTRACT ITEMS OF WORK PROVISIONS

Tree Holes in and Trees Cut Flush on Embankments: Holes left by the stump grinding work, the contractor shall fill and compact as shown on the plans. Trees that are cut flush to the embankment (smaller than 2 inches), the contractor shall treat those with appropriate herbicides to prevent new growth.

Rock Excavation:

- Mass excavation is defined as any material which cannot be dislodged by a D-8 Caterpillar bulldozer, or equivalent, equipped with hydraulically operated, single tooth power ripper without the use of hoe-ramming or blasting.
- Trench excavation is defined as any material which cannot be dislodged by a Caterpillar 330 hydraulic backhoe or equivalent.
- This item will be paid at the “STIPULATED PRICE ITEM” unit price.

Construction Survey: This item is to include all survey and layout required to build the project. The survey layout shall be based on 25’ intervals. In addition, a pre-construction survey and a final survey are required. These surveys will be used to determine the final pay quantities for the earthwork and excavation items of the contract.

As-Built Drawings: As per DCSM 10-150 requirements in PDF format. Also included in this pay item is a field survey with sufficient elevation information to ensure that the constructed wetlands are constructed per the plans.

Hydrant Meter: The contractor is required to obtain a fire hydrant meter from Town’s Utility Department to be used for withdrawing water during construction. Any illegal hookup to a fire hydrant will result in a \$1,000 fine for the first offense and a \$2,500 fine for each subsequent offense on the same job.

Private Entrances and Driveways: The Contractor shall minimize the duration of any blockage to private entrances and driveways. The affected property owner shall be notified a minimum of 24 hours in advance of such activities and the contractor shall make all private entrances and driveways accessible at the conclusion of each work day.

Utility Trenches: Haul-off excavation material shall be incidental to work items and Contractor shall include its cost in relevant pay items. The utility trenches shall be backfilled to the level of surrounding grade at the end of each work day.

Connection to Existing Structures: Connections made to existing structures shall be accomplished by means that are in accordance with the Town DCSM and VDOT specifications.

Storm Drainage: All storm drainage installed in paved areas shall be backfilled utilizing 21-A material, from the top of the bedding material used for the pipe to the sub-grade elevation. Storm drainage installed under sidewalks or grass areas shall be backfilled in accordance with the Town of Leesburg DCSM, and of VDOT specifications, whichever is most stringent. Any concrete cradles

or piers required for crossing existing sanitary or waterline are to be considered incidental.

Test Pits: Test pits as described on the plans in the General Notes or as required by MISS Utility over existing utilities, are to be considered incidental.

Topsoil: Contractor shall strip the topsoil and stockpile the required quantity for later use/re-spreading.

Temporary Stabilization: This item will be utilized only at the direction of the Loudoun County E&S field inspector or the Town of Leesburg Project Manager in order to keep the project in compliance with current regulations.

Damage to Existing Fence: In the event that a fence is damaged, the Contractor shall replace in kind at no additional cost to the Town.

Project Signs:



Burgundy: PMS 188

C: 0
M: 97
Y: 100
K: 50

R: 17
G: 6
B: 0

Gold: PMS 130

C: 0
M: 30
Y: 100
K: 0

R: 255
G: 179
B: 0

Dark Blue: PMS 2767

C: 100
M: 78
Y: 0
K: 54

R: 6
G: 16
B: 64

Project title: Pond Retrofit (for both signs)

Kohl's Pond: 1 year contract maintenance

1.1. Maintenance Inspections

To be performed 11 months after final acceptance. For site inspection, provide 48 hours' notice of inspection to the Town of Leesburg Construction Inspector. Maintenance of extended detention ponds is driven by inspections that evaluate the condition and performance of the pond, including the following:

- Monitor the embankment. Note the presence of any invasive plant species. Contractor shall remove plants within 30 days of inspection.
- Inspect the banks of upstream and downstream channels for evidence of sloughing, animal burrows, boggy areas, woody growth, or gully erosion that may undermine embankment integrity. Notify Town of Leesburg of any issues and agree upon remediation. Contractor shall perform remediation within 30 days of inspection.
- Inspect pond outfall channel for erosion, undercutting, rip-rap displacement, woody growth, etc. Notify Town of Leesburg of any issues and agree upon remediation. Contractor shall perform remediation within 30 days of inspection.
- Inspect condition of principal spillway for evidence of spalling, joint failure, leakage, corrosion, etc. Notify Town of Leesburg of any issues and agree upon remediation. Contractor to perform remediation within 30 days of inspection.
- Inspect embankment and embankment maintenance access to ensure it is free of woody vegetation, and verify that storm sewer outfall, trash rack, and low flow orifice are accessible and in good working order. Contractor shall remove any woody vegetation found within 30 days of inspection.
- Inspect internal and external side slopes of the overall pond for evidence of sparse vegetative cover, erosion, or slumping. Contractor shall make needed repairs immediately.

1.2. Ongoing Maintenance Issues

- Inspect low-flow orifice at 6 months and 11 months after final acceptance. If clogged, the Contractor shall clean it out to provide free flowing drainage within 30 days.
- Clean up the pond shoreline at 11 months after final acceptance to remove trash and floatables that accumulate on the bottom and sides of pond.

MAINTENANCE OF TRAFFIC

The Contractor shall conduct its operations in a manner that will ensure that traffic will be uninterrupted except as approved by the Town. At the close of each workday, the contractor shall make all private entrances and driveways accessible. The contractor shall make provisions to maintain a safe area for pedestrian traffic at all times during the project. No excavation shall remain open within the roadway without the approval of the Town except when the excavation can be safely bridged with the use of steel plates or other materials acceptable to the Town. When areas of excavation outside of the roadway do remain open, the area shall be barricaded and warning signs shall be posted.

At all times the Contractor shall use the personnel and traffic control signs and devices necessary to comply with Part VI of the "National Manual on Uniform Traffic Control Devices". During the progress of the work when the street may be obstructed to any extent by construction equipment or construction operations, in addition to the signs and barricades, special workers, equipped with VDOT required "STOP\SLOW" double-sided traffic control paddles, shall be designated by the Contractor to direct traffic. These workers so designated shall not be assigned to any other duties while engaged in directing traffic. The workers assigned to the flagging duties shall be VDOT-certified. The Contractor has sole responsibility for ensuring that its operations are conducted in a safe manner and notwithstanding any other provision to the contrary, shall fully indemnify the Town of Leesburg, its officers, agents and employees for any damage or injury related to traffic operations which is caused by negligent or otherwise improper or deficient performance under the Contract or nonperformance of the terms of the Contract.

1. All personnel, signs, barricades and any other items necessary for the maintenance of traffic and safety shall be provided by the Contractor. This item is to be considered incidental to all other items of work, unless specifically listed in the bid tabulation for separate payment.

2. The contractor will not be permitted to work on the following holidays:
-Annual Flower and Garden Show -Memorial Day -Independence Day
-Labor Day -Thanksgiving -Day after Thanksgiving -Christmas Day
-New Year's Day

3. Work hours on the project will be limited to 7:00 a.m. to 7:00 p.m., Monday through Friday. Weekend work will not be allowed without written permission from the Project Manager.

4. The Contractor is required to submit a Maintenance of Traffic Plan for review and approval. Approval of the Maintenance of Traffic Plan is required prior to beginning any construction activities on the project. **The Maintenance of Traffic Plan is required for the issuance of the required right-of-way permit issued by the Town of Leesburg.**

TREE PROTECTION SPECIFICATIONS

SITE CLEARING, DEMOLITION

The following work must be accomplished before any demolition or site-clearing activity occurs within 100 feet of the tree(s) to be saved.

1. The site contractor is required to meet with the Town Urban Forester at the site prior to beginning work to review all work procedures, access and haul routes, and tree protection measures.
2. The limits of all tree protection zones shall be staked in the field.
3. Tree(s) to be removed that have branches extending into the canopy of tree(s) to remain must be removed by a qualified arborist and not by demolition or construction contractors. A qualified arborist shall remove the tree in a manner that causes no damage to the tree(s) and understory to remain.
4. Any brush clearing required within the tree protection zone shall be accomplished with hand-operated equipment.
5. Trees to be removed shall be felled so as to fall away from tree protection zones and to avoid pulling and breaking of roots of trees to remain. If roots are entwined, the Town Urban Forester may require first severing the major woody root mass before extracting the trees. This may be accomplished by cutting through the roots by hand, with a vibrating knife, rock saw, narrow trencher with sharp blades, and other approved root-pruning equipment.
6. Trees to be removed from within the tree protection zone shall be removed by a qualified arborist. The trees shall be cut near ground level and the stump ground out.

Note special tree removal requirements for trees on the pond dam faces as shown on the plans.

7. All downed brush and trees shall be removed from the tree protection zone either by hand or with equipment sitting outside the tree protection zone. Extraction shall occur by lifting the material out, not by skidding it across the ground.
8. Brush shall be chipped and placed in the tree protection zone to a maximum depth of 6 inches leaving the trunk clear of mulch.
9. Structures and underground features to be removed within the tree protection zone shall use the smallest equipment possible, and operate from outside the tree protection zone. The Town Urban Forester shall be on site during all operations within the tree protection zone to monitor demolition activity.
10. All trees shall be pruned in accordance with the provided Pruning Specifications.

11. A 4-foot high, welded wire fence with steel T-posts shall be erected to enclose the tree protection zone.
12. Any damage to trees due to demolition activities shall be reported to the Town Urban Forester within 6-hours so that remedial action can be taken. Timeliness is critical to tree health.
13. If temporary haul or access roads must pass over the root area of trees to be retained, a road bed of 6 inches of mulch with ½ inch sheets of plywood on top shall be created to protect the soil. The roadbed material shall be replenished as necessary to maintain a 6-inch depth.

PRUNING SPECIFICATIONS

1. Specifications for individual trees, indicated by tree identification number, and describing which branches should be pruned and how, may be needed. Also consider requirements for crown reduction and crown raising where structures will be close to trees.
2. All trees within the project area shall be pruned to:
 - 2.1 Clear the crown of diseased, crossing, weak, and dead wood to a minimum size of 1-inch diameter;
 - 2.2 Provide 14 feet of vertical clearance over streets and 8 feet of vertical clearance over sidewalks;
 - 2.3 Remove stubs, cutting outside the wound wood tissue that has formed around the branch;
 - 2.4 Reduce end weight on heavy, horizontal branches by selectively removing small diameter branches, no greater than 2 to 3 inches, near the ends of the scaffolds.
 - 2.5 Where temporary clearance is needed for access, branches shall be tied back to hold them out of the clearance zone.
 - 2.6 Pruning shall not be performed during periods of flight of adult boring insects because fresh wounds attract pests. Pruning shall be performed only when the danger of infestation is past.
 - 2.7 A qualified arborist shall perform all pruning.
 - 2.8 All pruning shall be in accordance with the International Society of Arboriculture Tree-Pruning Guidelines and/or the ANSI A300 Pruning Standard (American National Standard for Tree Care Operations) and adhere to the most recent edition of ANSI Z133.1.
 - 2.9 Interior branches shall not be stripped out.

- 3.0 Pruning cuts larger than 4 inches in diameter, except for dead wood, shall be avoided.
- 3.1 Pruning cuts that expose heartwood shall be avoided whenever possible.
- 3.2 No more than 20 percent of live foliage shall be removed within the trees.
- 3.3. While in the tree, the arborist shall perform an aerial inspection to identify defects that require treatment. Any additional work needed shall be reported to the Town Urban Forester.
- 3.4 Brush shall be chipped and chips shall be spread underneath trees within the tree protection zone to a maximum depth of 6 inches leaving the trunk clear of mulch.

CONSTRUCTION SPECIFICATIONS

1. Fences have been erected to protect trees to be preserved. Fences define a specific protection zone for each tree or group of trees. Fences are to remain until all site work has been completed. Fences may not be relocated or removed without the written permission of the Town Urban Forester.
2. Construction trailers and traffic and storage areas must remain outside fenced areas at all times.
3. All underground utilities and drain or irrigation lines shall be routed outside the tree protection zone. If lines must traverse the protection area, they shall be tunneled or bored under the tree(s).
4. No materials, equipment, spoil, or waste or washout water may be deposited, stored, or parked within the tree protection zone (fenced area).
5. Additional tree pruning required for clearance during construction must be performed by a qualified arborist and not by construction personnel.
6. Any herbicides placed under paving materials must be safe for use around trees and labeled for that use. Any pesticides used on site must be tree-safe and not easily transported by water.
7. If injury should occur to any retained tree during construction, it shall be reported to the Town Urban Forester within 6-hours so that remedial action can be taken.
8. All trees shall be irrigated. Each irrigation event shall wet the soil within the tree protection zone to a depth of 12 inches.
9. Erosion control devices such as silt fencing, debris basins, and water diversion structures shall be installed to prevent siltation and/or erosion within the tree protection zone.

10. Before grading, pad preparation, or excavation for foundations, footings, walls, or trenching, trees shall be root pruned 1 foot outside the tree protection zone by cutting all roots cleanly to a depth of 24 inches. Roots shall be cut by manually digging a trench and cutting expose I roots with a saw, vibrating knife, rock saw, narrow trencher with sharp blades or other approved root-pruning equipment.
11. Any roots damaged during grading or construction shall be exposed to sound tissue and cut cleanly with a saw.
12. If temporary haul or access roads must pass over the root area of trees to be retained, a roadbed of 6 inches of mulch with ½ plywood over the mulch shall be created to protect the soil. The roadbed material shall be replenished as necessary to maintain a 6-inch depth.
13. Spoil from trenches, basements, or other excavations shall not be placed within the tree protection zone, either temporarily or permanently.
14. No burn piles or debris pits shall be placed within the tree protection zone. No ashes, debris, or garbage may be dumped or buried within the tree protection zone.
15. Maintain fire-safe areas around fenced areas. Also, no heat sources, flames, ignition sources, or smoking is allowed near mulch or trees.

END OF SECTION

LANDSCAPING SPECIFICATIONS

RELATED DOCUMENTS

Construction drawings and general provisions of Contract, including General and Special Conditions, Instructions to Bidders and Division 1 Specifications Sections, apply to this section.

SUMMARY

Extent of tree and wetland plantings are indicated on drawings.

Types of work required include following:

- Furnishing trees, shrubs and wetland plants.
- Preparing planting pits and beds including excavation, backfilling, and disposal of surplus and unsuitable excavated material.
- Planting trees including fertilizing, mulching, trimming, guying, and wrapping.
- Planting wetlands plants including storage, pre-planting watering & shading; seedbed preparation; planting; and post-planting water level management.
- Maintaining trees, shrubs and wetland plants.

SUBMITTALS

General: Submit the following in accordance with General Conditions Section 7, Submittals.

Product certificates of inspection, as may be required by governing authorities are to accompany shipments. For standard products, submit manufacturer's certified analysis. For other materials, submit analysis by a recognized laboratory made in accordance with methods established by Association of Official Agricultural Chemists, wherever applicable.

Planting schedule indicating anticipated dates and locations for each type of planting. **NOTE: wetlands plans must be ordered 6 months+ in advance and can only be planted early April to mid-June. Order plants from nurseries that provide common tree, shrub and plant species that are proven to do well in stormwater wetlands and that are native to the Mid-Atlantic region.**

Maintenance instructions recommending procedures to be established by Town for maintenance of wetlands plantings after acceptance.

QUALITY ASSURANCE

General: Comply with applicable federal, state, county, and local regulations governing landscape materials and work.

Employ only experienced personnel familiar with required work. Provide adequate supervision by qualified foreman.

Substitutions: If required landscape material is not obtainable, submit to town proof of non-availability and proposal for use of equivalent material. When authorized, adjustment of contract amount (if any) will be made by change order. Provide quantity, size, genus, species and variety of trees and plants indicated; comply with applicable requirements of ANSI Z60.1, "American Standard for Nursery Stock".

Locate trees and plants in compliance with requirements, and obtain Town's acceptance of their visual qualities before they are planted.

Measurements: Measure trees with branches and trunks or canes in their normal position. Do not prune to obtain required sizes. Take caliper measurements 6 inches above ground for trees up to 4 inches caliper size, and 12 inches above ground for larger sizes. Measure main body of tree for height and spread dimensions, do not measure from branch or root tip-to-tip.

Inspection: Town shall inspect trees and plants at site before planting for compliance with requirements for genus, species, variety, size and quality. Town retains right to inspect trees further for size, and condition of balls and root systems, insects, injuries, and latent defects and to reject unsatisfactory or defective material at any time during progress of work. Remove rejected trees and plants immediately from project site.

DELIVERY, STORAGE AND HANDLING

Delivery of Trees: Provide freshly dug trees to the greatest extent possible. Do not prune before delivery, except as approved by Urban Forester. Provide adequate protection of root systems, and balls from drying winds and sun. Do not bend or bind-tie trees in such a manner as to damage bark, break branches or destroy natural shape. Provide protective covering during delivery. Do not drop balled and burlapped stock during delivery.

Immediately after digging bare-root stock, pack root system in wet straw, hay, or other suitable material to keep root system moist until planting.

Deliver trees after preparations for planting have been completed and plant immediately. If planting is delayed more than 6 hours after delivery, set trees in shade (if stored on an asphalt surface, the trees must be placed on an insulating layer of wood chips no less than 6 inches deep), protect from weather and mechanical damage, and keep root moist as follows:

- Heel-in bare root stock. Soak roots in water for 2 hours if dried out.
- Set balled stock on ground and cover ball with soil, peat moss, sawdust or other acceptable material.
- Do not remove container-grown stock from containers before time of planting.

- Periodically water root system of trees stored on site with a fine mist spray. Water as often as necessary to maintain root systems in a moist condition.

Delivery of wetland plants: Coordinate plant material shipments with actual planting activities – reducing storage time at planting time reduces plant mortality. Plants that have been packaged, shipped and stored prior to planting may be stressed at time of planting. These plants are prone to desiccation and should be shaded and frequently watered while on-site.

JOB CONDITIONS

Timing: Plant trees during normal seasons for such work in location of project.

Plant frost-tender trees only after danger of frost is past (May-June) or sufficiently before frost season (October-December) to allow for establishment before first frost. Do not plant in frozen ground. Dates are subject to local conditions and authorization by Town.

Plant wetland plants between early April and mid-June.

Coordination with Lawns: Plant trees after final grades are established and before planting of lawns, unless otherwise acceptable to Town. If planting of trees occurs after lawn work, protect lawn areas and promptly repair damage to lawns resulting from planting operations.

SPECIAL PROJECT WARRANTY

Warranty trees and wetland plants, for a period of one year after date of substantial completion, against defects including unsatisfactory growth or decline from improper handling, but excepting defects resulting from neglect by Town, abuse or damage by others, or unusual phenomena or incidents beyond Contractor's control.

TREE AND SHRUB MATERIAL

General: Provide nursery grown trees, except as otherwise indicated, grown in a recognized nursery in accordance with good horticultural practice, with healthy root systems developed by transplanting or root pruning. Provide only healthy, vigorous stock free of disease, insects, eggs, larvae, and defects such as knots, sunscald, injuries, abrasions, and disfigurement.

Size: Provide trees of the sizes indicated in planting List and in accordance with dimensional relationship requirements of ANSI Z60.1 for kind and type of trees required. Trees of larger size than specified may be used if acceptable to Town; in that case, increase size of roots or balls proportionately.

Label each tree with securely attached waterproof tag bearing legible designation of botanical and common name.

Where formal arrangements or consecutive order of trees are shown, select stock for uniform height and spread, and label with number to assure symmetry in planting.

DECIDUOUS TREES

Size: Provide trees of height and caliper indicated.

Where shade trees are required, provide single-stem trees with straight trunk and intact leader as recommended by ANSI Z60.1 for size and kind of trees required.

NURSERY STOCK SPECIFICATIONS FOR SHADE TREES

In an effort to have the best available trees planted within the Town of Leesburg the following standards will apply to all trees planted within the Town limits.

Tree Health – As typical for the species/cultivar, tree shall be healthy and vigorous, as indicated by an inspection for the following:

- All plant material shall be sound, free of disease and insects, eggs or larvae.
- Crown form
- Foliage density
- Length of shoot growth
- Twig dieback
- Root appearance
- The relationship between caliper, height and root ball shall conform to the American Standard for Nursery Stock ANSI Z60.1.

Crown – Trees shall have a symmetrical form as typical for the species/cultivar and growth form.

- **Central Leader:** Trees shall have a single, relatively straight central leader and tapered trunk free of codominant stems; and vigorous, upright branches that compete with the central leader. If the original leader has been headed, a new leader at least one-half the diameter of the original leader shall be present (Figures 1—3). (Note: This section applies to single-trunk trees, as typically used for street or landscape planting. These specifications do not apply to plants that have been specifically trained in the nursery—for example, topiary, espalier, multistem, or clump, or unique selections such as contorted varieties.) Live crown ratio (distance from bottom of canopy to tree top/tree height) should be at least 60%.




Figure 1. Not topped is preferable

Figure 2. Heading back and retaining a central leader is acceptable.

Figure 3. Topping without retaining a central leader is not acceptable.

Main Branches (Scaffolds):

Branches should be distributed radially around and vertically along the trunk, forming a generally symmetrical crown typical for the species. Minimum vertical spacing may be specified.

- a. Main branches, for the most part, shall be well spaced.
- b. Branch diameter shall be no larger than two-thirds the diameter of the trunk, measured 1 inch above the branch (Figure 4).
- c. The attachment of scaffold branches shall be free of included bark (Figure 5). Branches shall diverge from the trunk at a wide angle except in cultivars that normally grow in narrow, upright forms.

Figure 4. Preferable diameter (left); unacceptable branch diameter (right)




Figure 5. Scaffold branches should be free of included bark; preferable (left); not acceptable (right)

- Temporary Branches: Temporary branches should be present along the lower trunk, particularly for trees less than 1-1/2 inches in trunk diameter. They should be no greater than 3/8 inch in diameter and no greater than one-half the diameter of the trunk at the point of attachment. Heading of temporary branches is sometimes necessary to limit their growth.

Trunk

- Trunk diameter and taper shall be sufficient so that the tree will remain vertical without

the support of a nursery stake. It shall be straight to near straight (less than a 5 degree bend).

- The trunk shall be free of wounds (except properly made pruning cuts), sunburned areas, conks (fungal fruiting-bodies), wood cracks, bleeding areas, and signs of boring insects, galls, cankers and/or lesions. Pruning cuts of limbs over ¾ inch in diameter that are not completely closed will be rejected.

Roots

- The trunk, root collar (root crown), and large roots shall be free of circling and/or kinked roots. Soil removal near the root collar may be necessary to inspect for circling and/or kinked roots. There shall be no roots greater than 1/10 diameter of the trunk circling more than one-third the way around in the top half of the root ball. Roots larger than this may be cut provided they are smaller than one-third the trunk diameter. There shall be no kinked roots greater than 1/5 the trunk diameter. Roots larger than this can be cut provided they are less than one-third the trunk diameter.
- The tree shall be well rooted in the soil mix. When the container is removed, the root ball shall remain intact. When the trunk is carefully lifted, both the trunk and root system shall move as one. The trunk should bend when gently pushed, not pivot at or below soil line.
- The point where the top-most primary root in the root ball emerges from the trunk shall be visible at the soil surface.

The above trunk and root ball specifications shall apply to evergreen and multi-stem trees as well. An additional branch specification for evergreen trees will be expressed, as the internode spacing shall not be greater than 12” apart.

Where small trees of upright or spreading type of required, provide trees with single stem, branched or pruned naturally according to species and type, and with relationship of caliper and branching recommended by ANZI Z60.1, unless otherwise indicated.

Where shown as “clump”, provide trees with 3 or more main stems starting from ground.

Provide balled and burlapped deciduous trees.

REQUIREMENTS FOR B&B STOCK

General: Where indicated to be balled and burlapped, provide trees dug with firm, natural ball of earth in which they are grown.

Provide ball size of not less than diameter and depth recommended by ANSI Z60.1 for type and size of tree required.

Wrap and tie earth ball as recommended by ANSI Z60.1 for size of balls required. Drum-lace

balls with a diameter of 30 inches or greater.

NEW TOPSOIL

Provide topsoil with a minimum pH of 6.5-7.5 that is fertile, friable, naturally loamy, surface soil; reasonably free of subsoil, clay lumps, brush, weeds, and other litter and free of roots, stumps, stones larger than 2 inches in any dimension, and other extraneous or toxic matter harmful to plant growth.

Obtain topsoil from local sources or from areas having similar soil characteristics to that found at site. Obtain topsoil from naturally well-drained sites where topsoil is at least 4 inches deep; do not obtain from bogs or marshes.

TRANSPLANT INOCULANT

Provide at time of planting a transplant supplement that contains a mycorrhizal inoculant, appropriate for the species planted, and root biostimulants.


MISCELLANEOUS MATERIALS

Mulch: Double-shredded hardwood, free from any debris or foreign matter that would be injurious to plant growth.

Anti-Desiccant: Emulsion type, film-forming agent designed to permit transpiration, but retard excessive loss of moisture from plants. Deliver in manufacturer's fully identified containers and mix in accordance with manufacturer's instructions.


Guying and staking materials: Ground anchors shall be arrowhead shaped earth anchors of malleable iron castings, aluminum castings, or stamped steel. Guying material shall be a wide fabric tape such as ArborTie[®], attached to the tree per the manufacturer's prescribed method (steps 1-4). Vertical supporting stakes shall be sound, uniform oak or cedar. They shall be a minimum of 2X2 inches in diameter, 8 feet long, and pointed at one end

Step 1




Tie a simple knot 18" - 24" (depending on diameter of tree) from either end of the tape.

Step 2




Wrap this end around tree. Begin the above knot below that was tied in Step 1.

Step 3



Follow motion of tape above, finishing the knot by pulling tightly on points A and B at the same time.

Step 4



Slide knot just completed up the knot tied in Step 1.
Fasten free end to stake or anchor.

Caution: DO NOT wrap tape around trunk, encircling trunk with tape.

Provide wood warning flaps for each guy, at least 2 inches wide by ½ inch thick by 12 inches long. Paint with luminescent white paint.

INSTALLATION OF PLANT MATERIALS

Layout individual tree locations and areas for multiple plantings. Stake locations and outline areas, and secure Town's acceptance before start of planting work. Make minor adjustments as may be requested by Town.

Excavation: Excavate pits, beds, and trenches with sloping sides and with bottom of excavation slightly raised at center to provide proper drainage.

For balled and burlapped trees, make excavations approximately 2-3 time as wide as ball diameter. Locate the top-most root and measure to the base of the root ball to determine the correct depth for excavation.

Place root ball on undisturbed subsoil at a depth equal to or slightly less than the height of the root ball. The root crown should not exceed 2 inches above finished grade.

Dispose of subsoil removed from landscape excavations. Do not mix with planting soil or use as backfill.

Obstructions: If rock, underground construction, or other obstructions are encountered in excavation for planting of trees, notify Town. New locations may be selected by Town, or change order may be issued to direct removal of obstructions at least 6 inches below required planting depth.

Drainage: If subsoil conditions indicate retention of water in planting areas, as shown by seepage or other evidence indicating presence of underground water, notify Town before backfilling. A change order may be issued to direct installation of drain tile or other measures beyond drainage requirement indicated.

PREPARATION OF PLANTING SOIL

Before mixing, clean excavated topsoil of roots, plants, sods, stones, clay lumps, and other extraneous materials harmful or toxic to plant growth.

Mix soil amendments and with topsoil at rates specified.

For pit or trench backfill, mix planting soil before backfilling and stockpile at site.

Setting and Backfilling:

Set balled and burlapped stock on undisturbed subsoil plumb and in center of pit or trench with top-most root at same elevation as adjacent finished landscape grades. Root crown should not exceed 2 inches above finished grade. Remove burlap from sides and tops of balls but do not remove from under balls. Remove pallets, if any, before setting. Remove top 1/2 of wire baskets. Do not use stock if ball is cracked or broken before or during planting operation. When set, place additional backfill around base and sides of ball, and work each layer to settle backfill and eliminate voids of air pockets. When excavation is approximately 2/3 full, water thoroughly before placing remainder of backfill. Repeat watering until no more is absorbed. Water again after placing final layer of backfill.

Dish top of backfill to allow for mulching.

Mulch pits trenches, and planted areas. Provide not less than following thickness of mulch, and work into top of backfill and finished level with adjacent finish grades. Provide 2 inches thickness of mulch. Do not mulch within 6 inches of tree trunks.

Apply anti-desiccant using power spray to provide an adequate film over trunks, branches, stems, twigs, and foliage.

If deciduous trees are moved in full-leaf, spray with anti-desiccant at nursery before moving and again in 2 weeks after planting.

Prune only dead or damage branches in accordance with standard arboricultural practice. Unless otherwise directed by Town, do not cut tree leaders, and remove only injured or dead branches from flowering trees.

Guy and stake trees immediately after planting.

Stake trees of 2 inches through 5 inches caliper. Stake trees of less than 2 inches caliper only as required to prevent wind “tip-out”. Use stakes or length required to penetrate at least 18 inches below bottom of backfilled excavation and to extend to at least 8 feet above grade. Set stakes vertical and space to avoid penetrating balls or root masses. Support trees with wide fabric tape. Allow enough slack to avoid rigid restraining of tree. Provide not less than one stake for trees 10 feet to 12 feet high and 2 inches or less in caliper, except no fewer than 2 shorter stakes may be used for low-branched trees. Use no fewer than 2 stakes for trees over 12 feet and less than 4 inches caliper size, and use no fewer than 3 stakes for trees of 4 inches to 5 inches caliper size. Space stakes equally around trees.

Guy trees of 5 inches and larger caliper located in lawn or planting areas and at least 10 feet away from pavement. Use no fewer than 3 guys for trees of 5 inches to 6 inches caliper and securely attach to stakes at least 2 inches by 4 inches by 30 inches long driven to grade. For trees over 6 inches caliper, anchor guys to deadmen 8 inches diameter and 48 inches long buried at least 36 inches below grade.

Attach wood warning flaps to each guy wire located 30 inches above finished grade.

MULCHING

Mulching is established as a cubic yard pay item. This item is to be utilized where fill is to be installed over existing exposed tree roots. The locations will be as directed by the project arborist in coordination with the Town Urban Forrester.

MAINTENANCE AND WARRANTY

General: Prune, water, cultivate, and weed during the one-year maintenance period as required for healthy growth. Restore planting saucers. Tighten and repair stake and guy supports, and reset trees and shrubs to proper grades or vertical position as required. Restore or replace

damaged wrappings. Spray as required to keep trees free of insects and disease.

Remove and replace trees found to be dead or unhealthy during the one-year warranty period. The warranty period will begin after acceptance and last for a period of 365 calendar days. Make replacements during planting season following end of warranty period. Replace trees that are in doubtful condition at end of warranty period unless, in opinion of Architect, it is advisable to extend warranty period for another growing season.

Contractor to remove all stakes and guy supports within (1) growing season.

WETLAND PLANT MATERIAL

INSTALLATION OF PLANTS

Proper water depth and its careful regulation are the most critical factors for plant survival in the first year of planting. New plants can fail because of mistaken concepts of wetland plants can survive in deep water. New plants lack the extensive root, stem and leaf systems with aerenchyma channels to transport oxygen to the roots.

After the constructed wetland cells are planted, the substrate should be saturated with water to about 1-inch for 4-5 weeks. After the 6th week, or when the submergent plants show new and vigorous growth, water levels should slowly and gradually be increased to support erect, upright growth forms. The plants should be allowed to become established before the temporary diversion for each wetland is replaced with the permanent diversion weir.

Install Zones 1, 2 and 3 plants by creating a hole with a spade or dibble, placing the plants in the hole, and firmly packing the soil around them. Plants allowed to float to the surface following installation shall result in rejection of the installation.

Install Zone 4 plants by creating a hole with a gas powered hand-held auger. Plant plugs level with existing soil grade. Be certain that soil is placed around the plugs and firmed into place. Do not fill around plugs with mulch. Thoroughly soak plugged area with water until soil is moist to a depth of 4 inches.

SEEDING IN ZONES 4 AND 5

Place a portion of the seed in a clean, dry 5 gallon bucket. Mix 2 parts potting mix with 1 part seed. Thoroughly mix seed and potting mix. Hand broadcast potting mix/seed mixture across the specified tilled area. Apply half of the mixture over the entire area. Apply the second half over the same area utilizing the same procedure. This method prevents using all of the seed before the entire area is covered. Lightly firm seedbed with a roller where soil moisture permits. Do not roll areas where soil is moist enough to stick to the roller.

Protection: Protect seeded areas with stakes and tape around area periphery.

ACCEPTANCE

Planted Wetland Communities: For acceptance at the end of the first growing season, the following condition shall be met for areas where live plants were installed.

1. 75% of the species planted shall be alive and present.
2. 50 % of the water surface in the shallow water community shall be covered with vegetation.
3. 25 % of the water surface in the floating leaf community shall be covered with vegetation.

Seeded Native Communities: For acceptance at the beginning of the second growing season (the end of the 1 year maintenance), the following conditions shall be met.

1. Coverage - 80 % of each plant community shall be covered with by vegetation.
2. Presence - 50 % of the species planted should be alive and present.
3. Abundance - 50 % of the vegetation should native species of the permanent matrix.

END OF SECTION

PURPLE MARTIN BOX AND BAT HOUSE

RELATED DOCUMENTS

Construction drawings and general provisions of Contract, including General and Special Conditions, Instructions to Bidders and Division 1 Specifications Sections, apply to this section.

SUMMARY

Provide purple martin boxes and bat houses as per the plans.

SUBMITTALS

Provide purple martin boxes with raccoon predator guard, installed and in place as determined in the field as per specifications found in at <https://www.purplemartin.org/shop/product/mss12/12-room-trio-martin-safety-system-grandpa/>. No other boxes will be accepted.

Provide small, economy bat houses, installed and in place as determined in the field, as per specifications found in http://dnr2.maryland.gov/wildlife/Pages/plants_wildlife/bats/batecon.aspx or approved equal. Submit construction specifications if using another design.

INSTALLATION

In March, the locations of the purple martin boxes and bat houses will be determined in the field. The boxes and houses are to be installed and functional by March 31st.

Recommended purple martin box height above ground is 12-18'. Poles should be securely set in concrete with 24"+ below ground.

END OF SECTION

END OF INSTRUCTIONS TO BIDDERS

THE TOWN OF LEESBURG

GENERAL CONDITIONS

Project Name:
Chesapeake Bay TMDL Project
(4 Ponds)
IFB No. : 15304-FY17-15

THE TOWN OF LEESBURG

GENERAL CONDITIONS

ARTICLE 1: CONTRACT DOCUMENTS

1.1 DEFINITIONS

1.1.1 The Contract Documents

The Contract Documents consist of the Advertisement or Invitation for Bids, Request for Proposals, Information for Bidders, Insurance Certificates, Official Bid Form, Offeror's Bid or Proposal, Bonds, the Notice of Award, the Project Manual, the Owner/Contractor Agreement, the General and Special Conditions, the Drawings, the Specifications, all Addenda issued prior to and all Modifications issued after execution of the Agreement. A Modification is either a written Change Order issued pursuant to the provisions of Article 12.5, or a Field Order issued pursuant to Article 12.2.

1.1.2 The Contract

The Contract is the sum of all the Contract Documents. This Contract represents the entire and integrated agreement between the Owner and the Contractor and supersedes all prior negotiations, representations, or agreements, either written or oral. The Contract may be changed only by a Modification as defined in Article 1.1.1.

1.1.3 The Work

The Work comprises the completed construction required by the Contract Documents and includes all labor, material, equipment, supplies and other facilities or things necessary to produce such construction, and all materials, equipment and supplies incorporated or to be incorporated in such construction.

1.1.4 The Project

The Project is the total construction of which the Work performed under the Contract Documents may be the whole or a part.

1.1.5 Furnish, Install, Provide

The terms "Furnish", "Install" or "Provide," unless specifically limited in context, mean: furnishing and incorporating a specified item, product or material in the Work, including all labor, materials, and equipment necessary to perform the Work required, ready for intended use.

1.1.6 Firm, Fixed Price or Lump Sum

The terms "Firm, Fixed Price" or "Lump Sum" mean that the Contract Work shall be performed for the price stated in the Contract without any adjustment based on

the Contractor's actual costs unless such adjustment is made by a properly executed Contract Change or Modification.

1.1.7 Schedule of Values

The term "Schedule of Values" means the unit prices for portions of the Work submitted by the Contractor and approved by the Owner's Project Manager for use in preparing Applications for Payment and pricing Contract Changes in accordance with Article 9.2. The Schedule of Values shall not alter the Firm, Fixed Price or Lump Sum value of the Contract.

1.1.8 Miscellaneous Words or Terms

Whenever they refer to the Work or its performance, "Directed," "Required," "Permitted," "Ordered," "Designated," "Prescribed," and words of like import shall imply the direction, requirements, permission, order, designation or prescription of the Owner and/or the Owner's Project Manager, and "Approved," "Acceptable," "Satisfactory," "in the judgment of," and words of like import shall mean approved by or acceptable to or satisfactory to or in the judgment of the Owner and/or the Owner's Project Manager. "Approved" means approved in writing, including subsequent written confirmation of prior oral approval and "Approval" means approval in writing, including all aforesaid.

1.2 EXECUTION, CORRELATION AND INTENT

1.2.1 The Contract Documents may be signed in duplicate originals by the Owner and the Contractor and each set shall be deemed an original, but all sets shall constitute one and the same instrument.

1.2.2 By executing the Contract, the Contractor represents that he has familiarized himself with, and assumes full responsibility for having familiarized himself with, the nature and extent of the Contract Documents, Work, locality, and with all local conditions and federal, state and local laws, ordinances, rules and regulations that may in any manner affect performance of the Work, and represents that his study and observations have been correlated with the requirements of the Contract Documents. The Contractor also represents that he has studied all surveys and investigation reports of subsurface and latent physical conditions referred to in the Contract Documents and made such additional surveys and investigations as he deems necessary for the performance of the Work at the Contract Price in accordance with the requirements of the Contract Documents and that he has correlated the results of all such data with the requirements of the Contract Documents. Failure to make an examination necessary for this determination shall not release the Contractor from the obligations of this Contract nor be grounds for any claim based upon unforeseen conditions.

The Owner assumes no responsibility for any conclusions or interpretations made by the Contractor based on the information made available by the Owner. The Owner assumes no responsibility for any understanding reached or representation made concerning conditions that can affect the Work by any of its officers or agents before the execution of this contract, unless that understanding or representation is expressly stated in this contract.

- 1.2.3** The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work. The Contract Documents are complementary, and what is required by any one shall be as binding as if required by all. Should any work or material be required which is not denoted in the drawings and specifications either directly or indirectly, but which is nevertheless necessary for the proper carrying out of the intent thereof, it is understood and agreed that the same is implied and required and that the Contractor shall perform such work and furnish such materials as fully as if they were completely delineated and prescribed.

Words and abbreviations which have well-known technical or trade meanings are used in the Contract Documents in accordance with such recognized meanings unless otherwise specifically defined herein. The Table of Articles, titles, headings, and running headlines are solely to facilitate reference to various provisions of the Contract Documents and in no way affect, limit or cast light upon the interpretation of the provisions to which they refer.

- 1.2.4** The organization of the specifications into divisions, sections and articles, and the arrangement of drawings are for clarity only, and shall not control the Contractor in dividing the Work among Subcontractors or in establishing the extent of Work to be performed by any trade. The Contractor may subcontract the Work in such divisions as he sees fit and he is ultimately responsible for furnishing all work shown on the drawings and/or in the specifications.

- 1.2.5** Unless otherwise provided for or amended herein, work shall be performed in accordance with the VDOT Road and Bridge Specifications, current edition; the Town of Leesburg Design and Construction Standards Manual (DCSM), current edition; the Virginia Erosion and Sediment Control Handbook; and the Special Provisions, Special Conditions, and Special Designs as may be described on the plans for the project or in this solicitation. Where there is a conflict between the VDOT Road and Bridge Specifications and the DCSM, the most stringent shall take precedence. A copy of the DCSM may be purchased from the Department of Plan Review at the current standard rate.

Anything shown on the drawings and not mentioned in the specifications or mentioned in the specifications and not shown on the drawings shall have the same effect as if shown or mentioned respectively in both. Technical specifications take priority over general specifications and detail drawings take

precedence over general drawings. Any work shown on one drawing shall be construed to be shown in all drawings and the Contractor will coordinate the Work and the drawings. If any portion of the Contract Documents shall be in conflict with any other portion, the various documents comprising the Contract Documents shall govern in the following order of precedence: The Owner/Contractor Agreement; Modifications; Changes; Addenda; the Supplementary Conditions; the General Conditions; the Specifications; the drawings; the Town DCSM; other published construction standards and specifications; the bonds; the advertisement for bids or invitation or request for proposal; information for bidders; bids; the notice of award. As between schedules and information given on drawings and the scaled measurements, the figures shall govern. As between large-scale drawings and small-scale drawings, the larger scale shall govern. Any such conflict or inconsistency between or in the drawings shall be submitted to the Project Manager whose decision thereon shall be final and conclusive.

1.2.6 This Contract is not intended to create, nor shall any provision be interpreted as creating, any contractual relationship between the Owner and any third parties including all Subcontractors.

1.2.7 The Provisions of this Contract cannot be changed, varied or waived in any respect except by a written Modification or Change Order. No person has authority to orally waive, or to release the Contractor from any of the Contractor's duties or obligations under or arising out of this Contract. Any waiver, approval or consent granted by Changes to the Contractor shall be limited to those matters specifically and expressly stated thereby to be waived, approved or consented to and shall not relieve the Contractor of the obligation to obtain any future waiver, approval or consent.

1.3 OWNERSHIP AND USE OF DOCUMENTS

1.3.1 All drawings, specifications, and copies thereof furnished by or to the Owner under this Contract are and shall remain the property of the Owner. They are to be used only with respect to this Project and are not to be used in whole or in part for any other purpose.

1.3.2 The Contractor shall be provided five sets of the Contract Documents by the Owner's Project Manager. Additional sets of Drawings and Specifications may be obtained from the Owner's Project Manager by paying the then current and regular printing, mailing and handling charges.

END OF ARTICLE 1

ARTICLE 2: OWNER'S PROJECT MANAGER

2.1 DEFINITIONS

2.1.1 The term "Project Manager" as used in the Contract Documents, shall mean the entity so identified in the Owner/Contractor Agreement or its duly authorized representatives.

2.1.2 The Project Manager is referred to throughout the Contract Documents as if singular in number and masculine in gender.

2.2 SERVICES OF THE OWNER'S PROJECT MANAGER

2.2.1 The Owner's Project Manager will serve during construction and until the end of the warranty period. The Owner's Project Manager will advise and consult with the Owner and will have the authority to act on behalf of the Owner only to the extent provided in the Contract Documents. The Owner may identify a substitute Owner's Project Manager at any time by providing written notice to the Contractor.

2.2.2 The Owner's Project Manager will inform the Owner and the Contractor whenever in his reasonable opinion any of the Work is proceeding contrary to the requirements of the Contract Documents and will be unacceptable. Failure of the Contractor to take corrective action to make the Work conform to the Contract Documents will subject the Contractor to any and all remedies available to the Owner, including, without limitation, termination pursuant to Article 14. Such notification by the Owner's Project Manager will not be a cause for the Contractor to claim either delay of the Work or any increase in the Contract Price.

2.2.3 The Owner, the Owner's Project Manager and other government representatives shall at all times have access to the Work wherever it is in preparation or progress, to include off-site facilities of Subcontractors and suppliers at any tier. The Contractor shall provide safe facilities for such access so the Owner's Project Manager may perform his functions under the Contract Documents.

2.2.4 All communications, correspondence, submittals and documents exchanged between the Owner's Project Manager and the Contractor in connection with the Project shall be through or in the manner prescribed by the Owner and consistent with the Owner/Contractor Agreement.

2.2.5 The Owner's Project Manager shall make decisions on all matters relating to aesthetic effect, which decision shall be final.

END OF ARTICLE 2

ARTICLE 3: OWNER

3.1 DEFINITIONS

- 3.1.1** "Owner" means the Town of Leesburg, Virginia, unless the Owner/Contractor Agreement provides otherwise. The Owner shall be referred to as the "Town," or as the "Owner."
- 3.1.2** The term "Owner" or "Owner's Project Manager" specifically excludes any and all inspectors having building code or Town ordinance responsibilities or jurisdiction under the requirements of the Building Permit, unless the Owner designates such person to serve as the Owner's Representative.
- 3.1.3** "Contractor" means the person or persons, firm or company whose bid or proposal has been accepted by the Owner and includes the Contractor's representatives, successors and assigns as permitted by the Owner.

3.2 INFORMATION, SERVICES AND RIGHTS OF THE OWNER

- 3.2.1** The Project Manager will provide administration of the Contract as described below.
- 3.2.2** The Owner or, at the Owner's sole discretion, the Owner's Project Manager or Project Manager, will review and process all Progress Payments, including the Final Payment.
- 3.2.3** The Project/Manager shall have the authority to reject the Work when, in his opinion, the Work does not conform to the Contract Documents.
- 3.2.4** Whenever in the Project Manager's reasonable opinion it is necessary or advisable for the implementation of the Contract Documents, the Project Manager will have authority to require special inspection or testing of the Work in accordance with the provisions of the Contract Documents, whether or not such Work is then fabricated, installed or completed.
- 3.2.5** The Owner or the Owner's Project Manager shall at all times have access to the Work wherever it is in preparation or progress. The Contractor shall provide safe facilities for such access.
- 3.2.6** The Owner, the Owner's Project Manager and the Engineer shall not be responsible for or have control or charge of the construction means, methods, techniques, sequences, or procedures, or for the safety precautions and programs in connection with the Work, and will not be responsible for the Contractor's failure to carry out the Work in accordance with the Contract Documents.

- 3.2.7** The Owner or the Owner's Project Manager shall not be responsible or liable to the Contractor for the acts, errors or omissions of the Contractor, any separate Subcontractor, any separate Contractor or any Contractor's or Subcontractor's agents or employees, or any other persons performing any of the Work.
- 3.2.8** The Owner assumes no responsibility for any conclusions or interpretations made by the Contractor based on the information made available by the Owner. The Owner assumes no responsibility for any understanding reached or representation made concerning conditions that can affect the Work by any of its officers or agents before the execution of this Contract, unless that understanding or representation is expressly set forth in this Contract.
- 3.2.9** The Owner shall not be held responsible for failure to perform the duties and responsibilities imposed by the Contract if such failure is due to strikes, fires, riots, rebellions, or Force Majeure, beyond the control of the Owner, that make performance impossible or illegal, unless otherwise specified in the Contract.
- 3.2.10** The Owner will, throughout the Contract Time and any extension thereof have the right of reasonable rejection and approval of staff assigned to the project by the Contractor. If the Owner reasonably rejects staff or Subcontractors, the Contractor must provide replacement staff or Subcontractors satisfactory to the Owner in a timely manner and at no additional cost to the Owner.
- 3.2.11** The foregoing rights are in addition to other rights of the Owner enumerated herein and those provided by law.

3.3 OWNER'S RIGHT TO STOP OR TO SUSPEND WORK

- 3.3.1** If the Contractor fails to correct defective Work as required by Article 13.2 "CORRECTION OF WORK," or fails to carry out the Work or supply labor and materials in accordance with the Contract Documents, the Owner by written order may order the Contractor to stop the Work, or any portion thereof, without monetary compensation to the Contractor until the cause for such order has been eliminated.
- 3.3.2** The Owner may order the Contractor in writing to suspend, delay, or interrupt all or any part of the Work for such period of time as he may determine to be appropriate for the convenience of the Owner.
- 3.3.3** If the performance of all or any part of the Work is suspended, delayed, or interrupted by the Owner or the Owner's Project Manager for an unreasonable period of time, or by failure of either of them to act within the time specified (or if no time is specified, within a reasonable time), an adjustment increasing the time of performance of the Work shall be made. Such adjustments will be made solely for unreasonable suspension, delay, or interruption. The Contract shall be

modified in writing accordingly. However, no claim for an extension of time shall be made under this Article 3.3.3 for any suspension, delay, or interruption pursuant to Article 3.4.1, or for which claim is provided or excluded under any other provision of this Contract.

No claim under this Article 3.3.3 shall be allowed for any claim for an extension of time required for performance, unless within twenty days after the act or failure to act involved, the Contractor submits to the Owner's Project Manager a written statement setting forth, as then practicable, the extent of such claimed time extension and unless the claim for an extension of time is submitted with supporting data within thirty days after the termination of such suspension, delay, or interruption.

3.3.4 In the event of a suspension of work or delay or interruption of work, the Contractor will and will cause his Subcontractors to protect carefully his, and their, materials and work against damage from the weather and maintain completed and uncompleted portions of the work as required by the Contract Documents. If, in the opinion of the Owner's Project Manager, any work or material shall have been damaged by reason of failure on the part of the Contractor or any of his Subcontractors to protect same, such work and materials shall be removed and replaced at the expense of the Contractor.

3.3.5 No claim by the Contractor under Article 3.3.3 shall be allowed if asserted after Final Payment under this Contract.

3.4 OWNER'S RIGHT TO CARRY OUT THE WORK

3.4.1 If the Contractor defaults or neglects to carry out the Work in accordance with the Contract Documents and fails within a seven day period after receipt of written notice from the Owner to commence and continue correction of such default or neglect with diligence and promptness, the Owner may after the seven day period give the Contractor a second written notice to correct the deficiencies within a three day period. If the Contractor fails to commence and continue to correct any deficiencies within the second notice's three day period, the Owner may, without prejudice to other remedies the Owner may have, correct such deficiencies. In such a case an appropriate Change Order shall be issued pursuant to Article 12 deducting from the payments then or thereafter due the Contractor the cost of correcting such deficiencies, including compensation for services of the Owner's Project Manager, the Engineer and any other additional services made necessary by such default, neglect or failure. If the payments then or thereafter due the Contractor are not sufficient to cover such amount, the Contractor shall pay on demand the difference to the Owner.

3.4.2 The Owner will not be liable or accountable to the Contractor for the method by which the Work, or any portion thereof, performed by the Owner or by separate

contractors pursuant to Article 3.4 is accomplished or for the price paid therefor. Notwithstanding the Owner's right to carry out a portion of the Work, maintenance and protection of the Work remains the Contractor's responsibility.

3.5 EXAMINATION OF RECORDS

3.5.1 The Owner, or any duly authorized representative, shall, until the expiration of five years after final payment hereunder, have access to and the right to examine, audit and copy any directly pertinent books, documents, as-builts, papers and records of the Contractor involving transactions related to this Contract. Any audit or examination shall occur during regular business hours and not exceed a reasonable period of time under the circumstances.

3.5.2 The Contractor further agrees to include in any subcontract for more than \$10,000 entered into as a result of this Contract, a provision to the effect that the Subcontractor agrees that the Owner or any duly authorized representative shall, until the expiration of three years after final payment under the Contract, have access to and the right to examine, audit and copy, without charge, any directly pertinent books, documents, papers and records of such contractor involved in transactions related to such subcontract, or this Contract. The term subcontract shall exclude subcontracts or purchase orders for public utility services at rates established for uniform applicability to the general public.

3.5.3 The period of access provided in Subparagraphs 3.5.1 and 3.5.2 above shall continue for all contracts and subcontracts until any appeals, litigation, or claims have been finally concluded.

3.5.4 Nothing in these General Conditions shall be deemed to modify in any manner any applicable statute of limitations.

END OF ARTICLE 3

ARTICLE 4: CONTRACTOR

4.1 DEFINITION

4.1.1 The Contractor is the person or organization identified as such in the Owner/Contractor Agreement. The term Contractor means the Contractor or his authorized representative, who shall have authority to bind the Contractor in all matters pertinent to this Contract.

4.1.2 The Contractor is not an agent for the Owner but is an independent contractor engaged in the business of providing the services and performing the Work described in the Contract Documents.

4.2 REVIEW OF CONTRACT DOCUMENTS

4.2.1 Before submitting his bid or proposal to the Owner, and continuously after execution of the Contract, the Contractor shall carefully study and compare the Contract Documents and shall at once report to the Owner any error, inconsistency or omission he may discover, including any requirement that may be contrary to any law, ordinance, rule, regulation or order of any public authority bearing on the performance of the Work. By submitting his bid or proposal for the Contract and the Work under it, the Contractor agrees that the Contract Documents are accurate, consistent and complete. The Contractor shall perform no portion of the Work at any time without Contract Documents and, where required, approved Shop Drawings, product data, samples, mock ups or other submittals for such portion of the Work

4.3 SUPERVISION AND CONSTRUCTION PROCEDURES

4.3.1 The Contractor shall supervise and direct the Work, using his best skill and attention. He shall be solely responsible for and have control over all construction means, uses, sequences, procedures, safety precautions and programs, and coordination of all portions of the Work under the Contract.

4.3.2 The Contractor shall be responsible to the Owner for the acts and omissions of his employees, Subcontractors, Suppliers, their agents and employees, and other persons performing any of the Work and for their compliance with each and every requirement of the Contract Documents, in the same manner as if they were fully employed by the Contractor.

4.3.3 The Contractor shall not be relieved from his obligations to perform the Work in accordance with the Contract Documents either by acts, failures to act or duties of the Owner or the Owner's Project Manager in their administration of the Contract, or by inspections, tests, or approvals (or the lack thereof) required or

performed under Article 4.4 "INSPECTION OF CONSTRUCTION" or Article 7.5 "TESTS" by persons other than the Contractor.

4.3.4 The Contractor shall employ no plant, equipment, materials, methods or persons to which the Owner or Owner's Project Manager reasonably objects.

4.3.5 The Contractor shall not remove any portion of the Work or stored materials from the site of the Work, if payment for such was requested or received from the Owner.

4.3.6 The Contractor shall at all times so conduct its work as to ensure the least possible obstruction to traffic and inconvenience to the general public and the residents in the vicinity of the Work. No road or street shall be closed to the public except with the permission of the Town Traffic Engineer and proper governmental authority. Fire hydrants on or adjacent to the Work shall be kept accessible to fire fighting equipment at all times. Temporary provisions shall be made by the Contractor to ensure the use of sidewalks and the proper functioning of all gutters, drainage inlets, drainage ditches, and irrigation ditches, which shall not be obstructed except as approved by the Owner's Project Manager.

4.3.7 When construction crosses highways, railroads, streets, or utilities under the jurisdiction of State, County, Town, or other public agency, public utility, or private entity, the Contractor shall secure written permission where necessary from the proper authority before executing such new construction. A copy of such written permission must be filed with the Owner before any work is started. The Contractor shall be required to furnish a release from the proper authority before final acceptance of the Work.

4.3.8 The Contractor shall provide and maintain such sanitary accommodations for the use of the Contractor's employees and those of its Subcontractors as may be necessary to comply with the requirements and regulations of the local and State departments of health and where additional accommodations are necessary for a reasonably sanitary activity, then such additional accommodations shall be made by the Contractor.

4.4 INSPECTION OF CONSTRUCTION

4.4.1 The Contractor shall maintain an adequate inspection system and perform such inspections as will ensure that the Work called for by this Contract conforms to Contract requirements. The Contractor shall maintain complete inspection records and make them available to the Owner and Owner's Project Manager. All work is subject to inspection and testing at all places and at all reasonable times before acceptance to ensure strict compliance with the terms of the Contract.

4.5 CONTRACTOR'S REPRESENTATIONS

4.5.1 By entering into this Contract with the Owner, the Contractor represents and warrants the following, together with all other representations and warranties in the Contract Documents:

- .1 That he is experienced in and competent to perform the type of work required and to furnish the plant, materials, supplies or equipment to be so performed or furnished by him;
- .2 That he is financially solvent, able to pay his debts as they mature, and possessed of sufficient working capital to initiate and complete the Work and Changes required under the Contract;
- .3 That he is familiar with all laws, ordinances, permits, regulations and resolutions that may in any way affect the Work or those employed therein, including but not limited to any special laws or regulations related to contractor licenses and/or registrations for the Work or any part thereof;
- .4 That such temporary and permanent work required by the Contract Documents that is to be done by him will be satisfactorily constructed and fit for use for its intended purpose and that such construction will not injure any person, or damage any property;
- .5 That he will fully comply with all requirements of the Contract Documents;
- .6 That he will perform the Work in a skillful manner consistent with good workmanship, sound business practice, and in the most expeditious and economical manner consistent with the best interests of the Owner;
- .7 That he will furnish efficient business administration and experienced superintendence and an adequate supply of workers, equipment, tools, and materials at all times;
- .8 That he has carefully reviewed the Work required and that the Work can be planned and executed in a normal and orderly sequence and be reasonably scheduled so as to insure completion of the Work in accordance with the Contract Documents, allowing for normal and reasonably foreseeable weather, labor

and other delays, interruptions and disruptions of the Work at the site designated;

- .9 That he will complete the Work within the Contract Time and all portions thereof within any required Contract milestones;
- .10 That his Contract Price is based upon the labor, materials, systems and equipment required by the Contract Documents, without exception;
- .11 That he does not and will not during the performance of the Contract violate the provisions of the Federal Immigration Reform and Control Act of 1986, as amended, which prohibits the employment of illegal aliens, and Federal and State employment and wage hour laws;
- .12 That he has taken steps reasonably necessary to ascertain the nature and locations of the Work of the Contract, has investigated and satisfied himself as to the general and local conditions which can affect the Work or its cost, including but not limited to: conditions bearing upon transportation, disposal, handling, and storage of materials; the availability of labor, water, electric power, and roads; uncertainties of weather, river stages, tides, or similar physical conditions at the site; the conformation and conditions of the ground; and the character of equipment and facilities needed before and during work performance;
- .13 That no employee of the Owner shall be admitted to any share or part of this Contract or to any benefit that may arise therefrom which is not available to the general public; and
- .14 That Contractor's bid or offer was made without collusion or fraud and that it has not offered or received any kickbacks or inducements from any other offeror, supplier, manufacturer, or Subcontractor and that it has not conferred on any public employee having official responsibility for this purchase any payment, loan, subscription, advance, deposit of money, services, or anything of more than nominal value, present or promised unless consideration of substantially equal or greater value was exchanged. Contractor acknowledges that this Contract incorporates by reference the Virginia Public Procurement Act, VA Code Sect. 2.2-4300 *et seq.* (VPPA), as well as any state or federal law related to ethics, conflicts of interest, or bribery, including by way of illustration and not limitation, the Virginia State and Local Government Conflict of Interests Act, the

4.6 LABOR AND MATERIALS

- 4.6.1** Unless otherwise provided in the Contract Documents, the Contractor shall provide and pay for all labor, materials, equipment, supplies, tools, construction equipment and machinery, heat, utilities, transportation, and other facilities and services necessary or proper for or incidental to the execution and completion of the Work required by and in accordance with the Contract Documents and any applicable code or statute, whether specifically required by the Contract Documents, or whether their provision may reasonably be inferred as necessary to produce the intended results, whether temporary or permanent and whether or not incorporated or to be incorporated in the Work. Unless otherwise specified, all materials and equipment incorporated in the Work under the Contract shall be new. All work performed, shall be accomplished by persons qualified in the respective trades. Final Payment will not be made until the Work is so completed.
- 4.6.2** Whenever materials or equipment are specified or described in the Drawings or Specifications by using the name of a proprietary item or the name of a particular manufacturer, fabricator, supplier, or distributor, the naming of the item is intended to establish the type, function, and quality required. Unless the name is followed by words indicating that no substitution is permitted, materials or equipment of other manufacturers, fabricators, suppliers or distributors may be accepted by the Owner's Project Manager if sufficient information is submitted by the Contractor to allow the Owner's Project Manager to determine that the material or equipment proposed is equivalent to that name.
- 4.6.3** Requests for review of substitute items of material and equipment will not be accepted by the Owner's Project Manager from anyone other than the Contractor. If the Contractor wishes to furnish or use a substitute item of material or equipment, the Contractor shall make written application to the Owner's Project Manager for acceptance thereof, certifying that the proposed substitute will perform adequately the functions called for by the general design, be similar and of equal or better substance to that specified, and be suited to the same use and capable of performing the same or better function as that specified. The application shall state whether or not acceptance of the substitute for use in the Work will require a change in the drawings or specifications to adapt the design to the substitute and whether or not incorporation or use of the substitute in connection with the Work is subject to payment of a license fee or royalty. All variations of the proposed substitute from that specified shall be identified in the application and available maintenance, repair, and replacement service shall be indicated.

4.6.4 The Contractor shall submit complete data substantiating compliance of the proposed substitution with the Contract Documents, including:

- .1 Product identification including manufacturer's name, address and phone number;
- .2 Manufacturer's literature showing complete product description, performance and test data, and all reference standards;
- .3 Samples and colors in the case of articles or products;
- .4 Name and address of similar projects on which the product was used and date of installation;
- .5 For construction methods, include a detailed description for the proposed method and drawings illustrating same;
- .6 Itemized comparison of proposed substitution with product or method specified and any cost reduction which shall benefit the Owner;
- .7 Accurate cost data on proposed substitution with product or method specified and any cost reduction which shall benefit the Owner;
- .8 All directions, specifications and recommendations by manufacturers for installation, handling, storing, adjustment and operation; and
- .9 A mock up if determined necessary by the Project Manager.

4.6.5 The Contractor shall also submit with his request for approval a sworn and notarized statement that shall include the following representations:

- .1 That he has investigated the proposed product or method and determined that it is equal or better in all respects to that specified and that it fully complies with all requirements of the Contract Documents;
- .2 That he will meet all Contract obligations with regard to the substitution;
- .3 That he will coordinate installation of accepted substitutions into the Work, making all such changes and any required schedule

adjustment, at no additional cost to the Owner, as may be required for the Work to be complete in all respects;

- .4 He waives all claims for additional costs and additional time related to substitutions which consequently become apparent. He also agrees to hold the Owner harmless from claims for extra costs and time incurred by other Subcontractors and suppliers, or additional services which may have to be performed by the Owner's Project Manager, for changes or extra work that may, at some later date, be determined to be necessary in order for Work to function in the manner intended in the Contract Documents;
- .5 He will provide the same warranty and guarantee, and perform any work required in accordance therewith, for the substitution that is applicable to the specified item for which the substitution is requested;
- .6 Material will be installed, handled, stored, adjusted, tested, and operated in accordance with the manufacturers' recommendations and as specified in the Contract Documents;
- .7 In all cases new materials will be used unless this provision is waived by notice from the Owner or the Owner's Project Manager or unless otherwise specified in the Contract Documents;
- .8 All material and workmanship will be in every respect in accordance with that which, in the opinion of the Owner or the Owner's Project Manager, is in conformity with approved current practice;
- .9 He has provided accurate cost data on the proposed substitution in comparison with the product or method specified; and
- .10 He has taken into consideration the necessary adjustment, relocation and/or installation of public utilities in areas within the limits of this Contract. No additional compensation will be paid to the Contractor for delays to the project schedule, work interruptions, changes in construction sequences, changes in handling excavation, drainage or paving, or for changes in types of equipment used, etc., caused by complying with the provisions of this statement. The Contractor shall include activities in its initial schedule indicating the utility relocation necessary to complete the Work. Delays to the project schedule caused by untimely relocations of utilities will not be considered a compensable delay, but if supported in accordance with the

provisions of Article 8.3, may entitle the Contractor to a non-compensable time extension. The Contractor shall assume all responsibility for coordinating with the various utility companies to verify their relocation schedules, determine the anticipated duration to complete the respective utility relocations, and to facilitate utility relocations to minimize the impact to the project schedule upon notification of being named the apparent low bidder.

- 4.6.6** The application shall also contain an itemized estimate of all costs that will result directly or indirectly from acceptance of such substitute, including costs of redesign and claims of other contractors affected by the resulting change. All of the foregoing shall be considered by the Owner's Project Manager in evaluating the proposed substitute. The Owner's Project Manager may require the Contractor to furnish at the Contractor's expense additional data about the proposed substitute. The Owner shall be the sole judge of acceptability, and no substitute shall be ordered or installed without the Owner's prior written acceptance. The Owner may require the Contractor to furnish at the Contractor's expense a special performance guarantee or other surety with respect to any substitute.
- 4.6.7** If a substitution is approved, no additional change in brand or make will be permitted unless satisfactory written evidence is presented to and approved by the Owner showing that the manufacturer cannot make scheduled delivery of the approved substituted item. Substitutions will not be considered by the Owner if:
- .1 The proposed substitution is indicated or implied on the Contractor's shop drawing or product data submittals and has not been formally submitted for approval by the Contractor in accordance with the above-stated requirement; or
 - .2 Acceptance of the proposed substitution will require substantial revisions to the Contract Document or is otherwise not acceptable to the Owner or his authorized representative.
- 4.6.8** The Contractor shall not have any right of appeal from the decision of the Project Manager rejecting any materials submittal.
- 4.6.9** Manufactured articles, material and equipment shall be applied, installed, connected, erected, used, cleaned, and conditioned as directed by the manufacturer unless herein specified to the contrary.
- 4.6.10** Any material specified by reference to the number, symbol or title of a specific standard, such as a Commercial Standard, a Federal Specification, a Trade Association Standard, or other similar standard, shall comply with the

requirements in the latest revision of the standards or specification and any amendment or supplement, except as limited to type, class or grade, or as modified in such reference. The standard referred to, except as modified in the Specifications, shall have full force and effect as though printed in the Specifications.

- .1 Reference in the Specifications or on the Drawings to any article, device, product, material, fixture, form or type of construction by name, make or catalog number shall be interpreted as establishing a standard of quality and shall not be construed as eliminating from competition other products of equal or better quality by other manufacturers where fully suitable, as approved by the Owner's Project Manager. Applications for approval of substitutions for the specified items will be considered only upon request of the Contractor, not of individuals, trades or suppliers, and only for a specific purpose; no blanket approvals will be granted. No approval of a substitution shall be valid unless it is in written form and signed by the Owner's Project Manager.
- .2 If any proposed substitution will affect a correlated function, adjacent construction or the work of other contractors, then the necessary changes and modifications to the affected work shall be considered as an essential part of the proposed substitution, to be accomplished by the Contractor without additional expense to the Owner, if and when approved. Detail drawings and other information necessary to show and explain the proposed modifications shall be submitted with the request for approval of the substitution.

4.6.11 All equipment, apparatus, or devices of any kind to be incorporated into the Work that are shown or indicated on the drawings or called for in the specifications or required for the completion of the Work shall be entirely satisfactory to the Owner's Project Manager as regards operations, capacity, or performance. No approval, either written or oral, of any drawings, descriptive data, or samples of such equipment, apparatus, or device shall relieve the Contractor of his responsibility to turn over the same in good working order for its intended purpose at the completion of the Work in complete accordance with the Contract Documents. Any equipment, apparatus and/or device not fulfilling these requirements shall be removed and replaced by proper and acceptable equipment, or put in good working order satisfactory to the Owner's Project Manager without additional cost to the Owner.

4.6.12 The Contractor shall at all times enforce strict discipline and good order among his employees and shall not employ on the Work any unfit person or anyone not skilled in the task assigned to him. The Owner may, by written notice, require

the Contractor to remove from the Work any employee the Owner deems incompetent, careless or otherwise objectionable.

4.7 WARRANTY

4.7.1 The Contractor guarantees and warrants to the Owner all work as follows:

- .1 That all materials and equipment furnished under this Contract will be new and the best of its respective kind unless otherwise specified;
- .2 That all Work will comply with or exceed industry standards and be free of omissions and faulty, poor quality, imperfect or defective materials or workmanship;
- .3 That where no standard is specified for such workmanship or materials, they shall be the best of their respective kinds;
- .4 That all applicable Work shall be entirely watertight and leakproof in accordance with all applicable industry customs and practices, and shall be free of shrinkage and settlement;
- .5 That the Work, including but not limited to, mechanical and electrical machines, devices and equipment shall be fit and fully usable for its intended and specified purpose and shall operate satisfactorily with ordinary care;
- .6 That consistent with requirements of the Contract Documents, the Work shall be installed and oriented in such a manner as to facilitate unrestricted access for the operation and maintenance of fixed equipment; and
- .7 That the Work will be free of abnormal or unusual deterioration that occurs because of poor quality materials, workmanship or unsuitable storage.

4.7.2 All work not conforming to guarantees and warranties specified in the Contract Documents, including substitutions not properly approved and authorized, may be considered defective. If required by the Owner's Project Manager, the Contractor shall furnish satisfactory evidence as to the kind and quality of materials and equipment. This warranty is not limited by the provisions of Article 13 "UNCOVERING AND CORRECTION OF WORK."

- 4.7.3** The warranties set forth in this Article 4.7 and elsewhere in the Contract Documents shall survive Final Completion of the Work under Article 9.8 "FINAL COMPLETION AND FINAL PAYMENT."
- 4.7.4** If, within one year after the Date of Final Acceptance of the Work or designated portion thereof or within one year after acceptance by the Owner of designated equipment or within such longer period as may be prescribed by law or by the terms of the applicable special warranty required by the Contract Documents, any of the Work is found to be defective, not in accordance with the Contract Documents, or not in accordance with the guarantees and warranties specified in the Contract Documents, the Contractor shall correct it within five working days, or such other period as agreed, after receipt of written notice from the Owner or Owner's Project Manager to do so.
- 4.7.5** If at any time deficiencies in the Work are discovered that are found to have resulted from latent defects, gross mistakes, fraud or misrepresentation by the Contractor, any Subcontractor or Supplier, the Contractor will be liable for replacement or correction of such Work or any damage that the Owner has incurred, or will incur, related thereto, regardless of the time limit of any guarantees or warranty.
- 4.7.6** Any materials or other portions of the Work, installed, furnished, or stored on site that are not of the character or quality required by the specifications, or are otherwise not acceptable to the Owner's Project Manager shall be immediately removed and replaced by the Contractor to the satisfaction of the Owner's Project Manager when notified to do so by the Owner's Project Manager.
- 4.7.7** If the Contractor fails to correct defective or nonconforming Work as required by Article 4.7.4 or Article 4.7.5 or, if the Contractor fails to remove defective or nonconforming Work from the site, as required by Article 4.7.6, the Owner may elect to either correct such Work in accordance with Article 3.4 "OWNER'S RIGHT TO CARRY OUT THE WORK" or remove and store materials and equipment at the expense of the Contractor.
- 4.7.8** The Contractor shall bear the cost of making good all work of the Owner, separate contractors or others, destroyed or damaged by such correction or removal required under this Article, Article 13 "UNCOVERING AND CORRECTION OF WORK" or elsewhere in the Contract Documents.

4.8 TAXES

- 4.8.1** The Contractor shall pay all applicable Federal, State, and local taxes and duties for the Work or portions thereof provided by the Contractor that are legally enacted at the time the Contract is awarded, whether or not yet effective.

Increases in the rates of such taxes and duties during performance of the Contract shall be the responsibility of the Contractor.

4.9 PERMITS, FEES AND NOTICES

4.9.1 The Contractor shall secure and pay for all permits, fees, licenses and inspections necessary for the proper execution and completion of the Work that are legally required at the time the proposals are received.

4.9.2 The Contractor shall give all notices and comply with all laws, ordinances, rules, regulations and lawful orders of any public authority bearing on the performance of the Work.

4.10 SUPERINTENDENT

4.10.1 The Contractor shall employ a competent Superintendent and necessary assistants who shall be in attendance at the Project site during the progress of the Work. The Superintendent shall be an authorized representative of the Contractor and all communications given to the Superintendent shall be as binding as if given to the Contractor.

4.10.2 The Superintendent shall be in attendance at the Project site not less than eight hours per day, five days per week, unless the job is closed down due to a general strike or conditions beyond the control of the Contractor or until termination of the Contract in accordance with the Contract Documents. It is understood that such Superintendent shall be approved in writing by the Owner and shall be the one who will continue in that capacity for the duration of the Project, unless the Superintendent ceases to be on the Contractor's payroll or his withdrawal is required or approved by the Owner. The Superintendent shall not be employed on any other project for or by the Contractor or any other entity during the course of the Work.

4.10.3 Such Superintendent shall be fluent in English and in such other languages as may be necessary to communicate effectively with all owner's representatives, employees and Subcontractors of the Contractor. This requirement may be satisfied by the on-site presence of a competent foreign language interpreter to English interpreter. Any costs associated with foreign language interpretation shall be borne by the Contractor.

4.10.4 Any and all project documents, including but not limited to daily reports and logs, maintained by the Superintendent or the Contractor's employees or Subcontractors shall be in English. Any costs of foreign language translation shall be borne solely by the Contractor and shall not be a basis for any additional compensation or time extension from the Owner.

4.11 PROJECT SCHEDULES

4.11.1 The Schedule of Completion shall consist of the Contractor planning, scheduling, and constructing this project by using a Critical Path Method Project Schedule (CPM). The CPM shall be used for coordinating and monitoring all the Work specified in the Contract Documents including all activities of subcontractors, vendors, suppliers, utilities, and all other parties associated with the construction of the project. The CPM shall be based upon the entirety of the Contract Documents. All physical work and major procurement activities shall be included. The CPM shall be the Activity-On-Arrow type. The Contractor shall use either Primavera or SureTrak scheduling software.

The CPM utilized float: Float is defined as the amount of time between when an activity “can start” (the early start) and when an activity “must start” (the late start). Float is a shared commodity for the Owner and the Contractor and is not for the exclusive use or financial benefit of either party. Either party has the full use of the float until it is depleted.

4.11.2 Initial Critical Path Method Project Schedule (ICPM) shall consist of the following:

- a. Activity-On-Arrow Time Scale Diagram
- b. Total Float Computer sort
- c. Written Narrative (WN)
- d. Printed calendars. The printed calendars shall include a listing, description, and calendar form tabulation of all calendars used in the ICPM. The calendars shall contain the total number of anticipated work days required to complete all the Work required in the Contract. The calendars shall delineate the holidays, anticipated nonwork days, and bad weather days. An explanation of the Contractor’s basis for determining nonwork and bad weather days shall be included with the calendars.
- e. Data disc containing all of the information for (a) thru (d). The format shall be compatible with the Owner’s computer software.

The ICPM diagram shall be drafted to a scale that allows the I node and J node numbers of each activity to be printed adjacent to that activity. The activities shall be clearly defined. All restraints between activities shall be shown.

The Contractor shall expend the entire Contract time specified in this Invitation for Bids. On Contracts with calendar date completions or calendar day durations, all planned activities shall have durations not exceeding 14 calendar days, except the activities required for the Owner’s review and approval of the working drawings and material sources which shall be given a duration of not less than 30 calendar days. On Contracts with working day durations, these time periods shall be 10 working days and 25 working days.

All activities in the Contract Documents along with a written narrative explanation shall be identified in the ICPM. The Project Manager reserves the right to specify the number of activities, and to require at any time additional breakdown of the activities.

The Contractor shall provide a written narrative as part of the ICPM describing the original critical path, the sequence of work, number of shifts per day, number of hours per shift, composition and number of crews, and the equipment to be utilized on each activity. Subcontracting activities shall be listed and identified by activity number. Each activity shall be identified by physical location and phase of work. Abbreviations used in preparing the ICPM shall be explained in the written narrative.

The Contractor shall complete the proposed ICPM within 14 calendar days after receiving the Notice of Award and submit 5 sets to the Project Manager for review and approval. The Project Manager will review the Contractor's ICPM within 5 calendar days after the submittal. If required, the Project Manager will convene a Joint Review Conference at which time the Project Manager and Contractor may make corrections and adjustments to the proposed ICPM. If a revision is necessary due to the Project Manager's review or the Joint Review Conference, the proposed revisions shall be submitted, by the Contractor, within 7 calendar days after the initial review date to the Project Manager for another review. Revisions shall conform to the format used in the ICPM. The Project Manager will respond to the revised ICPM within seven calendar days after its receipt.

No construction work shall begin until the Project Manager has accepted the ICPM. Time charges shall begin no later than the on or before date of the Notice to Proceed. Any delay in starting work caused by the acceptance of the ICPM by the Project Manager will not be a basis for any monetary claim.

4.11.3 When the Project Manager notifies the Contractor that the ICPM has been accepted, that document will become the CPM of Record (CPMR). The Contractor shall be responsible for implementing and executing the Work specified in the Contract in strict conformance with the CPMR. The CPMR shall be the Contractor's work plan for completing the entire Contract as specified in the Contract Documents.

Failure of the Contractor to adhere to the latest approved CPMR will be cause for the Owner to deny any and all requests for additional compensation or extensions of the Contract duration.

4.11.4 Revisions to the CPMR shall consist of one or more of the following:

- a. A change in duration of an activity.
- b. A change in the logic of the schedule.

- c. A change in the calendars.
- d. The deletion or addition of one or more activities.

The Contractor may submit a proposed revision to the CPMR at any time during the life of the Contract.

The Contractor shall submit a proposed revision to the CPMR whenever the activities differ from the accepted CPMR. Proposed revisions shall be submitted by the Contractor within 30-calendar days from the date on which the Contractor's activities deviated from the accepted CPMR. The revisions shall be submitted to the Project Manager in the same format used for the ICPM. The revisions shall include data from all CPMR Updates, which have been accepted by the Administration. The Written Narrative accompanying the revision shall describe the reason for the revisions, the critical path, and all logic and duration modifications to the CPMR. These shall include, but not be limited to, changes in the method or manner of the Work, changes in Specifications, extra work, addition or deletion of work, increased or decreased quantities, defective work and acceleration of the Work.

The Project Manager will review the CPMR and respond to the Contractor's proposed revision within 5 calendar days after its receipt. The Project Manager reserves the right to deny any proposed revision which adversely impacts the Owner, utilities, or other interested parties.

4.11.5 Any written request for an extension of time or change in incentive/disincentive date (if applicable) shall be accompanied by a revised CPMR, which documents the actual delay to the Contract completion date or incentive/disincentive date. The request shall include a written narrative of the events which would require an extension of the Contract time or incentive/disincentive date.

Only delays to activities, which affect the Contract completion date or incentive/disincentive date will be considered for a time extension. The extension of the specified Contract completion date or incentive/disincentive date will be based upon the actual number of calendar days the Contract completion date or incentive/disincentive date is adjusted. No extensions of the specified Contract completion date will be issued for work performed on activities with float.

4.11.6 Monthly updates of the CPMR are required. CPMR update submissions shall contain the activity data as specified in (a) thru (e) of the ICPM. The update shall describe the progress of the project to date. It shall include a description of the current critical path, the amount of float on the critical path, any delays or disruptions experienced by the Contractor during the period of the update, any change in manpower or equipment, the inclusion of any schedule revisions, and any potential delays or disruptions.

When a delay or a disruption to the Work is identified in the Written Narrative, which the Contractor believes to be the responsibility of the Owner, the Contractor shall submit a revision to the CPMR within 30 calendar days after the submittal of the updates.

4.11.7 The Owner and the Contractor will hold monthly job site progress meetings to discuss the progress of the project and update the CPMR. The Contractor shall arrange to have a representative of each subcontractor currently working on the project in attendance. The Contractor shall submit to the Project Manager the CPMR updates within 14 calendar days from the date of the monthly meeting. The Project Manager will review the update and advise the Contractor of its acceptability prior to the next monthly meeting.

4.12 RESPONSIBILITY FOR COMPLETION

4.12.1 The Contractor shall furnish such labor, materials, tools, equipment, and professional services and shall work such hours, including night shifts, overtime operations and Sundays and holidays, as may be necessary to ensure the performance of the Work within Milestone and Completion dates specified in the Owner/Contractor Agreement. If it becomes apparent to the Owner's Project Manager that the Work will not be completed within required Milestone or Completion dates, the Contractor agrees to undertake some or all of the following actions, at no additional cost to the Owner, in order to ensure, in the opinion of the Owner's Project Manager, that the Contractor will comply with all Milestone and Completion date requirements:

- .1 Increase labor, materials, tools, equipment and professional services;
- .2 Increase the number of working hours per shift, shifts per working day, working days per week, or any combination of the foregoing; and
- .3 Reschedule activities to achieve maximum practical concurrency of accomplishment of activities.

4.12.2 If the actions taken by the Contractor are not satisfactory, the Owner or the Owner's Project Manager may direct the Contractor to take any and all actions necessary to ensure completion within the required completion dates, without additional cost to the Owner. In such event, the Contractor shall continue to assume responsibility for his performance and for completion within the required dates.

4.12.3 If, in the opinion of the Project Manager, the actions taken by the Contractor pursuant to this Agreement or the progress or sequence of work are not accurately

reflected on the Construction schedule, the Contractor shall revise such schedule to accurately reflect the actual progress and sequence of work.

4.12.4 This provision does not eliminate the Contractor's responsibility to comply with the Town noise ordinances, all Town permit requirements and all other applicable laws, regulations, rules, ordinances, resolutions, and permit requirements.

4.13 DOCUMENTS, OTHER SUBMITTALS AT THE SITE; AS-BUILT DRAWINGS

4.13.1 The Contractor and his Subcontractors shall maintain at the site, and at all times make available to the Owner and the Owner's Project Manager one record copy of all Drawings, Specifications, Addenda, Change Orders, and other Modifications, in good order and marked currently to record all changes made during construction, and approved Shop Drawings, Product Data, Samples, Mock Ups and other Submittals ("as-built drawings").

4.13.2 The Contractor shall prepare the as-built drawings by marking up two sets of prints and one electronic copy of the applicable Contract Drawings to portray as-built construction, in conformance with the DCSM. The prints shall be neatly and clearly marked to show all variations between the Work actually provided and that indicated on the Contract Drawings, and all utilities encountered in the Work. All drafting shall conform to good drafting practice and shall include such supplementary notes, legends and details as may be necessary for legibility and clear portrayal of the as-built construction. These drawings shall be marked promptly at the completion of the project and shall be turned over the Owner prior to Final Payment.

4.14 SHOP DRAWINGS, PRODUCT DATA, SAMPLES AND OTHER SUBMITTALS

4.14.1 The term "Shop Drawings" shall mean all drawings, diagrams, illustrations, brochures, schedules and other data which are prepared by Contractor, a Subcontractor, manufacturer, supplier or distributor and which illustrate the equipment, material or some portion of the Work.

4.14.2 The Contractor shall submit with reasonable promptness and in such sequence as to cause no delay in the Work or in the work of the Owner or any separate Contractor, all Shop Drawings, Product Data, Manuals, Samples, and Submittals required by the Contract Documents. All such submissions shall be made so as to cause no delay in the project, allowing the Owner or his designated representative fourteen (14) working days for review and checking.

4.14.3 By approving and submitting Shop Drawings, Product Data, Manuals, Samples and Submittals, the Contractor represents that he has determined and verified all

materials, field measurements, and field construction criteria related thereto, and that he has checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents. The Contractor shall adhere to any supplementary processing and scheduling instructions pertaining to any submittals that may be issued by the Owner's Project Manager.

- 4.14.4** Parts and details not fully indicated on the Contract Drawings shall be detailed by the Contractor in accordance with standard engineering practice. Dimensions on the Contract Drawings, as well as detailed drawings themselves, are subject in every case to measurements of existing, adjacent, incorporated and completed work that shall be taken by the Contractor before undertaking any work dependent on such data.
- 4.14.5** Where the Contract Documents call for the submittal of manufacturer's data to the Owner or the Owner's Project Manager for information only, such submittals shall be made before the commencement of any portion of the Work requiring such submission.
- 4.14.6** The Contractor shall not be relieved of responsibility for any deviation from the requirements of the Contract Documents by virtue of the review by the Owner or the Owner's Project Manager of Shop Drawings, Product Data, Samples or Manuals unless the Contractor has specifically informed the Owner's Project Manager in writing of such deviation at the time of submission and the Owner's Project Manager has given written approval to the specific deviation. The Contractor shall not be relieved from responsibility for errors or omissions in the Shop Drawings, Product Data, Samples or Manuals by the Owner or Owner's Project Manager's review thereof.
- 4.14.7** Shop drawings shall be submitted in such number of copies that three copies may be retained by the Project Manager or his designee after approval. Each submission shall be accompanied by a letter of transmittal in duplicate, listing the contents of the submission and identifying each item by reference to specification section or drawing. All Shop Drawings shall be clearly labeled with the name of the project and such information as may be necessary to enable their complete review by the Project Manager or his designee. Catalog plates and other similar material that cannot be so labeled conveniently shall be bound in suitable covers bearing the identifying data.
- 4.14.8** Shop drawings shall be accompanied by all required certifications and other such supporting material, and shall be submitted in such sequence or in such groups that all related items may be checked together. When Shop Drawings cannot be checked because a submission is not complete, or because Shop Drawings on related items have not been received by the Project Manager or his designee, such Shop Drawings will be returned without action, and marked 'rejected' with

the reason for rejection clearly stated. Incomplete or defective submittals shall also be returned without action, and marked 'rejected' with the reason for rejection clearly stated.

4.14.9 Shop Drawings shall have been reviewed by the Contractor and coordinated with all other related or affected work before they are submitted for approval and shall bear the Contractor's certification that the Contractor has checked and approved them as complying with all relevant information in the Contract Documents. Shop Drawings submitted without such certification and coordination will be returned to the Contractor without action and will be considered not a formal submission.

4.14.10 SAMPLES required by the specifications or requested by the Project Manager or his designee shall be submitted for approval. Samples shall be submitted in single units only, unless the Contractor desires additional units for the Contractor's own use. Each sample shall bear a label indicating the material represented, the name of the producer and the title of the Project. Approval of a sample shall be only for conformance with the design concept of the Project and compliance with the information given in the Contract Documents, and only for the characteristics or use named in such approval. Such approval shall not be construed to change or modify any Contract requirements or the Contract Price. Materials and equipment incorporated in the Work shall match the approved samples.

4.14.11 All TESTS of materials and finished articles shall be made by bureaus, laboratories or agencies approved by the Project Manager or his designee, and the certified reports of such tests shall be submitted to the Project Manager. All costs in connection with the testing shall be borne by the Contractor. Failure of any material to pass the specified tests or any test performed by the Project Manager or his designee will be sufficient cause for refusal to consider, under this Contract, any further materials of the same brand or make of that material. Samples of various materials delivered on the site or in place may be taken by the Project Manager or his designee for testing. Samples failing to meet the requirements of the Contract Documents will automatically void previous approvals of the items tested. See Article 7.5 for additional test requirements.

Unless otherwise specified, testing for soil compaction, soil suitability, concrete testing, etc. will be performed by or on behalf of the Contractor at the Contractor's expense. The Contractor shall furnish copies of all test results or related reports or documents to the Project Manager.

4.15 CUTTING AND PATCHING OF WORK

4.15.1 The Contractor shall be responsible for all cutting, fitting or patching that may be required to complete the Work and to make its several parts fit properly and in accordance with the Contract Documents.

4.15.2 The Contractor shall not damage or endanger any portion of the Work or the work of the Owner or any separate Contractors by cutting, patching or otherwise altering any work, or by excavation. The Contractor shall not cut or otherwise alter the work of the Owner or any separate Contractor except with the written consent of the Owner and of such separate Contractor. The Contractor shall not unreasonably withhold from the Owner or any separate Contractor his consent to cutting or otherwise altering the Work. The Owner shall not be required to accept work with a cut, a splice, or patch when such cut, splice or patch is not generally accepted practice for the particular work involved or is otherwise unworkmanlike in the opinion of the Owner or the Owner's Project Manager.

4.16 DRUG-FREE WORKPLACE

During the performance of this contract, the Contractor agrees as follows:

- .1 The Contractor will provide a drug-free workplace for the Contractor's employees. The Contractor agrees to post in conspicuous places, available to employees and applicants for employment, a statement notifying employees that the unlawful manufacture, sale, distribution, dispensation, possession, or use of a controlled substance or marijuana is prohibited in the Contractor's workplace and specifying the actions that will be taken against employees for violations of such prohibition.
- .2 The Contractor shall state in all solicitations or advertisements for employees placed by or on behalf of the Contractor that the Contractor maintains a drug-free workplace.
- .3 The Contractor will include the provisions of the foregoing clauses in every subcontract or purchase order of over \$10,000, so that the provisions will be binding upon each Subcontractor or vendor.

For the purposes of this section, "drug-free workplace" means a site for the performance of work done in connection with a specific contract awarded to a Contractor in accordance with the VPPA Section 2.2-4312, the employees of whom are prohibited from engaging in the unlawful manufacture, sale, distribution, dispensation, possession or use of any controlled substance or marijuana during the performance of the contract.

4.17 NON-DISCRIMINATION IN EMPLOYMENT

During the performance of this Contract, the Contractor agrees to comply fully with VPPA § 2.2-4201 and § 2.2-4343.1 as follows:

- .1 The Contractor will not discriminate against any employee or applicant for employment because of race, religion, disability, color, sex or national origin, except where religion, sex or national origin is a bona fide occupational qualification reasonably necessary to the normal operation of the Contractor and the Contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices setting forth the provisions of this nondiscrimination clause;
- .2 The Contractor, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, will state that such Contractor is an equal opportunity employer;
- .3 Notices, advertisements and solicitations placed in accordance with Federal law, rule or regulation, shall be deemed sufficient for the purpose of meeting the requirements of this provision; and
- .4 The Contractor will include the provisions of paragraphs .1, .2, .3 above in every subcontract or purchase order of over \$10,000 so that the provisions will be binding upon every Subcontractor or vendor.
- .5 The Contractor will comply with the requirements VPPA Section 2.2-4343.1, Permitted Contracts with Certain Religious Organizations, as applicable.

4.18 SIGNS

The Contractor may at his option and without cost to the Owner, erect signs acceptable to the Owner on the site of the Contract for the purpose of identifying and giving directions to the job. No signs shall be erected without prior approval of the Owner as to design and location.

4.19 CLEANING UP

- 4.19.1** The Contractor at all times shall keep the project site and all surrounding public streets and neighboring property free from accumulation of waste materials or rubbish caused by his operations. At the completion of the Work and before Final Payment is made, he shall remove all his waste materials and rubbish from and about the Project as well as all his tools, equipment and surplus materials. The Contractor shall also thoroughly clean and leave reasonably dust free all interior of all buildings included in the Contract, and thoroughly clean all glass installed under the Contract including the removal of all paint and mortar splatters and other defacements.
- 4.19.2** If the Contractor fails to clean up during or at the completion of the Work, the Owner may do so as provided in Article 6.3 "OWNER'S RIGHT TO PERFORM DISPUTED WORK" and the cost thereof shall be charged to the Contractor.
- 4.19.3** The Contractor shall take all reasonable steps, including but not limited to providing a wash down area, to prevent mud, dirt, and other material from accumulating upon the public streets.
- 4.19.4** During and at the completion of the Work, the Contractor shall prevent site soil erosion, the runoff of silt or debris carrying water from the site, and the blowing of debris off the site in accordance with the applicable requirements and standards of the Virginia Erosion and Sediment Control Handbook, latest edition, and the Contract Documents.

4.20 ROYALTIES AND PATENTS

- 4.20.1** Contractor shall pay all license fees and royalties and assume all costs incident to the use in the performance of the Work of any invention, design, process, product or device which is the subject of patent rights or copyrights held by others. If a particular invention, design, process, product or device is specified in the Contract Documents for use in the performance of the Work and if to the actual knowledge of the Owner or Owner's Project Manager its use is subject to patent rights or copyrights calling for the payment of any license fee or royalty to others, the existence of such rights shall be disclosed by Owner in the Contract Documents. Contractor shall indemnify, defend and hold harmless Owner and Owner's Project Manager and anyone directly or indirectly employed by either of them from and against all claims, damages, losses and expenses (including attorneys' fees) arising out of any infringement of patent rights or copyrights incident to the use in the performance of the Work of any invention, design, process, product or device not specified in the Contract Documents, and shall defend all such claims in connection with any alleged infringement of such rights.

4.21 ANTITRUST

By entering into a contract Contractor conveys sells assigns and transfers to the Owner all rights, title and interest in and to all causes of the action it now may have or hereafter acquire under the antitrust laws of the United States and the Commonwealth of Virginia, relating to the particular good(s) or service(s) purchased or acquired by the Owner under this contract.

4.22 INDEMNIFICATION

4.22.1 To the fullest extent permitted by law, the Contractor shall, at his sole cost and expense, indemnify, defend, and hold harmless the Owner, the Owner's Project Manager, their agents, representatives, employees, successors and assigns from and against all claims, actions, judgments, costs, liabilities, penalties, damages, losses and expenses, including but not limited to, attorneys' fees, arising out of or resulting from the performance of the Work, provided that any such claim, action, judgment, cost, liability, penalty, damage, loss or expense:

- .1 Is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the Work itself) including loss of use resulting therefrom; and
- .2 Is caused in whole or in part by any negligent act or omission of the Contractor, any Subcontractor or supplier, anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be liable, regardless of whether or not it is caused in part by a party indemnified hereunder.

The Contractor shall not be obligated to indemnify the Owner or the Owner's Project Manager hereunder for any damages or injuries, including death, the proximate cause of which is the sole negligence of the Owner or the Owner's Project Manager, consistent with Va. Code § 11-4.1.

Such obligation shall not be construed to negate, abridge, or otherwise reduce any other right or obligation of indemnity that would otherwise exist as to any party or person described in this Article 4.22

4.22.2 In any and all claims against the Owner and the Owner's Project Manager or any of their agents, representatives, or employees by any employee of the Contractor, any Subcontractor, anyone directly or indirectly employed by any of them, or anyone for whose acts any of them may be liable, the indemnification obligation under this Article 4.22 shall not be limited in any way by any limitation on the amount or type of damages, compensation or benefits payable by or for the Contractor or any Subcontractor under workers' compensation acts, disability benefit acts or other employee benefit acts.

4.22.3 No provision of Article 4.22 shall give rise to any duties on the part of the Owner or the Owner's Project Manager, or any of their agents, representatives or employees.

4.22.4 The obligations of the Contractor under Article 4.22 shall not extend to the liability of the Owner's Project Manager, or the Owner's design architect or engineers, their agents or employees arising out of (a) the preparation or approval of maps, drawings, opinions, reports, surveys, Change Orders, designs or specifications, or (b) the giving of or the failure to give directions or instructions by Owner's Project Manager, his agents or employees provided such giving or failure to give is the primary cause of injury or damage.

4.23 PERSONS AUTHORIZED TO SIGN DOCUMENTS

The Contractor, within five days after the earlier of the date of a Notice to Proceed or the date of the Owner/Contractor Agreement shall file with the Owner's Project Manager a list of all persons who are authorized to sign documents such as contracts, certificates and affidavits on behalf of the Contractor and to fully bind the Contractor to all the conditions and provisions of such documents.

4.24 ASBESTOS AND OTHER HAZARDOUS SUBSTANCES

4.24.1 Whenever and wherever during the course of performing any work under this contract, the Contractor discovers the presence of asbestos or other hazardous substances or suspects the presence of any hazardous substances, he shall stop the work immediately, secure the area, notify the Owner and await positive identification of the suspect material. During the downtime in such a case, the Contractor shall not disturb any surrounding surfaces but shall protect the area with suitable dust covers. In the event the Contractor is delayed due to the discovery of asbestos, suspected asbestos or any other hazardous or suspected hazardous substances, then a mutually agreed extension of time to perform the Work shall be allowed the Contractor.

4.24.2 Any claims for extension of time shall be subject to the provisions of Article 8.

4.24.3 If the items/products to be purchased are "Hazardous Substances" as defined by 15 U.S.C. § 1261, then the Contractor certifies and warrants that the items or products to be delivered under the Contract shall be properly labeled as required by the foregoing sections and that by delivering the items/products, the Bidder does not violate any of the prohibitions of 15 U.S.C. § 1263.

4.24.4 Material Safety Data Sheets (MSDS) and descriptive literature shall be

provided with the submittal or delivery of each chemical and/or compound subject to Article 4.24.3. Failure on the part of the Contractor to submit such data may be cause for termination in accordance with Article 14.3.

4.25 RIGHT TO PUBLISH

The Contractor otherwise agrees that he will not publish, cause to be published, or otherwise disseminate any information of any nature relating to the Work performed under this Contract, except as may be approved by the Owner in writing.

4.26 MATERIALS AND EQUIPMENT LIST

4.26.1 At least ten (10) working days before the start of construction the Contractor shall submit to the Project Manager for approval a complete list of materials and equipment proposed for use in connection with the project. Partial lists submitted from time to time will not be considered.

4.26.2 After any material or piece of equipment has been approved, no change in brand or make will be permitted unless satisfactory written evidence is presented to prove that the manufacturer cannot make scheduled delivery of the approved material, or that material delivered has been rejected and the substitution of a suitable material is an urgent necessity, or that other conditions have become apparent which indicate that approval of such other material is in the best interest of the Owner.

END OF ARTICLE 4

ARTICLE 5: SUBCONTRACTORS

5.1 DEFINITIONS

5.1.1 A Subcontractor is any firm, supplier, distributor or vendor that performs work for or furnishes services, equipment or supplies to or for the Contractor or another Subcontractor in conjunction with the Contract. The term Subcontractor is referred to throughout the Contract Documents as if singular in number and masculine in gender and means a Subcontractor or his authorized representative. Although the term Sub-subcontractor may appear within the Contract Documents, the term Subcontractor includes any person or entity that has a direct or indirect contract with the Contractor to perform any of the Work.

5.1.2 The Contractor shall be fully responsible to the Owner for all acts and omissions of his Subcontractors, and of persons and organizations directly or indirectly employed by them, and of persons and organizations for whose acts any of them may be liable, to the same extent that he is responsible for the acts and omissions of persons directly employed by him.

5.1.3 Nothing contained in the Contract Documents is intended to, nor shall it create, any contractual relationship between the Owner, the Owner's Project Manager, or any of their agents, consultants, employees, independent contractors, or representatives and any Subcontractor, but the Owner shall be entitled to performance of all obligations intended for its benefit, and to enforcement thereof.

5.1.4 The Owner's Project Manager will not deal directly with any Subcontractor. Communication will be made only through the Contractor. Subcontractors shall route requests for information or clarification through the Contractor to the Owner's Project Manager.

5.2 AWARD OF SUBCONTRACTS AND OTHER CONTRACTS FOR PORTIONS OF THE WORK

5.2.1 The Contractor shall within fourteen days after award of the Contract furnish to the Owner's Project Manager in writing the names of the persons or entities (including those who are to furnish materials or equipment fabricated to a special design) proposed for each of the principal portions of the Work. The Owner's Project Manager will promptly reply to the Contractor in writing stating whether the Owner has objection to any such proposed person or entity.

5.2.2 The Contractor shall not contract with any such proposed Subcontractor to whom the Owner has made objection under the provisions of Article 5.2.1. The Contractor shall not be required to contract with anyone to whom he has an objection.

5.2.3 If the Owner objects to any proposed Subcontractor under Article 5.2.1, the Contractor shall name a substitute to whom the Owner has no objection within fifteen days.

5.2.4 The Contractor shall make no substitution for any Subcontractor previously proposed by the Contractor and not objected to by the Owner's Project Manager if the Owner makes objection to such substitution.

5.3 SUBCONTRACTUAL RELATIONS

5.3.1 By an appropriate agreement, written where legally required for validity, the Contractor shall require each Subcontractor, to the extent of the Work to be performed by the Subcontractor, to be bound to the Contractor by the terms of the Contract Documents, and to assume toward the Contractor all the obligations and responsibilities that the Contractor, by these Documents, assumes toward the Owner.

This agreement shall preserve and protect the rights of the Owner under the Contract Documents with respect to the Work to be performed by the Subcontractor. The subcontracting will not prejudice such rights, and shall allow to the Subcontractor, unless specifically provided otherwise in the Contractor-Subcontractor Agreements, the benefit of all rights, remedies and redress against the Contractor that the Contractor, by these Contract Documents, has against the Owner. Where appropriate, the Contractor shall require each Subcontractor to enter into similar agreements with his Subcontractors.

The Contractor shall make available to each proposed Subcontractor, prior to the execution of the Subcontract, copies of the Contract Documents to which the Subcontractor will be bound by this Article 5.3, and identify to the Subcontractor any terms and conditions of the proposed Subcontract that may be at variance with the Contract Documents. Each Subcontractor shall similarly make copies of such Contract Documents available to his Sub-subcontractors or Suppliers.

5.3.2 The Contractor shall be liable to and indemnify, defend and hold the Owner harmless from all costs, expenses, fees, attorney's fees, accountant's fees, damages and claims arising because of the Contractor's failure to comply with the provisions of this Article 5.3.

5.4 QUALIFICATION SUBMITTALS

5.4.1 Specific qualification submittals may be required of Subcontractors for certain critical items of the Work. Required qualification submittals are set forth in detail in the Contract Documents and shall be collected and submitted by the Contractor to the Owner's Project Manager for review and approval by the

Owner and Owner's Project Manager. All information required of a single Subcontractor shall be contained in a single, complete submittal. The Contractor shall submit the required qualification information within ten days after receipt of the Owner's Project Manager's request.

5.4.2 The Owner may reject any proposed Subcontractor, or any qualification submittals related thereto, for the following reasons:

- .1 The Contractor's failure to submit requested information within the specified time; or
- .2 The Contractor's failure to provide all of the requested information; or
- .3 The Contractor's submission of a Subcontractor, or its qualifications, that are unacceptable to the Owner.

5.4.3 Should the Owner have objection to any proposed Subcontractor, the Contractor shall submit another firm for approval within fifteen days.

END OF ARTICLE 5

ARTICLE 6: WORK BY OWNER OR BY SEPARATE CONTRACTORS

6.1 OWNER'S RIGHT TO PERFORM WORK AND TO AWARD SEPARATE CONTRACTS

6.1.1 The Owner reserves the right to perform work related to the Project with its own forces, and to award separate contracts in connection with other portions of the Project or other work on the site.

6.1.2 When separate contracts are awarded for different portions of the Project or other work on the site, the term Contractor in the Contract Documents in each case shall mean the Contractor who executes each separate Owner/Contractor Agreement.

6.2 MUTUAL RESPONSIBILITY

6.2.1 The Contractor shall afford other Contractors and the Owner reasonable opportunity for the introduction and storage of their materials and equipment and the execution of their work and shall properly connect and coordinate the Work with that of the Owner and other Contractors, to store his tools, materials and equipment in such orderly fashion at the site of the Work as will not unduly or unreasonably interfere with the progress of the Work or the work of any other Contractors.

6.2.2 If the execution or result of any part of the Work depends upon any work of the Owner or of any separate Contractor, the Contractor shall, prior to proceeding with the Work, inspect and promptly report in writing to the Owner's Project Manager any apparent discrepancies or defects in such work of the Owner or of any separate Contractor that render it unsuitable for such proper execution or result of any part of the Work under this Contract.

6.2.3 Failure of the Contractor to so inspect and report shall constitute an acceptance of the Owner or separate Contractor's work as fit and proper to receive the Work, except as to defects that may develop in the Owner's or separate Contractor's work after completion of the Work, and that the Contractor could not have discovered by its inspection prior to completion of the Work under this Contract.

6.2.4 Should the Contractor cause damage to the Work or property of the Owner or of any separate Contractor on the Project, or to other work on the site, or delay or interfere with the Owner's work on ongoing operations or facilities or adjacent facilities of the Contractor's work, the Contractor shall be liable for the same and, in the case of another Contractor, the Contractor shall attempt to settle such claim with such Contractor prior to such other Contractor's institution of litigation.

6.3 OWNER'S RIGHT TO PERFORM DISPUTED WORK

6.3.1 If a dispute arises between the Contractor and separate Contractors as to their responsibility for cleaning up as required by Article 4.19 "CLEANING UP" or for accomplishing coordination as required by Article 6.4 "COORDINATION OF THE WORK," the Owner may carry out such Work and charge the cost thereof to the Contractors responsible therefor as the Owner's Project Manager shall determine.

6.4 COORDINATION OF THE WORK

6.4.1 By entering into this Contract, Contractor acknowledges that there may be separate Contractors on the Site whose work will be coordinated with that of his own. Contractor warrants and guarantees that he will cooperate with separate Contractors, and will do nothing to delay, hinder or interfere with the Work of other separate Contractors, the Owner or the Owner's Project Manager.

END OF ARTICLE 6

ARTICLE 7: MISCELLANEOUS PROVISIONS

7.1 GOVERNING LAW

7.1.1 The Contract shall be governed by the law of the Commonwealth of Virginia, and shall be performed in accordance with the laws, ordinances, regulations, permits and resolutions of the Town of Leesburg. The sole venue for any litigation under this Contract shall be the Circuit Court of Loudoun County, Virginia. The conflicts of law provisions shall not be employed to apply the laws of any state other than those of the Commonwealth of Virginia to this Contract.

7.1.2 Each provision of law required to be inserted in this Contract shall be deemed inserted. If through mistake or otherwise, any provision is not properly inserted, the Contract shall be modified to include such provision upon the application of either party.

7.1.3 Where applicable, the Contractor shall meet or exceed all requirements of the Town of Leesburg Design and Construction Standards Manual and all other local, state and federal building codes.

7.2 SUCCESSORS AND ASSIGNS

7.2.1 The Contractor binds himself, his partners, successors, assigns and legal representatives to the Owner, its partners, successors, assigns and legal representatives in respect to all covenants, agreements and obligations contained in the Contract Documents. The Contractor shall not assign the Contract or sublet it as a whole without the written consent of the Owner, nor shall the Contractor assign any monies due or to become due to him under the Contract, without the previous written consent of the Owner and the Contractor's Surety. Nor shall any contract be entered into or assigned to any party that is debarred from doing business with or in the Commonwealth of Virginia.

7.2.2 In the event the Contractor desires to make an assignment of all or part of the contract or any monies due or to become due under this Contract, the Contractor shall file a written consent of Surety, together with a copy of the proposed Assignment with the Owner or the Owner's Project Manager. In the event the Contractor assigns all or any part of the monies due or to become due under this Contract, the instrument or assignment shall state that the right of assignees in and to any monies due to or to become due to the Contractor shall be subject to prior liens and claims of all persons, firms and corporations that provided labor, services, or furnished material and equipment during the performance of the Work. The rights of assignees shall further be subject to the payment of any liens, claims or amounts due to Federal or State governments, and to all rights of retention and set-off granted to the Owner by the Contract Documents.

7.3 CLAIMS FOR DAMAGES

7.3.1 Should the Contractor suffer injury or damage to person or property because of any act or omission of the Owner or of any of its employees, agents or others for whose acts either is legally liable, claim shall be made in writing to the Owner within thirty days after the first observance of such injury or damage; otherwise, the Contractor shall have waived any and all rights he may have against the Owner, or its employees, representatives and agents.

7.4 DISPUTES

7.4.1 A claim, if any, shall be made in writing and submitted by the Contractor to the Owner, the Project Manager and the Leesburg Town Attorney within ten calendar days after the occurrence of events giving rise to the claim. A claim is limited to events rising out of or relating to the Contract. Failure to file a written claim as required herein shall constitute an absolute waiver of any claim of any sort.

7.4.2 The parties shall first endeavor to resolve any disputes, claims or other matters in question between them through direct negotiations, and if such direct negotiations fail, by non-binding mediation, with the site of the mediation being the Town of Leesburg, Virginia.

7.4.3 If the procedures of subparagraph 7.4.2 have been followed, but more than 90 days have passed since a party has requested mediation, and the dispute, claim or matter in question remains unresolved, then either party may institute a lawsuit in the Circuit Court of Loudoun County, Virginia, which is agreed to be the sole and exclusive venue, and may pursue all available appeals in Virginia state courts, to the extent they have jurisdiction.

7.4.4 Nothing in paragraphs 7.4.1 or 7.4.2 shall prevent a party from seeking temporary injunctive or other temporary equitable relief in the Loudoun County Circuit Court if circumstances so warrant.

7.4.5 In the event of any dispute, claim, or other matter in question arising, Contractor shall continue its performance diligently during its pendency as if no dispute, claim or other matter in question had arisen. During the pendency of any dispute in connection with the payment of moneys, Contractor shall be entitled to receive payments for non-disputed items.

7.4.6 Notwithstanding any other provision hereof, the Contractor expressly waives all claims against the Owner for consequential damages arising out of or relating to this Contract. This waiver includes losses of financing, business and reputation, bonding capacity, and loss of profit other than profit arising directly from the Work where otherwise permitted in the Contract.

7.5 TESTS

7.5.1 If the Contract Documents, laws, ordinances, rules, regulations or orders of any public authority having jurisdiction require any portion of the Work to be inspected, tested, or approved, the Contractor shall give the Owner's Project Manager five days notice of its readiness so the Owner's Project Manager may observe such inspection, testing, or approval. The Contractor shall bear all costs of such inspections, tests or approvals conducted by public authorities.

7.5.2 If the Owner's Project Manager determines that any Work requires special inspection, testing, or approval that Article 7.5.1 does not include, the Owner's Project Manager will order the Contractor to make arrangements for such special inspection, testing or approval, and the Contractor shall give the Owner's Project Manager five days notice of such inspection. If such special inspection or testing reveals a failure of the Work to comply with:

- .1 The requirements of the Contract Documents, or
- .2 The conformance of the Work with laws, ordinances, rules, regulations, or orders of any public authority having jurisdiction.

The Contractor shall bear all costs of the Work, including compensation for the Owner's Project Manager and any additional services made necessary by such failure.

7.5.3 Inspections and tests required under Article 7.5.2 to establish compliance with the Contract Documents will be made by a testing agency employed by the Owner. If the initial tests indicate non-compliance with the Contract Documents, the Contractor shall bear the costs thereof and any subsequent testing occasioned by non-compliance shall be performed by the same agency and the cost thereof shall be borne by the Contractor. Representatives of the testing agency shall have access to the Work at all times. The Contractor shall provide facilities for such access in order that the agency may properly perform its functions.

7.5.4 Certificates of inspection, testing or approval required by public authorities shall be secured by the Contractor and promptly delivered by him to the Owner's Project Manager, in adequate time to avoid delays in the Work or Final Payment.

7.5.5 The Contractor shall pay for and have sole responsibility for inspection or testing performed exclusively for his own convenience and for tests necessary because of Contractor's or Subcontractor's errors, omission, or noncompliance with Contract Documents.

7.5.6 All materials and workmanship (if not otherwise designated by the specifications) shall be subject to inspection, examination and test by the Owner or the Owner's Project Manager, at any time during the manufacture or construction and at any place where such manufacture or construction are carried on. Special, full-sized and performance tests shall be described in the specifications. Without additional charge, the Contractor shall furnish promptly all reasonable facilities, labor and materials necessary to make tests safe and convenient.

7.5.7 It is specifically understood and agreed that an inspection and approval of the materials or work by the Owner or the Owner's Project Manager shall not in any way subject the Owner to pay for the said materials or work or any portion thereof, even though incorporated in the Work, if said materials or work shall in fact turn out to be not in compliance with the Contract Documents or otherwise defective.

7.6 UNENFORCEABILITY OF ANY PROVISION

7.6.1 If any provision of this Contract is held as a matter of law to be unenforceable or unconscionable, the remainder of the Contract shall be enforceable without such provision.

7.7 AVAILABILITY OF LANDS

7.7.1 Owner shall furnish, as indicated in the Contract Documents, the lands upon which the Work is to be done, rights-of-way or easements for access thereto. The Owner reserves the right to delay the notice to proceed with the Contract Work in order to secure rights of way, easements or to relocate utilities, such as sewer, water, gas, electricity, cable television and other services.

7.7.2 If the Contractor requires additional land for temporary construction facilities and for storage of materials and equipment other than the areas available on the site or right-of-way, or as otherwise furnished by the Owner, the Contractor shall provide such other lands and access thereto entirely at the Contractor's own expense and without liability to the Owner. The Contractor shall not enter upon private property for any purpose without written permission. The contractor shall provide to the Owner evidence of written permission for entry onto private property for the purpose of temporary construction facilities and/or storage of materials and equipment.

7.8 NONEXCLUSIVITY OF REMEDIES

All remedies available to the Owner under the Contract are cumulative and no such remedy shall be exclusive of any other remedy available to the Owner.

END OF ARTICLE 7

ARTICLE 8: TIME

8.1 DEFINITIONS

8.1.1 The Contract Time is the period set forth in the Owner/Contractor Agreement for Final Completion of the Work as defined in Article 8.1.4, including authorized extensions thereto.

8.1.2 The date of commencement of the Work is the date established in the Notice to Proceed issued by the Owner.

Submission by the Contractor of all Certificates of Insurance, Performance and Payment Bonds and their approval by the Owner are conditions precedent to the issuance of the Notice to Proceed. Availability of lands under Article 7.7 is also a condition precedent to the issuance of the Notice to Proceed. The Contractor shall not commence the Work or store materials or equipment on site until written Notice to Proceed is issued or until the Contractor otherwise receives the written consent of the Owner.

8.1.3 The date of Substantial Completion of the Work or designated portion thereof is the date certified by the Owner's Project Manager that the Work or a designated portion thereof is sufficiently complete, in accordance with the Contract Documents, so the Owner can fully occupy or utilize the Work or designated portion thereof for the use for which it is intended, with all of the Project's parts and systems operable as required by the Contract Documents. Only punch list work and any final cleaning beyond that needed for the Owner's full use may remain for Final Completion.

8.1.4 The date of Final Completion of the Work is the date certified by the Owner's Project Manager when the Work is complete, to include punch list work and final clean up, in accordance with the Contract Documents and the Owner may fully occupy or fully utilize the Work for the use for which it is intended.

8.1.5 If the date or time of completion is included in the Contract, it shall be the Date of Final Completion as defined in Article 8.1.4, including authorized extensions thereto, unless otherwise provided.

8.1.6 The term Day as used in the Contract Documents shall mean calendar day unless otherwise specifically designated. All dates shall mean midnight of the indicated day unless otherwise stipulated.

8.2 PROGRESS AND COMPLETION

8.2.1 All time limits stated in the Contract Documents are of the essence of this Contract.

8.2.2 The Contractor shall prosecute the Work diligently to Final Completion.

8.3 DELAYS AND EXTENSIONS OF TIME

8.3.1 The time during which the Contractor is delayed in the performance of the Work, by the acts or omissions of the Owner, the Owner's Project Manager or their employees or agents, acts of God, unusually severe and abnormal climatic conditions, fires, floods, epidemics, quarantine restrictions, strikes (not to exceed the actual duration of the strike), riots, terrorism, civil commotions, war or freight embargoes, or other conditions beyond the Contractor's control and that the Contractor could not reasonably have foreseen and provided against, shall be added to the Contract Time; provided, however, that no claim by the Contractor for an extension of time for delays will be considered unless made in compliance with the requirements of this Article and other provisions of the Contract Documents.

8.3.2 The Contract Time shall be adjusted only for Change Orders pursuant to Article 12, "CHANGES IN THE WORK," Article 3.3, "OWNER'S RIGHT TO STOP OR SUSPEND THE WORK," and Article 8.3, "DELAYS AND EXTENSIONS OF TIME." If the Contractor requests an extension of the Contract Time, he shall furnish such justification and supporting evidence as the Owner's Project Manager may deem necessary for a determination of whether the Contractor is entitled to an extension of time under the provisions of the Contract.

8.3.3 The burden of proof to substantiate a claim for an extension of the Contract Time shall rest with the Contractor, including evidence that the cause was beyond his control. The Owner's Project Manager shall base his findings of fact and decision on such justification and supporting evidence and shall advise the Contractor in writing thereof.

8.3.4 The Contractor shall not be entitled to and hereby expressly waives any extension of time resulting from any condition or cause unless the request for an extension of time is made in writing to the Owner's Project Manager within seven days of the first instance of delay.

8.3.5 Any claim for an extension of time for a delay for any cause shall be made by filing a written notice of claim with the Owner and the Owner's Project Manager at the beginning of the occurrence or within seven days thereafter if the resulting delay was not reasonably foreseeable. If the asserted cause of delay is weather,

such notice shall be given within seven days after asserted commencement of the claim delayed. The notice of claim shall state the circumstances of the occurrence, the justification for the delay and for the extension of time, and the estimated duration of the delay and of the extension requested. The claim for an extension of time for weather delays shall be further substantiated by weather data collected during the period of delay at the construction site. Said data must demonstrate that an actual departure from normal weather occurred at the work site during the dates in question. Within seven days after the cause of delay has been remedied, the Contractor shall give written notice to the Owner and the Owner's Project Manager of the actual time extension requested as a result of the claimed delay. Failure to file either of the notices as required herein shall constitute an absolute waiver of any claims resulting from a delay or any sort.

The anticipated adverse weather days per month are shown in the chart below.

<u>Jan</u>	<u>Feb</u>	<u>Mar</u>	<u>Apr</u>	<u>May</u>	<u>June</u>	<u>July</u>	<u>Aug</u>	<u>Sept</u>	<u>Oct</u>	<u>Nov</u>	<u>Dec</u>
8	7	7	8	8	7	5	6	4	6	5	5

The above chart will constitute the base line for monthly weather time evaluations. Actual adverse weather days will be recorded on a calendar day basis (including holidays and weekends), and compared to the anticipated monthly adverse monthly days based on the above chart. The number of actual adverse weather days shall be calculated chronologically from the first day to the last day in each month.

- 8.3.6** Any extension of time beyond the date of completion fixed by the Contract shall not be effective unless granted in writing, signed by the Owner.
- 8.3.7** The Contractor shall be entitled to an extension of time for delay which in the opinion of the Owner is entirely beyond the expectation and control of the Contractor by suspension of work pursuant to Article 3, or by strikes, lockouts, fire, insurrection, war, lightning, hurricane, and tornado. The Contractor shall be entitled to an extension of time for such causes only for the number of days of delay that the Owner may determine to be due solely to such causes and only to the extent that such occurrences actually delay the completion of the Project. Any request for extension of time shall be accompanied by detailed documentation of which specific schedule activities were affected, when they were affected and for what duration.
- 8.3.8** No extension of time will be granted to the Contractor for delays occurring to parts of the Work that have no measurable impact on the competition of the total Work under this Contract; nor will extension of time be granted for delays to

parts of the Work that are not located on the Critical Path as reflected on the approved construction schedule at the time of such delay.

- 8.3.9** Delays in the delivery of equipment or material purchased by the Contractor or his Subcontractors (including Owner-selected equipment), or in the submission of required drawings or specifications by the Contractor's or its Subcontractor's materialmen, manufacturers or dealers, or in the performance of any of the Contractor's Subcontractors or caused by the performance of any of the Contractor's Subcontractors, shall not be considered as a just cause for delay. The Contractor shall be fully responsible for the timely submission, ordering, scheduling, expediting, delivery and installation of all equipment, materials and drawings.
- 8.3.10** Within sixty days after the Contractor files the notice of the actual duration of the extension of time as required herein, the Owner's Project Manager shall present his written opinion to the Owner as to whether an extension of time is justified, and, if so, his recommendation as to the number of days for time extension. The Owner will make the final decision on all requests for extension of time. The Owner's written decision shall be presented to the Contractor within thirty days from receipt of the Owner's Project Manager's recommendation. All such decisions made by the Owner shall be binding and conclusive upon the Contractor.
- 8.3.11** With respect to suspensions of work under Article 3, the Contractor may be entitled to an extension of time if the claim for such extension is submitted in accordance with the requirements of this Article, and if the suspension is not due to any act or omission of the Contractor, any Subcontractor or Sub-subcontractor or any other person or organization for whose acts or omission the Contractor may be liable.
- 8.3.12** An extension of time shall be the sole remedy under this Contract for any reasonable delay caused by any reason or occurrence. The Contractor acknowledges such extension of time to be its sole remedy hereunder, and agrees to make no claim for monetary damages of any sort for delay in the performance of this Contract occasioned by or in any way related to or arising from any act or omission to act of the Owner or the Owner's Project Manager or any representatives of the Owner or any representatives of the Owner's Project Manager, or because of any injunction which may be brought against the Owner or the Owner's Project Manager.
- 8.3.13** As a condition precedent to such additional compensation for unreasonable delay, the Contractor shall satisfy all notice and submission requirements set forth in the Contract Documents for approval of any extension of Contract Time or any change in the Contract Price.

8.3.14 If the Contractor asserts an unwarranted claim for additional compensation for unreasonable delay, the Contractor shall be liable to the Owner and shall pay the Owner all costs incurred by the Owner in investigating, analyzing, negotiating, and litigating the claim.

8.3.15 This Article shall be construed to be included where applicable in every portion of the Contract Documents regardless of whether or not it is specifically referenced therein.

END OF ARTICLE 8

ARTICLE 9: PAYMENTS AND COMPLETION

9.1 CONTRACT PRICE

9.1.1 Unless all or a part of the Contract is based on unit prices, the Contract Price is stated in the Contract and, including authorized adjustments thereto, is the firm, fixed price amount payable by the Owner to the Contractor for the performance of the Work under the Contract Documents. The Contract Price includes, but is not limited to, the Contractor's profits and general overhead and all costs and expenses of any nature whatsoever (including without limitation taxes, labor and materials), foreseen or unforeseen, and any increases in said costs and expenses, foreseen and unforeseen, incurred by the Contractor on this project. The Contractor agrees to assume all increases in costs of any nature whatsoever that may develop during the performance of the Work. The Contract Price includes all applicable Federal, State and local taxes and duties.

9.2 SCHEDULE OF VALUES

9.2.1 Within ten days after the Notice to Proceed is issued, the Contractor shall submit to the Owner's Project Manager a Schedule of Values, allocated to the various portions of the Work including mobilization and demobilization. This schedule, supported by data from the approved Progress Schedule, shall be used as a basis for the Contractor's Applications for Payment upon approval by the Owner's Project Manager. The Schedule of Values shall not alter in any way the firm, fixed price or lump sum contract price. The Contractor shall not front-end load or otherwise assign disproportionate amounts to the Schedule of Values.

9.2.2 If at any time the Contractor expects to receive an amount for a monthly progress payment larger than that indicated by the Schedule of Values and the approved Construction Schedule, the Contractor shall notify the Owner at least thirty days in advance of that payment so that the necessary allocation of funds can be processed. If the Contractor fails to give such notice, the Owner may defer such excess payment to the following progress payment.

9.2.3 With respect to any portion of the Contract subject to unit prices, the schedule of unit prices in the accepted bid shall be used as the basis for preparing Applications for Payment, and each partial payment shall represent the total value of all units of work completed, computed at the unit prices stated in the Contract, less the aggregate of previous payments and retainage. Final payment will be based on the actual quantities performed and justified on as-built drawings.

9.3 APPLICATIONS FOR PAYMENT

- 9.3.1** The Owner shall make progress payments monthly as the Work proceeds on Applications for Payment approved by the Owner's Project Manager.
- 9.3.2** Prior to the date for each progress payment established in the Contract, the Contractor, in accordance with any Supplementary Conditions concerning schedules or payments, shall submit to the Owner's Project Manager an itemized Application for Payment, supported by such data substantiating the Contractor's right to payment as the Owner's Project Manager may require, including but not limited to the Contractor's certification that all work for which payment is requested has been completed in full accordance with the Contract Documents, copies of requisitions from Subcontractors and reflecting retainage, if any, as provided elsewhere in the Contract Documents. The Contractor shall certify that he has paid all due and payable amounts for which previous Certificates for Payment were issued and payments received from the Owner.
- 9.3.3** The Owner will retain five percent of the amount of all progress payments until the Work is substantially completed and accepted, whether or not the Owner has occupied any or all of the Project before such time.
- 9.3.4** The Contractor warrants that title to all Work, materials and equipment covered by an Application for Payment will pass to the Owner either by incorporation in the construction or upon the receipt of payment by the Contractor, whichever occurs first, free and clear of all liens, claims, security interests or encumbrances, hereinafter referred to in this Article 9 as "LIENS". The Contractor further warrants that no Work, materials or equipment covered by an Application for Payment will have been acquired by the Contractor, or by any other person performing Work at the site or furnishing materials and equipment for the Project, subject to an agreement under which an interest therein or an encumbrance thereon is retained by the seller or otherwise imposed by the Contractor or such other person.
- 9.3.5** Unless otherwise provided in the specifications the Owner will make partial payments to the Contractor on the basis of a duly certified and approved estimate of the Work performed during the preceding calendar month as certified by the Owner's Project Manager.
- 9.3.6** The Contractor may, in preparing estimates, take into consideration the material delivered on site and preparatory work done, if properly documented as required by this Contract, or as may be required by the Owner or the Owner's Project Manager so that the quantities may be verified.
- 9.3.7** The Contractor may, in preparing estimates, take into consideration material such as large pieces of equipment and items purchased specifically for the project, but

stored off the site within the Commonwealth of Virginia, and these items may be considered for payment at the sole discretion of the Owner, provided that all of the following are accomplished prior to the submission of the monthly payment request in which payment for such materials is requested:

- .1 The Contractor must notify the Owner in writing at least ten days prior to the submission of the payment request, through the Owner's Project Manager, that specific items will be stored off site in a designated secure place within the Commonwealth of Virginia. The Schedule of Values must be detailed to separately indicate both the value of the material and of the labor/installation for trades requesting payment for stored materials. The Contractor warrants by giving such notification and by requesting payment for material stored off-site that the storage location is safe and suitable for the type of material stored and agrees that loss of such material shall not relieve him of the obligation to furnish these types and quantities of materials for the project and on a schedule to meet the time completion requirements of the Contract, subject to Article 8.
- .2 Such notification, as well as the payment request, shall:
 - a. itemize the quantity of such materials, and document with invoices the cost of said materials;
 - b. indicate the identification markings used on the materials. Such markings shall clearly reference the materials to the Project;
 - c. State the specific location of the materials. The location must be within reasonable proximity to the job site within the Commonwealth of Virginia;
 - d. State that the Surety on the Performance Bond and the Labor and Material Payment Bond has been notified of the request for payment of materials stored off the site and is agreeable to such payment;
 - e. Certify that adequate all-risk insurance has been obtained by the Contractor on the materials. Such insurance shall be in the name of the Owner and the Contractor.
- .3 The Owner's Project Manager shall indicate, in writing, to the Owner that submittals for such materials have been reviewed and meet the requirements of the drawings and specifications of the

Contract documents, that the stored materials meet the requirement of the drawings and specifications, and that such material conforms to the approved submittals.

- .4 The Owner, through the Owner's Project Manager, shall notify the Contractor in writing of his agreement to prepayment for materials.
- .5 The Contractor shall notify the Owner in writing, through the Owner's Project Manager, when the materials are to be transferred to the site and when the materials are received at the site.
- .6 No partial payment shall be made until the appropriate Certificates of Insurance have been provided.
- .7 All material and Work for which partial payments are made shall thereupon become the sole property of the Owner, but this provision shall not relieve the Contractor from the sole responsibility for all materials and Work, including those for which payment has been made, or the restoration of any damaged Work or as a waiver of the right of the Owner to require the fulfillment of all the terms of the Contract.

9.4 CERTIFICATES FOR PAYMENT

9.4.1 The Owner's Project Manager will within ten days after receipt of the Contractor's Application for Payment, either approve the Application for Payment for such amount as he determines is properly due, or notify the Contractor in writing of his reasons for not approving the Application for Payment as provided in Article 9.6 "PAYMENTS WITHHELD."

9.4.2 The submission and approval of the Progress Schedule and monthly updates thereof, as required by any Supplementary Conditions concerning Schedules, shall be part of the application upon which progress payment shall be made. The Contractor shall be entitled to progress payments only as determined from the currently Approved and Updated Progress Schedule.

9.5 PROGRESS PAYMENTS

9.5.1 After an Application for Payment has been approved by the Owner's Project Manager, the Owner shall make payment in the manner and within the time provided in the Contract Documents.

9.5.2 In accordance with Title 2.2-4354, Va. Code. Ann., Contractor is obligated to take one of the two following actions within seven (7) days after receipt of amounts paid to the Contractor by the Owner for work performed by any Subcontractor under this Contract:

- .1 Pay the subcontractor for the proportionate share of the total payment received from the Owner attributable to the Work performed by the Subcontractor under this Contract; or
- .2. Notify the Owner and the Subcontractor, in writing, of the Contractor's intention to withhold all or a part of the Subcontractor's payment with the reason for nonpayment.

The Contractor is obligated to provide its social security numbers and if a proprietorship, partnership, or corporation, they must provide its federal employer identification number.

The Contractor is obligated to pay interest to Subcontractors on all amounts owed by the Contractor that remain unpaid after seven (7) days following receipt by the Contractor of payment from the Owner for Work performed by the Subcontractor under this Contract, except for amounts withheld as allowed in Article 9.5.2.2, above. It is herewith provided that interest shall accrue at the base rate on corporate loans (prime rate) at large United States money center commercial banks as reported daily in the publication entitled The Wall Street Journal.

The Contractor shall include in each of its subcontracts a provision requiring each Subcontractor to include or otherwise be subject to the same payment and interest requirements with respect to each lower-tier Subcontractor.

The Contractor's obligation to pay an interest charge to a Subcontractor pursuant to the above provisions shall not be construed to be an obligation of the Owner. A Contract modification may not be made for the purpose of providing reimbursement for such interest charge. A cost reimbursement claim may not include any amount for reimbursement for such interest charge.

9.5.3 The Owner's Project Manager may, on request and at his discretion, furnish to any Subcontractor, if practicable, information regarding the percentages of completion or the amounts applied for by the Contractor, and the action taken thereon by the Owner's Project Manager on account of Work done by such Subcontractor.

9.5.4 The Owner has no obligation to pay or to see to the payment of any monies to any Subcontractor except as may otherwise be required by law.

9.5.5 No Application for Payment, nor any progress payment, nor any partial or entire use or occupancy of the Project by the Owner, shall constitute an acceptance of any Work that is not in accordance with the Contract Documents.

9.5.6 In the event of disputes, payment shall be mailed on or before the Payment date for amounts and Work not in dispute, subject to any set-offs claimed by the Owner; except in instances where further appropriations are required by the Owner or where the issuance of further bonds is required, in which case, payment shall be made within thirty days after the effective date of such appropriation or within thirty days after receipt of bond proceeds by the Owner.

9.6 PAYMENTS WITHHELD

9.6.1 The Owner's Project Manager may decline to approve the Application for Payment or reduce payment or because of subsequently discovered evidence or subsequent observations, he may nullify the whole or any part of any Application for Payment previously approved to such extent as may be necessary in his opinion to protect the Owner from loss, because of:

- .1 Defective Work not remedied;
- .2 Third party claims filed, whether in court, in arbitration or otherwise, or reasonable evidence indicating probable filing of such claims;
- .3 Failure of the Contractor to make payments properly to Subcontractors;
- .4 Reasonable evidence that the Work cannot be completed for the unpaid balance of the Contract Price;
- .5 Damage to the Owner or to a separate contractor;
- .6 Reasonable evidence that the Work will not be completed within the Contract Time, or within any Contract Milestones as established in the Contract Documents;
- .7 Failure or refusal of the Contractor to carry out the Work in accordance with or to otherwise substantially or materially comply with the Contract Documents;
- .8 Failure or refusal of the Contractor to properly schedule and coordinate the Work, or to provide Progress Schedules, reports and updates; and

.9 Failure or refusal of the Contractor to fully comply with the provisions of Article 4.13 "DOCUMENTS, OTHER SUBMITTALS AT THE SITE; AS-BUILT DRAWINGS."

9.6.2 When the above grounds in Article 9.6.1 are removed, payment shall be made for amounts withheld because of them.

9.7 SUBSTANTIAL COMPLETION

9.7.1 When the Contractor considers that the Work, or a designated portion thereof which is acceptable to the Owner's Project Manager, is substantially complete as defined in Article 8.1.3, the Contractor shall prepare for submission to the Owner's Project Manager a list of items that in his opinion are to be completed or corrected and shall request in writing that the Owner's Project Manager perform a Substantial Completion inspection. The Owner's Project Manager shall review the Contractor's list and will compile a punch list of items to be corrected and completed. The failure to include any items on such list does not alter the responsibility of the Contractor to complete all Work in accordance with the Contract Documents. When the Owner's Project Manager on the basis of an inspection determines that the Work or designated portion thereof is substantially complete, he will then prepare a Certificate of Substantial Completion that will establish the Date of Substantial Completion, state the responsibilities of the Owner and the Contractor for security, maintenance, heat, utilities, damage to the Work, and insurance, and shall fix the time within which the Contractor shall complete the items listed.

The Certificate of Substantial Completion shall be issued to the Contractor for his written acceptance of the responsibilities assigned to him in such Certificate and returned to the Owner's Project Manager within five days after issuance

9.7.2 The Contractor shall have thirty days from the Date of Substantial Completion to complete all items on the punch list to the satisfaction of the Owner's Project Manager. The Owner's Project Manager shall have the option to correct any and all punch list items not completed by the Contractor within thirty days from the Date of Substantial Completion by utilizing his own forces, those of the Owner, or by a separate Contractor. The cost of such correction of remaining punch list items by the Owner or others shall be deducted from the Final Payment to the Contractor.

9.7.3 The issuance of the Certificate of Substantial Completion does not indicate final acceptance of the Project by the Owner, and the Contractor is not relieved of any responsibility for the Project except as specifically stated in the Certificate of Substantial Completion.

9.7.4 Should the Owner's Project Manager determine that the Work or a designated portion thereof is not substantially complete, he shall provide the Contractor a written notice stating why the project or designated portion is not substantially complete. The Contractor shall expeditiously complete the Work and shall request in writing that the Owner's Project Manager perform a Substantial Completion reinspection and the costs, if any, associated with such reinspection shall be assessed to the Contractor.

9.8 FINAL COMPLETION AND FINAL PAYMENT

9.8.1 Upon receipt of the documentation required by Article 9.8.3, and of written notice that the Work is ready for final inspection and acceptance, the Owner's Project Manager will promptly make such inspection and, when he finds the Work acceptable under the Contract Documents and the Contract fully performed, he will issue a Certificate of Final Completion to the Contractor. Upon his receipt of the Final Completion Certificate, the Contractor may submit his Application for Final Payment to the Owner's Project Manager for his approval. Final Payment shall be made in full to the Contractor within thirty calendar days after the approval by the Owner's Project Manager of the Application for Final Payment provided that the requirements of Article 9 have been fulfilled, except for an amount agreed upon for any Work remaining uncompleted for which the Owner is entitled a credit under the Contract Documents.

9.8.2 Should the Owner's Project Manager determine that the Work or a designated portion thereof is not complete, he shall provide the Contractor a written notice stating why the Project or designated portion is not complete. The Contractor shall expeditiously complete the Work and shall request in writing that the Owner's Project Manager perform a Final Completion reinspection and the costs, if any, associated with such reinspection shall be assessed to the Contractor.

9.8.3 Neither the Final Payment nor the remaining retained percentage shall become due until the Work is free and clear of any and all Liens and the Contractor submits to the Owner's Project Manager:

- .1 An affidavit that all payrolls, bills for materials and equipment, and other indebtedness connected with the Work for which the Owner or its property might in any way be responsible, have been paid or otherwise satisfied;
- .2 Consent of surety to Final Payment, if necessary;
- .3 As-built drawings, operation and maintenance manuals and other project closeout submittals, as required by the Contract Documents;

- .4 A fully executed and notarized Release of claims in such form as may be designated by the Owner; and
- .5 A written certification that:
 - a. the Contractor has reviewed the requirements of the Contract Documents;
 - b. the Work has been inspected by the Contractor for compliance with all requirements of the Contract Documents;
 - c. pursuant to this inspection, the Contractor certifies and represents that the Work complies in all respects with the requirements of the Contract Documents;
 - d. the Contractor further certifies and represents that all equipment and systems have been installed and tested in accordance with the Contract Documents and the Owner personnel training in the proper operation and maintenance of equipment is complete; and
 - e. the Contractor provides construction releases as required by the Contract Documents from each property owner on whose property an easement for construction of this project has been obtained by the Owner, such release to be in the forms to be provided by the Owner. This release is for the purpose of releasing the Owner and the Contractor from liability, claims, and damages arising from construction operations on or adjacent to the easement and includes proper restoration of the property after construction. It shall be the Contractor's sole responsibility to obtain all such releases and furnish them to the Owner.

9.8.4 The making of Final Payment shall constitute a waiver of all claims by the Owner against the Contractor except those arising from:

- .1 Unsettled liens and claims against the Owner;
- .2 Faulty, defective or non-conforming Work discovered or appearing after Substantial or Final Completion;
- .3 Failure of Work to comply with the requirements of the Contract Documents; and

.4 Terms of any warranties contained in or required by the Contract Documents.

9.8.5 The acceptance of Final Payment shall constitute a waiver of all claims by the Contractor except those previously made in writing and identified by the Contractor as unsettled at the time of the Application for Final Payment.

9.8.6 Warranties required by the Contract Documents shall commence on the Date of Final Acceptance of the Work or designated portion thereof unless otherwise provided in writing.

9.9 PARTIAL OCCUPANCY OR USE

9.9.1 The Owner may occupy or use any completed or partially completed portion of the Work at any stage when such portion is designated by separate agreement with the Contractor, provided such occupancy or use is consented to by the insurer as required under Article 11.2.8 and authorized by public authorities having jurisdiction over the Work. Such partial occupancy or use may commence whether or not the portion is substantially complete, provided the Owner and the Contractor have accepted in writing the responsibilities assigned to each of them for payments, retainage, if any, security, maintenance, heat, utilities, damage to the Work and insurance, and have agreed in writing concerning the period for correction of the Work and commencement of warranties required by the Contract Documents. When the Contractor considers a portion substantially complete, the Contractor shall prepare and submit a list to the Owner's Project Manager as provided under Article 9.7. Consent of the Contractor to partial occupancy or use shall not be unreasonably withheld. The stage of the progress of the Work shall be determined by written agreement between the Owner's Project Manager and the Contractor or, if no agreement is reached, by decision of the Owner's Project Manager.

9.9.2 Immediately prior to such partial occupancy or use, the Owner or the Owner's Project Manager, and the Contractor shall jointly inspect the area to be occupied or portion of the Work to be used in order to determine and record the condition of the Work.

9.9.3 Unless otherwise agreed upon, partial occupancy or use of a portion or portions of the Work shall not constitute acceptance of Work not complying with the requirements of the Contract Documents.

END OF ARTICLE 9

ARTICLE 10: PROTECTION OF PERSONS AND PROPERTY

10.1 SAFETY PRECAUTIONS AND PROGRAMS

10.1.1 The Owner and the Owner's Project Manager are not responsible for the means, methods, techniques, sequences or procedures utilized by the Contractor, or for safety precautions and programs in connection with the Work. The Contractor shall be solely responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the Work. This requirement applies continuously throughout the Contract performance, until Final Payment is made, and is not limited to regular working hours.

10.2 SAFETY OF PERSONS AND PROPERTY

10.2.1 The Contractor shall take reasonable precautions for safety of, and shall provide reasonable protection to prevent damage, injury or loss, to:

- .1 All employees on the Work and other persons who may be affected thereby;
- .2 All the Work and materials and equipment to be incorporated therein whether in storage off the site, under the care, custody or control of the Contractor or any of his Subcontractors, machinery and equipment. The Contractor shall comply with, and ensure that the Contractor's personnel and subcontracted personnel comply with all current applicable local, state and federal policies, regulations and standards relating to safety and health, including, by way of illustration and not limitation, the standards of the Virginia Occupational Safety and Health Administration for the General Industry and for the Construction Industry, the Federal Environmental Protection Agency Standards, the Manual of Accident Prevention in Construction published by the Associated General Contractors of America and the applicable standards of the Virginia Department of Environmental Quality.
- .3 Other property at or adjacent to the Work, including trees, shrubs, lawns, walks, pavements, roadways, structures and utilities not designated for removal, relocation or replacement in the course of construction.

10.2.2 The Contractor shall give all notices and comply with applicable laws, ordinances, permits, rules, regulations and orders of any public authority bearing on the safety of persons or property or their protection from damage, injury or loss.

- 10.2.3** The Contractor shall at all times safely guard the Owner's property from injury or losses in connection with this Contract. He shall at all times safely guard and protect his own work and adjacent property as provided by law and the Contract Documents from damage. All security personnel, passageways, guard fences, lights, and other facilities required for protection of the property and the Work described herein shall be provided and maintained at the Contractor's expense.
- 10.2.4** The Contractor shall erect and maintain, as required by existing conditions and progress of the Work, all reasonable safeguards for safety and protection, including danger signs and other warnings against hazards, promulgating safety regulations and notifying owners and users of adjacent utilities.
- 10.2.5** When the use or storage of explosives or other hazardous materials or equipment is necessary for the execution of the Work, the Contractor shall exercise the utmost care and shall carry on such activities under the supervision of properly qualified personnel.
- 10.2.6** The Contractor shall promptly remedy at his own cost and expense all damage or loss to any property referred to in Articles 10.2.1.2 and 10.2.1.3. The Contractor shall perform such restoration by underpinning, repainting, rebuilding, replanting, or otherwise restoring as may be required or directed by the Owner's Project Manager or shall make good such damage in a satisfactory and acceptable manner. In case of failure on the part of the Contractor to promptly restore such property or make good such damage, the Owner may, upon two days written notice, proceed to repair, rebuild or otherwise restore such property as may be necessary, and the cost thereof will be deducted from any monies due or to become due to the Contractor under the Contract.
- 10.2.7** The Contractor shall give notice in writing at least 48 hours before breaking ground, to the Owner, all persons, Public Utility Companies, superintendents, inspectors or those otherwise in charge of property, streets, water pipes, gas pipes, sewer pipes, telephone cables, electric cables, railroads or otherwise, who may be affected by the Contractor's operation, in order that they may remove any obstruction for which they are responsible and have a representative on site to see that their property is properly protected. The Contractor is responsible for any damages or claims resulting from any excavation and shall defend, fully indemnify, and hold harmless the Owner from all actions resulting from such work regardless of whether the Contractor gave proper notice under this clause.
- 10.2.8** The Contractor shall protect all utilities encountered while performing its work, whether indicated on the Contract Documents or not. The Contractor shall maintain utilities in service until moved or abandoned. The Contractor shall exercise due care when excavating around utilities and shall restore any damaged utilities to the same condition or better as existed prior to starting the Work, at no cost to the Owner. The Contractor shall maintain operating utilities or other

services, even if they are shown to be abandoned on the Contract Drawings, in service until new facilities are provided, tested and ready for use.

- 10.2.9** The Contractor shall return all improvements on or about the site and adjacent property that are not shown to be altered, removed or otherwise changed to conditions that existed prior to starting work.
- 10.2.10** The Contractor shall protect the Work, including but not limited to, the site, stored materials and equipment, excavations, and excavated or stockpiled soil or other material, intended for use in the Work, and shall take all necessary precautions to prevent or minimize damage to same or detrimental effect upon his performance or that of his Subcontractors, caused by or due to rain, run-off, floods, temperature, wind, dust, sand, and flying debris. For example, but not by way of limitation, Contractor shall, when necessary, utilize temporary dikes, channels or pumping to carry-off, divert or drain water, and as necessary tie-down or otherwise secure the Work and employ appropriate covers and screens.
- 10.2.11** The Contractor shall be responsible for the prevention of accidents and the protection of material, equipment and property.
- 10.2.12** The Contractor shall not load or permit any part of the Work to be loaded so as to endanger the safety of the Work, persons or adjacent property.
- 10.2.13** The Contractor has sole and complete responsibility for the correction of any safety violation and sole liability for the consequences of the violation. The Contractor shall give prompt written notice of any safety violation to the Owner's Project Manager.
- 10.2.14** The Contractor shall provide, or cause to be provided, all technical expertise, qualified personnel, equipment, tools and material to safely accomplish the Work, specified to be performed by the Contractor and Subcontractor(s).
- 10.2.15** The Contractor shall be responsible for the preservation of all public and private property, trees, monuments, etc., along and adjacent to the street and/or right-of-way, and shall use every precaution to prevent damage to pipes, conduits and other underground structures, curbs, pavements, etc., except those to be removed or abandoned in place and shall protect carefully from disturbance or damage all monuments and property marks until an authorized agent has witnessed or otherwise referenced their location and shall not remove them until directed. Any damage which occurs by reason of the operations under this Contract shall be completely repaired by the Contractor at the Contractor's expense.
- 10.2.16** The Contractor shall shore, brace, underpin, secure, and protect, as may be necessary, all foundations and other parts of existing structures adjacent to,

adjoining, and in the vicinity of the site that may be affected in any way by excavations or other operations connected with the Work contained in this Contract. The Contractor shall be responsible for the giving of any and all required notices to any adjoining or adjacent property owned or other party before commencement of any Work. The Contractor shall indemnify and save the Owner harmless from any damages on account of settlements or loss of all damages for which the Owner may become liable in consequence of such injury or damage to adjoining and adjacent structures and their premises.

10.2.17 The Contractor shall identify to the Owner's Project Manager at least one on-site person who is the Contractor's competent, qualified, and authorized person on the worksite and who is, by training or experience, familiar with policies, regulations and standards applicable to the Work being performed. The competent, qualified and authorized person must be capable of identifying existing and predictable hazards in the surroundings or working conditions which are unsanitary, hazardous or dangerous to employees, shall be capable of ensuring that applicable safety regulations are complied with, and shall have the authority and responsibility to take prompt corrective measures, which may include removal of the Contractor's personnel from the work site.

10.2.18 The Contractor shall provide to the Owner's Project Manager, a copy of the Contractor's written safety policies and safety procedures applicable to the Work within seven (7) days of the issuance of the Notice to Proceed.

10.3 EMERGENCIES

10.3.1 In any emergency affecting the safety of persons or property, the Contractor shall act to prevent threatened damage, injury, or loss to the Owner. The Contractor shall notify the Owner's Project Manager of the situation and all actions taken immediately thereafter. If, in the opinion of the Contractor, immediate action is not required, the Contractor shall notify the Owner's Project Manager of the emergency situation and take necessary steps. If any loss, damage, injury or death occurs that could have been prevented by the Contractor's prompt and immediate action or the emergency resulted from acts or omissions of the Contractor or his Subcontractors, or anyone directly or indirectly employed by any of them, or by anyone whose acts any of them may be liable, the Contractor shall defend, fully indemnify and hold harmless the Owner (including attorneys' fees) from all actions resulting from the emergency. Any additional compensation or extension of time claimed by the Contractor on account of emergency work shall be determined as provided in Article 12 "CHANGES IN THE WORK."

10.3.2 Prior to commencing his work and at all times during the performance of the Work, the Contractor shall provide the Owner with two, 24-hour emergency phone numbers where his representatives can be contacted.

END OF ARTICLE 10

ARTICLE 11: BONDS AND INSURANCE

11.1 BONDS

- 11.1.1** The Contractor shall furnish to the Owner a performance bond in the sum of the contract price executed by a surety authorized to do business in Virginia, payable to the Town of Leesburg, Virginia, or such other entity as may be identified in the Contract, and conditioned upon the faithful performance of the contract in strict conformity with the plans, specifications, and conditions of the Contract Documents.
- 11.1.2** The Contractor shall furnish to the Owner a payment bond in the amount of the contract price payable to the Town of Leesburg or such other entity as may be identified in the Contract, and executed by a surety authorized to do business in Virginia. Such bond shall be conditioned on the prompt payment to all claimants who have and fulfill contracts to supply labor or materials to the Contractor for all material furnished or labor supplied or performed in the prosecution of the Work. "Labor and materials" shall include public utility services and reasonable rentals of equipment, but only for periods when the equipment rented is actually used at the project site.
- 11.1.3** If the amount of all Work subcontracted to any one Subcontractor is in excess of \$10,000, the Contractor may at his option require the Subcontractor to furnish a Labor and Material Payment Bond with surety thereon, in the amount of fifty percent of the amount of the Subcontract.
- 11.1.4** The Contractor shall ensure that all sureties providing bonds for the Project will give written notice to the Owner, at least thirty days prior to expiration or termination of the bond(s).
- 11.1.5** If the surety on any Bond furnished by the Contractor is declared bankrupt or becomes insolvent or its right to do business is terminated in any state where any part of the Project is located, the Contractor shall within five days thereafter substitute another Bond and surety, both of which shall be acceptable to the Owner.
- 11.1.6** If at any time, the Owner shall be or become dissatisfied with any surety or sureties then upon the Performance and Labor and Materials Payment Bonds, or if for any other reason, such bond shall cease to be adequate security to the Owner, the Contractor shall within five days after notice from the Owner to do so, substitute an acceptable bond(s) in such form and sum and signed by such other sureties as may be satisfactory to the Owner. The premium on such bond(s) shall be paid by the Contractor. No further payment shall be deemed due nor shall be made until the new sureties have been qualified and accepted by the Owner.
- 11.1.7** If more than one surety executes a bond, each shall be jointly and severally liable to the Owner for the entire amount of the bond.

11.2 CONTRACTOR'S LIABILITY INSURANCE

11.2.1 The Contractor shall provide to the Owner, a Certificate of Insurance indicating that the Contractor has in force the coverage below prior to the start of any Work under this Contract. The Contractor agrees to maintain such insurance until the completion of this Contract. All required insurance coverages must be acquired from insurers authorized to do business in the Commonwealth of Virginia and acceptable to the Owner. The minimum insurance coverage shall be:

- .1 Workers Compensation Insurance – as required by federal, state, and municipal laws for the protection of all Contractors' employees working on or in connection with the project, shall be in accordance with Title, 2.2-4332, Va. Code Ann.
- .2 Comprehensive General Liability Bodily Injury and Property Damage: \$3,000,000 combined single limit/each occurrence in the primary policy or through the use of Umbrella or Excess Limits.

The General Liability Insurance shall include the following coverages; comprehensive form, premises-operations, explosion and collapse hazard, underground hazard, products/completed operations hazard, contractual liability insurance, broad form property damage including completed operations, contractors protective liability, personal injury (all insuring agreements) deleting the employee exclusion, and owners protective liability.

- .3 Contractor's Automobile Liability (Bodily Injury and Property Damage):

\$3,000,000 combined single limit per occurrence in the primary policy or through the use of Umbrella or Excess Limit

The Automobile Liability Insurance shall include the following coverages; comprehensive form, owned, hired, and non-owned.

- .4 Property insurance written on a builder's risk "all-risk" or equivalent policy form in the amount of the initial Contract Sum, plus value of subsequent Contract modifications and cost of materials supplied or installed by others, comprising total value for the entire Project at the site on a replacement cost basis without optional deductibles. Such property insurance shall be maintained, unless otherwise provided in the Contract Documents or otherwise agreed in writing by all persons and entities who are beneficiaries of such insurance, until final payment has been made as provided in Article 9.8 or until no person or entity other than the Owner has

an insurable interest in the property required by this Article 11.5 to be covered, whichever is later. This insurance shall include interests of the Owner, the Contractor, Subcontractors and Sub-subcontractors in the Project. The property insurance shall be on an "all-risk" or equivalent policy form and shall include, without limitation, insurance against the perils of fire (with extended coverage) and physical loss or damage including, without duplication of coverage, theft, vandalism, malicious mischief, collapse, earthquake, flood, windstorm, falsework, testing and startup, temporary buildings and debris removal including demolition occasioned by enforcement of any applicable legal requirements.

If the liability insurance purchased by the Corporation has been issued on a "claims made" basis, the Corporation must comply with the following additional conditions. The limits of liability and the extensions to be included as described previously in these provisions, remain the same.

The Corporation must either:

1. Agree to provide certificates of insurance evidencing the above coverage for a period of two (2) years after final payment for the Agreement for General Liability policies. This certificate shall evidence a "retroactive date" no later than the beginning of the Corporation's work under this Agreement, or
2. Purchase the extended reporting period endorsement for the policy or policies in force during the term of this Agreement and evidence the purchase of this extended reporting period endorsement by means of a certificate of insurance or a copy of the endorsement itself.

11.2.2 Additional Insured – The Owner, its officers, elected and appointed officials, and employees shall be named as an additional insured in the Contractor's Commercial General Liability policy; evidence of the Additional Insured endorsement shall be typed on the certificate and a copy of the additional insured endorsement shall be forwarded to the Owner along with the copy of the insurance certificate.

11.2.3 Contract Identification – The insurance certificate shall state this Contract's number and title.

11.2.4 The Contractor shall secure and maintain until all work required under the Contract is accepted, such insurance as will protect the Contractor and the Owner from claims directly or indirectly arising or alleged to arise out of the performance of, or failure to perform the Work, or the condition of the Work or the jobsite, from claims by workers, suppliers, Subcontractors, and the general public; from claims made under safe place laws, or any law with respect to protection of adjacent landowners; and from any other claims for damages to property from operations by the Contractor or any Subcontractor,

or anyone directly or indirectly employed by either of them.

The Contractor assumes all risks for direct and indirect damage or injury to the property or persons used or employed on or in connection with the Work contracted for, and of all damage or injury to any person or property wherever located, resulting from any action, omission, commission or operation under the Contract, or in connection in any way whatsoever with the contracted Work.

No acceptance or approval of any insurance by the Owner shall be construed as relieving or excusing the Contractor from any liability or obligation imposed upon the Contractor by the provisions of the Contract Documents.

- 11.2.5** These certificates and the insurance policies required by Article 11.2 shall contain a provision that coverages afforded under the policies will not be canceled or allowed to expire until at least thirty days prior written notice has been given to the Owner. If any of the foregoing insurance coverages are required to remain in force after final payment and are reasonably available, an additional certificate evidencing continuation of such coverage shall be submitted with the final Application for Payment as required by Article 9.8. Information concerning reduction of coverage on account of revised limits or claims paid under the General Aggregate, or both, shall be furnished by the Contractor with reasonable promptness in accordance with the Contractor's information and belief.
- 11.2.6** Neither the Owner nor the Owner's Project Manager shall have any obligation to review any Certificates of Insurance provided by the Contractor or to check or verify the Contractor's compliance with any and all requirements regarding insurance imposed by the Contract. The Contractor is fully liable for the amounts and types of insurance required herein and is not excused should any policy or Certificate of Insurance provided by the Contractor not comply with the Contract's insurance requirements.
- 11.2.7** If the Contractor fails to comply with the Contract's insurance requirements, the Owner shall be entitled to recover all amounts payable as a matter of law to the Owner or any other parties, including but not limited to the Owner's Project Manager, had the insurance coverage been in effect. Any recovery shall include but is not limited to interest for the loss of the use of such amounts of money, attorneys' fees, costs and expenses incurred in securing such determination and any other consequential damages.
- 11.2.8** Partial occupancy or use in accordance with Article 9.9 shall not commence until the insurance company or companies providing property insurance have consented to such partial occupancy or use by endorsement or otherwise. The Owner and the Contractor shall take reasonable steps to obtain consent of the insurance company or companies and shall, without mutual written consent, take no action with respect to partial occupancy or use that would cause cancellation, lapse or reduction of insurance.

11.3 WAIVERS OF SUBROGATION

11.3.1 The Owner and Contractor waive all rights against (1) each other and any of the Subcontractors, Sub-subcontractors, agents and employees, each of the other, and (2) the Owner's Project Manager and Engineer or Architect or their consultants, separate contractors, if any, and any of their Subcontractors, Sub-subcontractors, agents and employees, for damages caused by fire or other causes of loss to the extent covered by property insurance obtained pursuant to this Article 11.5 or other property insurance applicable to the Work, except such rights as they have to proceeds of such insurance held by the Owner as fiduciary. The Owner or Contractor, as appropriate, shall require of his consultants, separate contractors, if any, and the Subcontractors, Sub-subcontractors, agents and employees of any of them, by appropriate agreements, written where legally required for validity, similar waivers each in favor of other parties enumerated herein. The policies shall provide such waivers of subrogation by endorsement or otherwise. A waiver of subrogation shall be effective as to a person or entity even though that person or entity would otherwise have a duty of indemnification, contractual or otherwise, did not pay the insurance premium directly or indirectly, and whether or not the person or entity had an insurable interest in the property damaged.

11.4 ADDITIONAL INSURANCE PROVISIONS

11.4.1 A loss insured under Owner's property insurance shall be adjusted by the Owner as fiduciary and made payable to the Owner as fiduciary for the insureds, as their interests may appear, subject to requirements of any applicable mortgagee clause and of Article 11.5.10. The Contractor shall pay Subcontractors their just shares of insurance proceeds received by the Contractor, and by appropriate agreements, written where legally required for validity, shall require Subcontractors to make payments to their Sub-subcontractors in similar manner.

11.4.2 If required in writing by a party in interest, the Owner as fiduciary shall, upon occurrence of an insured loss, give bond for proper performance of the Owner's duties. The cost of required bonds shall be charged against proceeds received as fiduciary. The Owner shall deposit in a separate account proceeds so received, which the Owner shall distribute in accordance with such agreement as the parties in interest may reach. If after such loss no other special agreement is made and unless the Owner terminates the Contract for convenience, replacement of damaged property shall be performed by the Contractor after notification of a Change in the Work in accordance with Article 12.

11.4.3 The Owner as fiduciary shall have power to adjust and settle a loss with insurers unless one of the parties in interest shall object in writing within five days after occurrence of loss to the Owner's exercise of this power; if such objection is made, the dispute shall be resolved as provided in Article 7.4. The Owner as fiduciary shall, in the case of disputes, make settlement with insurers in accordance with orders of the Court.

END OF ARTICLE 11

ARTICLE 12: CHANGES IN THE WORK

12.1 CHANGES IN THE WORK

12.1.1 The Owner, without invalidating the Contract and without notice to the surety, may order a Change in the Work consisting of additions, deletions, modifications or other revisions to the general scope of the Contract, or changes in the sequence of the performance of the Work. The Contract Price and the Contract Time shall be adjusted accordingly. All such Changes in the Work shall be authorized by written Change Order, and all Work involved in a Change shall be performed in accordance with the terms and conditions of this Contract. If the Contractor should proceed with a Change in the Work upon an oral order, by whomever given, it shall constitute a waiver by the Contractor of any claim for an increase in the Contract Price or Contract Time, on account thereof.

12.1.2 When the Owner and the Contractor have agreed upon a Change in the Work, but a written Change Order Document has not yet been executed, the Owner may, at its sole discretion and option, direct in writing the Contractor to proceed with the Change in the Work pending the execution of the formal Change Order. Contractor shall proceed in accordance with such direction.

12.1.3 The Contractor shall not begin work on any alteration requiring a modification until such modification has been executed by the Owner and the Contractor. If a satisfactory agreement cannot be agreed to for any item requiring a modification, the Owner reserves the right to terminate the contract as it applies to the items in question and make such arrangements as may be deemed necessary to complete the Work.

12.2 FIELD ORDER

12.2.1 A Field Order is a written order to the Contractor signed by the Owner or the Owner's Project Manager interpreting or clarifying the Contract Documents or directing the Contractor to perform minor changes in the Work. Any work relating to the issuance of a Field Order shall be performed promptly and expeditiously and without additional cost to the Owner and within the Contract Time, unless the Contractor submits a Proposed Change Order, defined below, which is approved by the Owner. Field Orders shall be numbered consecutively by date of issuance by the Owner or the Owner's Project Manager.

12.3 REQUEST FOR PROPOSAL

12.3.1 A Request For Proposal (“RFP”) describes a proposed Change in the Work. In response to a Request for Proposal issued by the Owner or the Owner’s Project Manager, the Contractor is required to submit a complete Proposal for the total cost and additional time, if any, necessary to perform the proposed Change in the

Work. Requests For Proposals shall be numbered consecutively by date of issuance by the Owner or the Owner's Project Manager.

12.3.2 The Contractor's Proposal in response to an RFP shall be in the form prescribed by the Owner's Project Manager, including all appropriate back-up material.

12.4 PROPOSED CHANGE ORDER

12.4.1 A Proposed Change Order is a written request from the Contractor to the Owner requesting a change in the Contract Price and/or Contract Time. A Proposed Change Order may be submitted as a proposal in response to a Request For Proposal issued by the Owner or as a claim for an increase in the Contract Price and/or Contract Time pursuant to the issuance of a Field Order. A Proposed Change Order must be submitted within twenty days of the issuance of a Request For Proposal or a Field Order. Proposed Change Orders shall be numbered consecutively by date of issuance by the Contractor. The Contractor shall also indicate on the Proposed Change Order the number of the Request For Proposal or the Field Order to which it responds.

12.4.2 If a Request for Proposal provides for an adjustment to the Contract Price, the adjustment shall be based on one of the following methods:

- .1 mutual acceptance of a lump sum properly itemized and supported by sufficient substantiating data to permit evaluation;
- .2 unit prices stated in the Contract Documents or subsequently agreed upon;
- .3 cost to be determined in a manner agreed upon by the parties and a mutually acceptable fixed or percentage fee; or
- .4 as provided in Articles 12.5.3 and 12.5.4.

12.4.3 If it is necessary in this subparagraph to increase the Contract Time to perform the Change in the Work, the Contractor shall provide an estimate of the increase in the Contract Time which shall be negotiated by the parties to the Contract. The Contractor's request for a time extension shall be evaluated in accordance with the criteria described in Article 8.

12.4.4 If the Contractor's Proposed Change Order is rejected by the Owner as being within the scope of the Work required by the Contract Documents the Owner may, at its sole option and discretion, direct the Contractor to perform the Work which is the subject of the Proposed Change Order; the Contractor shall then promptly proceed with the Work. Nothing shall excuse the timely performance by the Contractor of the Work because any Proposed Change Order is pending.

12.5 CHANGE ORDER

12.5.1 A Change Order is a written order to the Contractor signed by the Contractor and the Owner's Project Manager, issued after execution of the Contract, authorizing a Change in the Work or an adjustment in the Contract Price and/or the Contract Time. The Contract Price and the Contract Time may be changed only by Change Order. A Change Order signed by the Contractor indicates his agreement therein, including the adjustment in the Contract Price and/or the Contract Time. Change Orders shall be numbered consecutively by date of issuance by the Owner or the Owner's Project Manager and shall, if applicable, indicate the number of the Field Order(s), Request For Proposal(s) and/or Proposed Change Order(s) to which it relates.

12.5.2 If the Owner and the Owner's Project Manager determine that the Contractor's Proposed Change Order, submitted pursuant to Article 12.4 for a change in the Contract Price or Contract Time, is acceptable, the Owner's Project Manager shall prepare and issue, or cause to be prepared and issued, a Change Order which will authorize the Contractor to proceed with the Change in the Work for the cost and time stated in the Proposed Change Order, or as otherwise may be agreed upon by the parties. The amounts stated in the Change Order for the cost and time to perform the Change in the Work shall be binding on the parties.

.1 The contractors markup for allowable profit and overhead shall be limited to 10%.

12.5.3 After issuance of the Change Order, the Contractor shall ensure that the amount of the Performance and Payment Bond coverage has been revised to reflect the increase in the Contract Price due to the Change Order.

12.5.4 If the Contractor's Proposed Change Order is not acceptable to the Owner and the Owner's Project Manager or if the parties are unable to otherwise agree as to the cost and time necessary to perform the Change in the Work, the Owner may, at its sole option and discretion, direct the Contractor to perform the Work on a time and material basis. The Contractor shall then promptly proceed with the Work.

12.5.5 If the Owner and the Owner's Project Manager elect to have the Change in the Work performed on a time and material basis, the same shall be performed, whether by the Contractor's forces or the forces of any of his Subcontractors or Sub-subcontractor's, at actual cost to the entity performing the Change in accordance with the time and material provisions included in the Road and Bridge Specifications of the Virginia Department of Transportation, current edition.

12.5.6 Prior to starting the work on a time and material basis, the Contractor shall notify the Owner's Project Manager in writing as to what labor, materials, equipment or

rentals are to be used for the Change in the Work. During the performance of the Change, the Contractor shall submit to the Owner daily time and material tickets, which shall list the categories and amounts of labor and equipment for which Change Order compensation is to be charged for the previous work day. Such tickets shall be submitted in strict accordance with the time and material provisions included in the Road and Bridge Specifications of the Virginia Department of Transportation.

- 12.5.7** The Contractor shall commence submission of daily time and material tickets immediately upon commencement of the Change Order Work and continue to submit them until completion of the Change Order Work. The Owner may require authentication of all time and material tickets and invoices by persons designated by the Owner for such purpose.
- 12.5.8** The failure of the Contractor to provide any required authentication shall, if the Owner elects to treat it as such, constitute a waiver by the Contractor of any claim for the cost of that portion of the Change in the Work covered by a non-authenticated ticket or invoice; provided, however, that the authentication of any such ticket or invoice by the Owner shall not constitute an acknowledgment by the Owner that the items thereon were reasonably required for the Change in the Work.
- 12.5.9** The Contractor shall submit his complete submission of the reasonable actual cost and time to perform the Change in the Work within twenty days of the request of the Owner's Project Manager to do so. The Owner and the Owner's Project Manager shall review the costs and time submitted by the Contractor on the basis of reasonable expenditures and savings of those performing the Change in the Work. If such costs and time are acceptable to the Owner and the Owner's Project Manager, or if the parties otherwise agree to the actual reasonable cost to perform the Change in the Work, the Owner's Project Manager shall issue a Change Order for the cost and time agreed upon. The amounts stated in the Change Order for the cost and time to perform the Change in the Work shall be binding upon the parties.
- 12.5.10** The Contractor shall be entitled to costs as provided for in Article 12.4 which the Contractor, or his Subcontractors, may incur as a result of delays, interferences, suspensions, changes in sequence or the like, which are unreasonable, arising from the performance of any and all changes in the Work, caused by acts or omissions of the Owner, performed pursuant to this Article 12.
- 12.5.11** If any dispute should arise between the parties with respect to an increase or decrease in the Contract Price or an extension or reduction in the Contract Time or as a result of a Change in the Work, the Contractor shall not suspend performance of a Change in the Work or the Work itself unless otherwise so ordered by the Owner's Project Manager in writing. Disputes must be resolved

pursuant to Article 7.4 of the Contract. The Owner will, however, pay the Contractor up to the Owner's Project Manager's estimated value of the Change in the Work, regardless of the dispute, if the Change in the Work results in an increase in the Contract Price; and the Owner will have the right to decrease the Contract Price up to the Owner's Project Manager's estimated value of the Change in the Work, regardless of the dispute, if the Change in the Work results in a decrease in the Contract Price.

12.6 UNILATERAL CHANGE ORDER

12.6.1 In the event that the parties are unable to agree as to the reasonable cost and time to perform the Change in the Work and the Owner does not elect to have the Change in the Work performed on a time and material basis, the Owner and the Owner's Project Manager shall make a unilateral determination of the reasonable cost and time to perform the Change in the Work, based upon their own estimates, the Contractor's submission or a combination thereof. A Change Order shall be issued for the amounts of cost and time determined by the Owner and the Owner's Project Manager and shall become binding upon the Contractor unless the Contractor submits his protest in writing to the Owner within ten days of the issuance of the Change Order. The procedure for the resolution of the Contractor's protest shall be as described in Article 12.10. The Owner has the right to direct in writing the Contractor to perform the Change in the Work, which is the subject of such Unilateral Change Order. Failure of the parties to reach an agreement regarding the cost and time of performing the Change in the Work, or any pending protest, shall not relieve the Contractor from performing the Change in the Work promptly and expeditiously.

12.7 DECREASES AND WORK NOT PERFORMED

12.7.1 Should it be deemed expedient by the Owner or the Owner's Project Manager at any time that the Contract Work is in progress to decrease the dimensions, quantity of material or work, or vary in any other way the Work herein contracted for, the Owner or the Owner's Project Manager shall have the full power to do so, and shall order, in writing, such decreases to be made or performed without affecting the enforcement of the Contract. The Contractor shall, in pursuance of such written orders and directions from the Owner or the Owner's Project Manager, execute the work ordered, and the difference in expense occasioned by such decrease so ordered shall be deducted from the amount payable under this Contract.

12.7.2 If Work is not performed, and such deletion of Work is not approved by the Owner, the Owner's Project Manager shall ascertain the amount of the credit due the Owner, based on the reasonable value of the labor and materials so deleted, for the lesser amount of materials and labor required.

12.7.3 If Work is deleted from the Contract by Change Order, the amounts to be credited to the Owner shall reflect the same current pricing as if the Work were being added to the Contract at the time the deletion is ordered, and documentation will be required for a credit as specified in Article 12.4. If such deleted materials and equipment shall have already been purchased and stored on site and cannot be used in other projects or returned for credit or cannot be returned for credit at the price paid by the Contractor at the time of purchase, the Contractor shall be entitled, upon proper documentation and certification, to an adjustment in the pricing of the credit to avoid hardship to the Contractor. If necessary in order to establish such reasonable value, the Contractor may be required to submit a detailed breakdown of his original bid for the items or Work involved.

12.8 CHANGES IN LINE AND GRADE

12.8.1 The Owner reserves the right through the Owner's Project Manager to make such alterations in the line and grade of various structures or pipelines shown on the drawings, as may be necessitated by conditions found during construction or that in the judgment of the Owner's Project Manager appears advisable. The Contractor shall not claim forfeiture of Contract by reason of such changes by the Owner's Project Manager.

12.8.2 In case of a fixed price contract, the price of the Work shall be negotiated as herein provided. If such alterations or changes diminish the quantity of Work to be done, they shall not constitute a claim for damages or for loss of anticipated profits in the Work which may be dispensed with, and the Work as constructed shall be paid for in accordance with the Contract prices as established for such Work under this Contract. In the case of a unit price, or partial unit price, contract, the altered Work shall be performed at the appropriate unit price.

12.8.3 The Contractor shall employ a certified Land Surveyor to establish a base line and set bench marks for the Contractor's use as necessary to stake the basic layout of the Work. Where new construction connects to existing facilities, it shall be the responsibility of the Contractor to check and establish the location of all existing facilities prior to construction of the new facilities.

12.8.4 All stakes, bench marks, and other base line information provided by the Owner or the Owner's Project Manager shall be carefully preserved by the Contractor, and in case of their removal by any cause without prior written consent from the Owner, such stakes, bench marks, and other base line information will be replaced by the Contractor at the Contractor's sole expense.

12.8.5 The dimensions for lines and elevations for grades of the structures, appurtenances, and utilities are indicated on the Drawings, together with pertinent information required for laying out the Work. Utility locations are approximate and it shall be the Contractor's responsibility to determine the exact location of

the utilities prior to commencing Work in all areas where conflicts with utility installations are possible. If site conditions vary from those indicated, the Contractor shall notify the Owner immediately, who will promptly direct any adjustment as required. The locations of existing utilities, including underground utilities, which may affect the Work, are indicated on the drawings or in the specifications insofar as their existence and location were known at the time of preparation of the drawings. However, nothing in these drawings or specifications shall be construed as a guarantee that such utilities are in the location indicated or that they actually exist, or that other utilities are not within the area of the operations. The Contractor shall make all necessary investigations to determine the existence and locations of such utilities. The Contractor will be held responsible for any damage to and maintenance and protection of existing utilities and structures, of both public and private ownership. Acceptability of restored utility installation shall be determined by the respective utility Owner. All utilities shall remain in service during the construction of this project unless written authorization of interruption of service is received from the respective utility Owner and the interruption is approved by the Project Manager.

12.8.6 Contractor shall notify the Owner immediately upon discovery of any apparent errors in the lines or grades. If Contractor proceeds with knowledge of such apparent error without first receiving written clarification from the Owner's Project Manager, the Contractor does so at his own risk.

12.9 DIFFERING SITE CONDITIONS

12.9.1 The Contractor shall promptly, and before the conditions are disturbed, give written notice to the Owner's Project Manager of (a) subsurface or latent physical conditions at the site which differ materially from those indicated in the Contract Documents, or (b) unknown physical conditions at the site, of an unusual nature, which differ materially from those ordinarily encountered and generally recognized as inhering in work of the character provided for in the Contract and which were not reasonably anticipated as a result of the investigation required by Article 1.2.2.

12.9.2 The Owner's Project Manager shall investigate the site conditions promptly after receiving the notice. If the conditions do materially so differ and cause an increase or decrease in the cost or time of performance, the provisions of Article 12 "Changes in the Work" shall apply.

12.9.3 No request by the Contractor for a Change Order under this Article shall be allowed, unless the Contractor has given the required written notice.

12.9.4 No request by the Contractor for a Change Order under this Article shall be allowed if made after final payment under the Contract.

12.10 CLAIMS FOR ADDITIONAL COST AND/OR TIME

12.10.1 If the Contractor wishes to make a claim for an increase in the Contract Price and/or Contract Time, he shall give the Owner written notice thereof within seven calendar days after the occurrence of the event giving rise to such claim. This notice shall be given by the Contractor before proceeding to execute the Work, except in an emergency endangering life or property in which case the Contractor shall proceed as provided in Article 10. No claim shall be allowed and no amounts shall be paid for any costs incurred more than ten calendar days prior to the time notice is given to the Owner. Any change in the Contract Price or Contract Time resulting from such claim must be authorized by Change Order. The Contractor's complete claim submittal for an increase in the Contract Price shall be submitted no later than twenty calendar days after the Work for which the claim is made has been completed or after the request of the Owner or the Owner's Project Manager, whichever is earlier.

12.10.2 If the Contractor claims that additional cost or time is involved because of, but not limited to, any of the following circumstances, the Contractor shall make such claim as provided in Subparagraph 12.10.1: (1) any written interpretation pursuant to Article 2, (2) any order by the Owner to stop the Work pursuant to Article 3.3 where the Contractor was not at fault, (3) failure of payment by the Owner pursuant to Article 9, or (4) any written order for a minor change in the Work issued pursuant to Article 12.8.1.

12.11 ATTORNEYS' FEES AND OTHER EXPENSES

12.11.1 In recognition of the public monies being administered by the Owner to fund this Contract, the Contractor agrees that he will not submit, assert, litigate or otherwise pursue any frivolous or unsubstantiated delay claims. If the Contractor's delay claim, or any separate item of a delay claim, is determined through litigation or other dispute resolution process to be false or to have no basis in law or fact, the Contractor shall be liable to the Owner and shall pay it for all Investigation Costs incurred by the Owner. These costs include investigating, analyzing, negotiating, appealing, defending, and litigating the false or baseless delay claims, attorneys' fees, audit costs, accountants' fees, expert witness' fees, additional architect/engineer expenses and any other consultant costs. The amount to be paid hereunder to the Owner shall be the percentage of the Owner's total Investigation Costs in an amount equal to the percentage of the Contractor's total delay claim which is determined to be false or to have no basis in fact.

12.11.2 If the Contractor breaches any obligation under the Contract Documents, the Contractor shall reimburse the Owner for all costs and expenses incurred by the Owner relating to such breach, including but not limited to, attorneys' fees, audit

costs, accountants' fees, expert witness' fees, additional architectural or engineering expenses, and any other consultant costs.

- 12.11.3** If the Owner prevails in a claim brought against the Contractor, including but not limited to, claims for fraud or misrepresentation, overpayment, defective work, delay damages, and recovery of termination expenses, the Contractor shall reimburse the Owner for all costs and expenses incurred by the Owner relating to such claim, including but not limited to, attorneys' fees, audit costs, accountants' fees, expert witness' fees, additional architect or engineering expenses, and any other consultant costs.

END OF ARTICLE 12

ARTICLE 13: UNCOVERING AND CORRECTION OF WORK

13.1 UNCOVERING OF WORK

13.1.1 If any portion of the Work should be covered contrary to the request of the Owner's Project Manager or to requirements specifically expressed in the Contract Documents or to requirements of applicable Construction Permits, it must, if required in writing by the Owner's Project Manager, be uncovered for its observation and shall be replaced at the Contractor's expense.

13.1.2 If any portion of the Work has been covered that the Owner's Project Manager has not specifically requested to observe prior to being covered, the Owner's Project Manager may request to see such Work and it shall be uncovered by the Contractor. If such Work complies with the Contract Documents, the cost of uncovering and replacement shall, by appropriate Change Order, be charged to the Owner. If such Work does not comply with the Contract Documents, the Contractor shall pay such costs unless the Owner caused this condition, in which event the Owner shall pay such costs.

13.2 CORRECTION OF WORK

13.2.1 The Contractor shall promptly reconstruct, replace or correct all Work rejected by the Owner's Project Manager as defective or as failing to conform to the Contract Documents or as not in accordance with the guarantees and warranties specified in the Contract Documents whether observed before or after Substantial Completion and whether or not fabricated, installed or completed. The Contractor shall bear all costs of correcting such rejected Work, including compensation for the Owner's Project Manager and any other additional services made necessary thereby.

13.2.2 The Contractor, unless removal is waived by the Owner, shall remove from the site all portions of the Work that are defective or non-conforming, or if permitted or required, he shall correct such Work in place at his own expense promptly after receipt of notice, and such rejected Work shall not thereafter be tendered for acceptance unless the former rejection or requirement for correction is disclosed.

13.2.3 If the Contractor does not proceed with the correction of such defective or non-conforming Work within a reasonable time fixed by written notice from the Owner's Project Manager, the Owner may either:

- .1 By separate contract or otherwise replace or correct such Work and charge the Contractor the cost occasioned the Owner thereby and remove and store the materials or equipment at the expense of the Contractor; or

.2 Terminate this Contract as provided in Article 14.3 "DEFAULT TERMINATION."

13.2.4 The Contractor shall bear the cost of making good all work of the Owner or separate Contractors destroyed or damaged by such correction or removal.

13.2.5 Nothing contained in this Article 13.2 shall be construed to establish a period of limitation with respect to any other obligation that the Contractor might have under the Contract Documents, including Article 4.7 "WARRANTY" hereof. The establishment of the period of one year after the Date of Final Completion or such longer period of time as may be prescribed by law or by the terms of any warranty required by the Contract Documents relates only to the specific obligation of the Contractor to correct the Work, and has no relationship to the time within which his obligation to comply with the Contract Documents may be sought to be enforced, or to the time within which proceedings may be commenced to establish the Contractor's liability with respect to his obligations other than specifically to correct the Work.

13.3 ACCEPTANCE OF DEFECTIVE OR NON-CONFORMING WORK

13.3.1 If the Owner or its Project Manager prefers to accept defective or non-conforming Work, it may do so instead of requiring its removal and correction. In this case, a Change Order will be issued to reflect a reduction in the Contract Price where appropriate and equitable, or the Owner may elect to accept payment in materials or services, in lieu of a reduction in the Contract Price. If the amount of a reduction is determined after Final Payment, it shall be paid on demand to the Owner by the Contractor.

END OF ARTICLE 13

ARTICLE 14: TERMINATION OF THE CONTRACT

14.1 TERMINATION FOR THE CONVENIENCE OF THE OWNER

14.1.1 The Owner may, at any time upon ten days written notice to the Contractor, terminate, without prejudice to any right or remedy of the Owner, the whole or any portion of the Work for the convenience of the Owner. This Notice of Termination shall specify that portion of the Work to be terminated and the effective date of termination. The Contractor's sole remedy, in the event of such termination, will be the allowable termination costs permitted by Article 14.2 "ALLOWABLE CONVENIENCE TERMINATION COSTS."

14.1.2 The Contractor shall include termination clauses identical to Article 14 in all subcontracts and purchase orders related to the Work. Failure to include these termination clauses in any subcontracts or purchase orders shall preclude recovery of any termination costs related to that subcontract or purchase order.

14.1.3 Non-appropriation Clause

Notwithstanding anything contained herein to the contrary, this contract shall be terminated if all of the following events shall have occurred:

1. Funds are not appropriated for a subsequent fiscal period during the term of this contract for the acquisition of substantially the same functions as provided for herein, and written notice thereof is given to CONTRACTOR at least thirty (30) days prior to the first day of such subsequent fiscal periods or within five (5) days of the approval of the final budget for such fiscal year, whichever occurs later.
2. Town has exhausted all funds legally available for payment under this contract.

Upon such termination, Contractor's only remedy shall be to terminate the contract at the end of the fiscal period during which notice is given. Payment in compliance with the contract for materials, goods, and services rendered hereunder during the fiscal year at the end of which termination occurs, without penalty, termination, profit or overhead expenses of any kind shall constitute full performance on the part of the Town.

14.2 ALLOWABLE CONVENIENCE TERMINATION COSTS

14.2.1 After complying with the provisions of Article 14.4, the Contractor may submit a termination claim, not later than six months after the effective date of its

termination, unless one or more extensions of three months each are granted by the Owner in response to the Contractor's written request.

14.2.2 The Owner shall pay the Contractor's reasonable costs of termination, plus a mark-up of ten percent for profit and overhead. This amount will not exceed the original contract price, reduced by any payments made prior to Notice of Termination, and further reduced by the price of the supplies not delivered, or the service not provided. This Contract shall be amended accordingly, and the Contractor shall be paid the agreed amount.

14.2.3 If the parties cannot agree on the amount to be paid to the Contractor by reason of termination under this clause, the Owner shall pay to the Contractor the amounts, as determined by the Owner's Project Manager as follows, without duplicating any amounts which may have already been paid under the preceding paragraph of this clause:

.1 With respect to all Contract performance prior to the effective date of Notice of Termination, the total of:

- a. cost of work performed or supplies delivered;
- b. the costs of settling and paying any reasonable claims as provided in Article 14.4; and
- c. a mark-up of ten percent for profit and overhead. Neither the Contractor nor any Subcontractor shall be entitled to profit or overhead associated with the portion of the work not performed, nor to profit associated with costs of demobilization.

.2 The total sum to be paid under .1 above shall not exceed the contract price, as reduced by the amount of payments otherwise made, and as further reduced by the contract price of work not done or supplies not delivered. The Owner may subtract from the amount claimed by the Contractor any claim the Owner has against the Contractor

14.2.4 If the Contractor is not satisfied with any payments that the Owner's Project Manager shall determine to be due under this clause, the Contractor may proceed in accordance with Article 7.4 "DISPUTES."

14.2.5 If the Contractor would have sustained a loss on the entire Contract had it been completed, no profit shall be included or allowed and an appropriate adjustment shall be made reducing the amount of the settlement to reflect the indicated rate of loss.

14.3 DEFAULT TERMINATION

14.3.1 The Owner may, upon ten days written notice to the Contractor, terminate, without prejudice to any right or remedy of the Owner, the Contract for default, in whole or in part, and may take possession of the Work and complete the Work by contract or otherwise in any of the following circumstances:

- .1 The Contractor refuses or fails to prosecute the Work or any separable part thereof with such diligence as will ensure the Substantial Completion of the Work within the Contract Time, or fails to meet any milestones established in the Contract Documents or fails to substantially complete the Work within this period;
- .2 The Contractor is in default in carrying out any provision of the Contract for a cause within his or his Subcontractors' control;
- .3 The Contractor fails to supply a sufficient number of properly skilled workers or proper equipment or materials;
- .4 The Contractor fails to make prompt payment to Subcontractors or for materials or labor;
- .5 The Contractor disregards laws, permits, ordinances, rules, regulations, or orders of any public authority having jurisdiction;
- .6 The Contractor breaches any provision of the Contract Documents;
- .7 The Contractor voluntarily abandons the Project;
- .8 Upon at least thirty calendar days prior written notice by the Owner to the Contractor, at any time during the term of the Agreement, the Owner determines that maintaining the Agreement in force will harm, bring into disrepute, or affect the integrity of the Owner.

14.3.2 Upon termination of this Agreement under this Article, the Contractor shall remove all of his employees and property from the Project in a smooth, orderly, and cooperative manner.

14.3.3 The right of the Contractor to proceed shall not be terminated under Article 14.2 because of any delays in the completion of the Work due to unforeseeable causes beyond the control and without the fault or negligence of the Contractor or his Subcontractors as specifically set forth in Article 8, "DELAYS AND EXTENSIONS OF TIME."

14.3.4 If, after the Contractor has been terminated for default pursuant to Article 14.3, it is determined that none of the circumstances set forth in Article 14.3.1 exist, then such termination shall be considered a termination for convenience pursuant to Article 14.1. In such case, the Contractor's sole remedy will be costs permitted by Article 14.2.

14.3.5 If the Owner terminates the Contract, the Contractor shall not be entitled to receive any further payment until the Work is finished. If the unpaid balance of the Contract Price exceeds the cost of completing the Work including compensation for additional managerial, administrative and inspection services and any damages for delay, such excess amount shall be paid to the Contractor. If such expenses exceed the unpaid balance, the Contractor and his sureties shall be liable to the Owner for such excess amount.

14.3.6 If the right of the Contractor to proceed with the Work is partially or fully terminated, the Owner may take possession of and utilize in completing the Work such materials, appliances, supplies, plant and equipment as may be on the site of the terminated portion of the Work and necessary for the completion of the Work. If the Owner does not fully terminate the right of the Contractor to proceed, the Contractor shall continue to perform the part of the Work that is not terminated.

14.4 GENERAL TERMINATION PROVISIONS

14.4.1 After receipt of a Notice of Termination from the Owner, pursuant to Article 14.1 or 14.3, and except as otherwise directed by the Owner, the Contractor shall:

- .1 Stop Work under the Contract on the date and to the extent specified in the Notice of Termination;
- .2 Place no further purchase orders or subcontracts for materials, services, or facilities, except as may be necessary for completion of such portion of the Work under the Contract that is not terminated;
- .3 Terminate all purchase orders and subcontracts to the extent that they relate to the performance of Work terminated by the Notice of Termination;
- .4 At the option of the Owner, assign to the Owner in the manner, at the times and to the extent directed by the Owner, all of the rights in the contracts so terminated, in which case, the Owner shall have the right, at his discretion, to settle or pay any or all claims arising out of the termination of such purchase orders and subcontracts;
- .5 Settle all outstanding liabilities and all claims arising out of such termination of purchase orders and subcontracts, with the approval

or ratification of the Owner, to the extent he may require, which approval or ratification shall be final for all the purposes of this Article;

- .6 Transfer title and deliver to the entity or entities designated by the Owner, in the manner, at the times and to the extent directed by the Owner to the extent specifically produced or specifically acquired by the Contractor for the performance of such portion of the Work as has been terminated, the following:
 - a. The fabricated or unfabricated parts, Work in progress, partially completed supplies and equipment, materials, parts, tools, dies, jigs, and other fixtures, completed work, supplies and other material produced as part of, or acquired in connection with the performance of, the Work terminated by the Notice of Termination; and
 - b. The completed or partially completed plans, drawings, Shop Drawings, submittals, information, releases, manuals, and other property related to the Work and which, if the Contract had been completed, would have been required to be furnished to the Owner.
- .7 Use his best efforts to sell, in the manner, at the times, to the extent and at the price or prices directed or authorized by the Owner or Owner's Project Manager, any property of the types referred to in Article 14.4.1.6; provided, however, that the Contractor:
 - a. Shall not be required to extend credit to any buyer; and
 - b. May acquire such property under the conditions prescribed by and at a price or prices approved by the Owner; and provided further that the proceeds of any such transfer or disposition shall be applied in reduction of any payments to be made by the Owner to the Contractor under the Contract or shall otherwise be credited to the Contract Price covered by the Contract or paid in such other manner as the Owner may direct;
- .8 Complete performance of such part of the Work as shall not have been terminated by the Notice of Termination; and
- .9 Take such action as may be necessary, or as the Owner or Owner's Project Manager may direct for the protection and preservation of

the property related to the Contract that is in the possession of the Contractor and in which the Owner has or may acquire an interest.

14.4.2 If the convenience termination, pursuant to Article 14.1, is partial, the Contractor may file with the Owner a claim for an equitable adjustment of the Contract Price relating to the continued portion of the Contract (the portion not terminated by the Notice of Termination) for costs increased because of such partial termination. Such equitable adjustment as may be agreed upon shall be made in the Contract Price. Any claim by the Contractor for an equitable adjustment under this Article must be submitted in writing to the Owner's Project Manager within sixty days from the Notice of Termination.

14.4.3 The Contractor shall refund to the Owner any amounts paid by the Owner to the Contractor in excess of costs reimbursed under Article 14.4 within sixty days of receipt of a written request from the Owner to do so.

END OF ARTICLE 14