

### Edwards Ferry Road Sidewalk Project July 7, 2021 at 7 PM

We will be starting soon.

You were muted as you entered.

The attendee list will NOT be visible to other attendees.

Text or call (571) 919-1646 for help w/ technical issues or email croe@leesburgva.gov





#### Edwards Ferry Road Sidewalk Project

#### Anne Geiger, Town of Leesburg

Public Information Meeting July 7, 2021





#### Meeting Topics

- Project Description
- Project History & Goals
- Utility Relocations
- Design Presentation
- ▶ What to Expect During Construction
- Next Steps
- Comments and Questions





# Project: Upgrade sidewalk from 600 ft. west of Woodberry Rd. to Prince St.









#### Project History

- 2015: Study prepared to establish project budget for CIP
- ▶ 2018: Project added to the Town CIP for construction in 2023
- ▶ 2019: Drainage issues of south side of road discussed, and funding added to project to address.
- 2020: Project accelerated forward for construction in 2021





#### Project Goals:

- Provide vertical separation between cars and sidewalk, and ADA standard sidewalk on north side
- Address storm drainage flow from the right-of-way on the south side

#### Project includes:

- New curb, gutter, brick sidewalk and upgraded drainage system on north side
- Limited curb & gutter on south side






#### Utility Relocations Needed

- Utility conflicts
  - No above ground conflicts
  - Below ground conflicts include:
    - Watermain relocation
    - Washington Gas 6" gas line in road + services
    - FIOS & Comcast services









Edwards Ferry Road NE Sidewalk July 7, 2021














































Edwards Ferry Road NE Sidewalk July 7, 2021





## What to Expect During Construction

- Road will remain open during construction with flaggers
  - Working hours 9am-3:30pm.
- Construction of driveway aprons will be staggered
- Driveways will use high-early strength concrete
- ▶ 48 hrs. notice for all interruptions





#### Next Steps


- **▶** Summer 2021:
  - Land & Easement Acquisition
  - Utility Relocations
- ► Fall 2021: Project put out for bid
- Spring 2022: Construction, taking about 9 months.






#### Questions?

#### Raise your Hand:





open Q&A Pane

- Anne Geiger
  - 703-771-2742
  - ageiger@leesburgva.gov
- Sarah Biggs
  - 703-771-6671
  - sbiggs@leesburgva.gov
- www.leesburgva.gov/EdwardsFerry

